Table 1.4 - Portfolio Measure Grouping Gross and NET

Measure Summary Categories	Unit Description (1*)	Unit Goals	Total Gross Therms	Total Net Therms	% Portfolio Therms	Weighted Avg NTG Ratio	Weighted Avg EUL
Residential							
Appliances							
516008-Energy Star Dishwasher EF=.65	*Dishwasher*	10,455	40,775	40,775	0%	**100%**	**11.00**
517003-Energy Star Labeled Dishwasher EF=0.65	*Dishwasher*	190,650	1,010,445	1,010,445	1%	**100%**	**11.00**
517005-Energy Star Clothes Washer - MEF=1.80	*Clothes Washer*	140,220	4,346,273	4,346,273	5%	**100%**	**11.00**
HVAC							
516004-Attic Insulation	*SQFT*	125,460	5,676	5,676	0%	**100%**	**20.00**
517001-Attic Insulation	*sqft*	18,696,000	585,786	585,786	1%	**100%**	**20.00**
517002-Wall Insulation	*sqft*	5,412,000	537,280	537,280	1%	**100%**	**20.00**
517004-Central Gas Furnace 92% AFUE	*Per KBTU*	559,650	241,777	241,777	0%	**100%**	**20.00**
LIEE	*UNIT*	9,202,958	9,202,958	9,202,958	10%	**100%**	**15.00**
Res NC							
515001-Whole Building Gas	*Home*	530,130	530,130	530,130	1%	**100%**	**20.00**
Water Heating							
516005-Central System Natural Gas Water Heater	*Unit*	1,722	442,554	442,554	0%	**100%**	**13.00**
516006-Central System Gas Boiler: Water Heating Only	*Unit*	560	419,738	419,738	0%	**100%**	**15.00**
516007-Gas Wtr Htr Controller Small Complex	*Unit*	771	655,529	655,529	1%	**100%**	**10.00**
516010-Gas Wtr Htr Controller Large Complex	*Unit*	1,433	2,434,582	2,434,582	3%	**100%**	**10.00**
516009-Tankless Water Heater	*Tank, WtrHtr*	2,214	66,940	66,940	0%	**100%**	**20.00**
516001-Gas Storage Water Heater (EF>= 0.62)	*Hot Water Tank*	12,915	251,946	251,946	0%	**100%**	**13.00**
516002-Faucet Aerators/Self Install - kits	*Household*	135,300	366,555	366,555	0%	**100%**	**10.00**
516003-Low Flow Showerhead/Self Install	*Showerhead*	184,500	1,092,240	1,092,240	1%	**100%**	**10.00**
512004-Pipe Wrap	*Household*	11,070	89,257	89,257	0%	**100%**	**11.00**
Subtotal							
Commercial							
Process							
511001-Water Heating -Commercial Pool Heater	*Mbtuh*	232,470	560,253	560,253	1%	**100%**	**5.00**
511002-Pipe Insulation - Medium pressure steam >15 psi >	*LinearFt*	161,130	10,151,190	10,151,190	11%	**100%**	**20.00**
511003-High Efficiency Small Gas Storage Water Heater - 5	*MBTU*	18,450	9,539	9,539	0%	**100%**	**11.00**
511004-High Efficiency Large Gas Storage Water Heater - (	*MBTU*	101,475	304,401	304,401	0%	**100%**	**11.00**
510001-Steam Traps	*Therm*	3,703,530	3,703,530	3,703,530	4%	**100%**	**6.00**
New Construction							
514001-Whole Building (per Therm)	*Therm*	1,359,150	1,359,150	1,359,150	1%	**100%**	**20.00**

Table 1.4 - Portfolio Measure Grouping Gross and NET

Measure Summary Categories	Unit Description (1*)	Unit Goals	Total Gross Therms	Total Net Therms	% Portfolio Therms	Weighted Avg NTG Ratio	Weighted Avg EUL
Industrial							
Process							
513001-Tank Insulation - High Temperature Applic. (LF) 2 ir	*SquareFT*	223,961	2,329,193	2,329,193	2%	**100%**	**20.00**
513002-Pipe Insulation - Low Pressure Steam Applic. (LF) 1	*LinearFt*	49,200	659,280	659,280	1%	**100%**	**20.00**
513003-EER Convection Oven	*Unit*	1,691	546,274	546,274	1%	**100%**	**12.00**
513004-EER Fryer - High Effic. Unit	*Unit*	1,033	521,766	521,766	1%	**100%**	**12.00**
513005-EER Cabinet Steamer Tier II	*MBTU*	291,510	2,527,392	2,527,392	3%	**100%**	**12.00**
512005-Process Optimization	*Therm*	461,250	461,250	461,250	0%	**100%**	**20.00**
512006-Boiler Replacement	*Therm*	461,250	461,250	461,250	0%	**100%**	**20.00**
512007-Nonresidential Equipment Modernization/Upgrades	*Therm*	738,000	738,000	738,000	1%	**100%**	**20.00**
512001-CPI Heat Recovery	*Therm*	7,783,500	7,783,500	7,783,500	8%	**100%**	**20.00**
512002-PER Misc. Process Equip. and Replacement Equip	*Therm*	10,035,447	10,035,447	10,035,447	11%	**100%**	**20.00**
512003-CPI Equip. Modernization	*Therm*	13,857,950	13,857,950	13,857,950	15%	**100%**	**20.00**
Agricultural							
Process							
508001-PER Boiler Replacement	*Therm*	1,937,987	1,937,987	1,937,987	2%	**100%**	**20.00**
508002-Burners and burner related equipment (IEU)	*Therm*	3,649,533	3,649,533	3,649,533	4%	**100%**	**20.00**
508003-Equipment repair/upgrades (IEU)	*Therm*	999,990	999,990	999,990	1%	**100%**	**3.00**
Misc.							
509002-Greenhouse Heat Curtain	*Sqft*	15,350,400	2,931,926	2,931,926	3%	**100%**	**5.00**
509001-Infrared Film for Greenhouses	*Sqft*	14,145,000	1,810,560	1,810,560	2%	**100%**	**5.00**
Subtotal							
C&S							
Codes & Standards	*UNIT*	4,116,040	4,116,040	4,116,040	4%	**100%**	**10.00**
Total			**93,775,840**	**93,775,840**	100%		