

SoCalGas’s Open System Hydrogen Blending Project
Workpaper Supporting the Direct Testimony of Blaine Waymire Chapter 2
Joint Amended IOU Hydrogen Blending Demonstration Application
(A.22-09-006)

Explanation of Work Paper

This work paper (WP-2) includes all Level 5 cost estimates to support SoCalGas’s proposed Open System Hydrogen Blending Demonstration Project (Open System Project) sited in the City of Orange Cove, California. For information on the associated revenue requirement and rate impact, see the Direct Testimony of Nasim Ahmed and Marjorie Schmidt-Pines (Chapter 6).

Table 1 summarizes the O&M costs related to the Open System Project. Tables 2 to 5 reflect the costs by project phase, as described in the Direct Testimony of Blaine Waymire (Chapter 2). Detailed cost estimates and assumptions to support the work paper are provided in WP-2 Appendix A.

Table 1: Project Cost Estimates (O&M)

2025	2026	2027	2028	Total
\$34,366,986	\$11,709,582	\$966,419	\$1,371,045	\$48,411,032

Cost Mechanism Justification

The Open System Project is a demonstration project that was designed to be in accordance with D.22-12-057 and D.21-07-005. Once the Open System Project is planned, designed, constructed, and commissioned, SoCalGas will test various hydrogen blends in the City of Orange Cove over the course of approximately 18 months. After the testing, there are various options for decommissioning and equipment removal, however, cost estimates in this workpaper make a conservative assumption of full decommissioning and equipment removal. For the purposes of Cost Mechanism, the demonstration nature of the project planned for the Open System Project is different than most utility activities and closer to a research, development, and demonstration (RD&D) project than a typical capital project. For this reason, all of the equipment costs and related direct labor are being treated as O&M.

Project Description

The Open System Project has been designed to blend hydrogen into an open portion of a medium-pressure natural gas distribution pipeline system that will ultimately serve the City of Orange Cove. The equipment is slated to be located in an empty plot of land at the southwest corner of Jacobs Avenue and South Avenue, situated diagonally across the intersection from SoCalGas’s regulator station in Orange Cove, California. No modification will be made to the existing pipeline system for isolation, with the exception of one short gas pipeline that will direct natural gas coming into the community to the hydrogen blending equipment. All hydrogen-related equipment will be procured and deployed onsite. The Open System Project will begin by observing 100% natural gas in the pipeline system. Once a baseline is established, SoCalGas plans to

SoCalGas’s Open System Hydrogen Blending Project

Workpaper Supporting the Direct Testimony of Blaine Waymire Chapter 2

Joint Amended IOU Hydrogen Blending Demonstration Application
(A.22-09-006)

blend and inject electrolytic hydrogen produced onsite into the system, starting at 0.1% hydrogen by volume and up to 5% by volume over time. The blend volume will be gradually increased based on safety and technical feasibility validated with testing throughout the project, including evaluating key impacts on pipes, meters, and end-use equipment. Upon conclusion of the estimated 18-month testing period, SoCalGas will move forward with decommissioning specifics that will be outlined in an agreement between SoCalGas and the City of Orange Cove, which may include leaving equipment in place for future hydrogen blending. A final report will be prepared and publicly disseminated to share the results and findings of the demonstration.

Project Plan

Table 2. Summary of Project Phases

Phase & Activity	Description	Estimated Duration
0. Pre-development	All efforts supporting this Amended Application submittal are considered “Pre-development.” Upon Commission approval, the project will move on to subsequent phases	Pre-application submittal
1. Design, Construction, and Commissioning	Hydrogen production and blending equipment is designed; detailed safety and feasibility analyses are performed. Stakeholder engagement will be conducted throughout the project’s lifespan. Following design and feasibility, equipment is procured, constructed, and commissioned; pre-demo equipment and pipeline system inspections and any necessary remediation are conducted	18 months
2. Demonstration and Data Collection	Hydrogen is blended in system on a data analysis schedule; data is collected; periodic inspection of equipment and pipelines; test pipelines and components pre-, during, and post-hydrogen blend exposure	24 months (18 months live blending and 6 months asset inspection and validation)
3. Decommissioning, Equipment Removal, and System Restoration	Potential removal of hydrogen equipment	6 months
4. Data Analysis and Dissemination	Data from pilot is analyzed and a public report will be released	9 months

SoCalGas’s Open System Hydrogen Blending Project
Workpaper Supporting the Direct Testimony of Blaine Waymire Chapter 2
 Joint Amended IOU Hydrogen Blending Demonstration Application
 (A.22-09-006)

Forecast Methodology (Construction Costs and Labor)

SoCalGas’s methodology for forecasting costs is discussed in Chapter 2 testimony. SoCalGas used a Level 5 Estimate for Total Installed Cost (TIC) estimate to implement the scope of work in Phases 1 and 3. The TIC estimate includes direct costs associated with project management, engineering and design, environmental permitting, material and equipment procurement, and construction. For programmatic, operational, and data collection-related expenses in Phases 2 and 4, the forecast method developed for this cost category is zero-based. This method is most appropriate because RD&D needs and activities will evolve with the project, and this is a new type of project with new technologies.

During cost estimate preparation, this project was in the preliminary design stage. Further development of this project could reveal new information requiring some adjustments to the project plan in areas such as engineering, materials, permitting, environmental and land, staffing, and customer engagement, all of which could impact actual costs compared to this cost estimate. An average 30% contingency has been utilized.

Schedule

Implementation of the Open System Project is proposed to be completed consistent with the overall prioritization and timing described in Chapter 2 testimony. The critical project deliverables were identified and incorporated into a work breakdown structure and durations were determined for each project phase.

PHASE 1 COSTS

Table 3: Phase 1 (O&M)					
Phase 1	2025	2026	2027	2028	Total
Total	\$34,366,986	\$11,455,662	0	0	\$45,822,648

Phase 1 Assumptions

Refer to WP-2 Appendix A for a detailed list of assumptions used to develop Phase 1 estimates.

PHASE 2 COSTS

Table 4: Phase 2 (O&M)					
Phase 2	2025	2026	2027	2028	Total
Total	0	\$253,920	\$317,400	0	\$571,320

SoCalGas’s Open System Hydrogen Blending Project
Workpaper Supporting the Direct Testimony of Blaine Waymire Chapter 2
 Joint Amended IOU Hydrogen Blending Demonstration Application
 (A.22-09-006)

Phase 2 Assumptions

The following assumptions were made to develop this cost estimate:

- Level 5 Estimate (- 50% / +100%);
- Monthly odorant sampling and analysis;
- Quarterly leak surveys and leak detection equipment evaluation;
- As needed equipment checks;
- Regular maintenance of major equipment (blending skid and electrolyzer);
- Program management; and
- 10% contingency built into hourly rate.

PHASE 3 COSTS

Table 4: Phase 3 (O&M)					
Phase 3	2025	2026	2027	2028	Total
Total	0	0	\$649,019	\$1,298,037	\$1,947,056

Phase 3 Assumptions

Refer to WP-2 Appendix A for a detailed list of assumptions to develop Phase 3 estimates.

PHASE 4 COSTS

Table 5: Phase 4 (O&M)					
Phase 4	2025	2026	2027	2028	Total
Total	0	0	0	\$73,008	\$73,008

Phase 4 Assumptions

The following assumptions were made to develop this cost estimate:

- Level 5 Estimate (- 50% / +100%)
- An engineering and data team of 1, working 8 hours per week for 39 weeks
- A management team of 3, each employee working 2 hours per week for 39 weeks
- 30% contingency in alignment with Level 5 estimates is included

Phase 1:

**Orange Cove H2 Blending Estimate Phase 1
PROJECT SUMMARY**

Summary Description	Bare Total	Contingency	Total Cost	Basis
Mechanical Contractor	\$ 7,530,309	30%	\$ 2,259,093	\$ 9,789,402 See "Digs - Capital" Tab
Electrical Contractor	\$ 7,427,352	30%	\$ 2,228,206	\$ 9,655,558 See "Elect - Capital" Tab
Material- Pipe	\$ 148,876	30%	\$ 44,663	\$ 193,539 See "Digs - Capital" Tab
Material-Valves & Fittings	\$ 260,375	30%	\$ 78,112	\$ 338,487 See "Digs - Capital" Tab
Material- Other	\$ 13,751,719	30%	\$ 4,125,516	\$ 17,877,235 See "Elect - Capital" Tab
Sub-Total Construction and Materials	\$ 29,118,631		\$ 8,735,589	\$ 37,854,221

Summary Description	Bare Total	Override	Contingency	Total Cost	Basis	
Bellhole Inspection Services	\$ 48,402	3.9%	30%	\$ 14,521	\$ 62,922 See "Digs - Capital" Tab	
SCG / SDG&E Labor - Mgmt. & Non Labor	\$ 1,048,271	3.6%	30%	\$ 314,481	\$ 1,362,752 Historical %	
SCG / SDG&E Labor - Union T/H	\$ 376,000	0.1%	\$ 376,000	30%	\$ 112,800	\$ 488,800 2 workers for project duration
SCG / SDG&E Labor - Outreach & Public Affairs	\$ 1,019,152	3.5%	30%	\$ 305,746	\$ 1,324,898 Historical %	
Engineering / Design Services	\$ 506,250	0.8%	\$ 506,250	30%	\$ 151,875	\$ 658,125 Based on Engineering quote from SPEC S
PM / Project Services	\$ 387,750	3.5%	\$ 387,750	30%	\$ 116,325	\$ 504,075 Based on project duration and stage
Construction Management / Inspection	\$ 640,375	2.1%	\$ 640,375	30%	\$ 192,113	\$ 832,488 Based on project duration
Surveying / As-builts	\$ 35,000	0.2%	\$ 35,000	30%	\$ 10,500	\$ 45,500 Historical %
Environmental Services	\$ 1,073,559	3.0%	30%	\$ 322,068	\$ 1,395,627 Historical %	
Pressure Test Certification Services	\$ 22,798	0.1%	\$ 22,798	30%	\$ 6,839	\$ 29,637 Pipe size & duration of sub onsite
Water Storage	\$ 58,237	0.2%	30%	\$ 17,471	\$ 75,708 Historical %	
Weld X-Ray / NDE	\$ 39,984	0.1%	\$ 39,984	30%	\$ 11,995	\$ 51,979 Days of welding at \$2200/dy
Land Services	\$ 166,903	0.4%	\$ 166,903	30%	\$ 50,071	\$ 216,974 Historical % increased due to area of lease
CNG / LNG	\$ -	1.2%	\$ -	30%	\$ -	\$ - Assumes not needed
Gas Capture / Cross Compression	\$ -	0.8%	\$ -	30%	\$ -	\$ - Assumes not needed
Miscellaneous Services	\$ 611,491	2.1%	30%	\$ 183,447	\$ 794,939 Historical %	
Outreach & Public Affairs (Third Party)	\$ 58,237	0.2%	30%	\$ 17,471	\$ 75,708 Historical %	
Permits	\$ 116,475	0.4%	30%	\$ 34,942	\$ 151,417 Historical %	
Other Non-Labor Costs	\$ 122,171		\$ 122,171	30%	\$ 36,651	\$ 158,822 5% of SCG / SDG&E labor
Total Direct Estimated Cost (No Loaders)	\$ 35,449,687			\$ 10,634,906	\$ 46,082,648	

Basis Of Estimate

Project Details:

Project Location: Jacobs Ave & South Ave. Orange Cove, CA 93646

High Level Schedule: N/A

Peak Load: None provided

Pipeline Extension Diameter: 2" - 1"

Pipeline Extension Length: 1080 LF

Gas Source: Natural Gas

Collectable:

Scope Of Work:

Design and build a hydrogen blending site that will produce hydrogen onsite. A compound will be built in an existing parking lot that will utilize a PEM electrolyzer as the key component to producing hydrogen. Natural gas, water, sewer and electrical utilities will be extended from nearby sources to site compound equipment.

Assumptions:

The following assumptions and clarifications were used in the creation of this estimate based on feedback from the project team:

- Estimating Benchmarking database was utilized to source comparable projects.
- Additional costs for closeout/commissioning to be assumed based on past projects
- Assumes 5x10s work schedule
- Assumes site will be closed to the public during construction
- Assumes equipment and materials will be staged in the same parking lot as the compound
- Rates are based on average union rates
- Includes installation of 1000 LF of 6" PE pipe and associated appurtenances
- Assumes primary electrical connection is within 300 LF of compound
- Assumes equipment foundations will be scarified and compacted prior to pouring concrete
- Assumes water connection is within 3500 LF from compound (water canal location)
- Assumes sewer connection is within 300 LF of compound
- Includes (1) flow meter and (2) gas analyzers
- Includes hydrogen detectors, fire detectors, and ESD system
- Assumes existing asphalt is up to 6" thick and no substructures
- Includes (100) bollards at compound and surrounding equipment
- Project includes new SCADA enclosure that lies outside of Class 1, Div 1 area with a raised foundation pad
- Assumes third party will be hired to design and build the blending skid, including its control systems
- Assumes pipe is 6" PE pipe with the same specifications as natural gas requirements
- Assumes site is currently asphalt and will be excavated using mechanical means
- Includes (10) days of contractor commissioning support for equipment
- Assumes mechanical and electrical work will be performed at the same time
- Assumes joint trenching can be utilized for pipe and conduits
- Includes 0 sac slurry for backfilling trenches
- Estimate is based on SOW received, assumes constructability aligns with design proposed
- Assumes utility study will be conducted by others
- Includes 24 months of land leasing for project through decommissioning
- Includes 9 MW Battery Energy Storage System (BESS)
- Includes (1) PV inverter
- Assumes solar panels will be mounted no more than 10' high
- Assumes similar solar panel mounting design as shown on Vendor Quotes tab
- Assumes 6.5 acres of solar panels will be installed
- Estimate is based on SOW received, assumes constructability aligns with design proposed
- Assumes utility study will be conducted by others
- Includes 30% contingency - per PM request

Exclusions and Basis Of Estimate:

- Excludes seismic design considerations
- Excluding actuals spent to date
- Excludes Force Mejeur
- Excludes site drainage modifications
- Landscaping
- Estimate excludes any maintenance and utility costs that would be incurred after site is operational
- Ongoing electrical costs once site is operational
- Masonry walls
- Traffic control, assumes parking lot will be closed during construction
- Removal of trees or existing underground structures within site
- Geotechnical studies
- Overexcavation for equipment pads due to soil stability issues
- More than 1 mobilization
- Off-site work
- Site security
- Removal or relocation of unrelated owner equipment obstructing construction
- Permanent site fencing
- Site paving
- Demo/removal of any existing substructures
- Land Acquisition
- Equipment enclosures or sound mitigation methods
- Site lighting
- Handling, hauling, excavating contaminated soils
- Site grading
- Watertable controls/ Site dewatering
- Decommissioning/removal of site equipment
- Haz ops site assessment
- Demo/removal of any existing substructures
- Delays caused by road moratoriums

WOA Summary

Type	O&M Project	Capital/Plant - New Install	Total Capital/Plant - Removal	TOTALS
Company Labor	\$ 3,176,450			\$ 3,176,450
Contract Labor	\$ 18,982,737			\$ 18,982,737
Pipe Costs	\$ 193,539			\$ 193,539
Other Stores Material	\$ 818,770			\$ 818,770
Purchased Material	\$ 17,396,952			\$ 17,396,952
Purchased Services	\$ 4,743,683			\$ 4,743,683
Paving	\$ 460,278			\$ 460,278
Permits	\$ 151,417			\$ 151,417
Other Direct Costs	\$ 158,822			\$ 158,822
TOTAL DIRECT COSTS	\$ 46,082,648			\$ 46,082,648

Phase 2:

		Occurrences	Number of Staff	Hours Per Year	Average Hourly Rate	Labor Estimate (Direct Dollars)	Non-Labor Estimate (Direct Dollars)	Total Per Year (Direct Dollars)	Total for Phase 2 (Direct Dollars)
Equipment Maintenance	Union	99	8.5	1236	\$ 59.22	\$ 73,200.00	\$ 25,000.00	\$ 98,200.00	\$ 147,300.00
	Management	89	7	1096	\$ 90.00	\$ 98,640.00	\$ 25,000.00	\$ 123,640.00	\$ 185,460.00
	Third-Party	0	-	-	-	\$ -	\$ 57,000.00	\$ 57,000.00	\$ 85,500.00
Pipeline Leak Detection	Union	5	8.5	80	\$ 50.00	\$ 4,000.00	\$ -	\$ 4,000.00	\$ 6,000.00
	Management	0	8	0	-	\$ -	\$ -	\$ -	\$ -
Appliance Inspection	Union	1	8.5	8	\$ 45.00	\$ 360.00	\$ -	\$ 360.00	\$ 540.00
	Management	0	7	0	-	\$ -	\$ -	\$ -	\$ -
Odorant Testing and Sampling	Union	0	8.5	0	-	\$ -	\$ -	\$ -	\$ -
	Management	8	7	128	\$ 90.00	\$ 11,520.00	\$ -	\$ 11,520.00	\$ 17,280.00
Data Collection and Monitoring	Union	16	9	172	\$ 57.21	\$ 9,840.00	\$ -	\$ 9,840.00	\$ 14,760.00
	Management	77	7	688	\$ 90.00	\$ 61,920.00	\$ -	\$ 61,920.00	\$ 92,880.00
Test Plan Management	Union	0	8.5	0	-	\$ -	\$ -	\$ -	\$ -
	Management	20	7	160	\$ 90.00	\$ 14,400.00	\$ -	\$ 14,400.00	\$ 21,600.00
						\$ 273,880.00	\$ 107,000.00	\$ 380,880.00	\$ 571,320.00

Phase 3:

**Orange Cove H2 Blending Estimate Phase 3
PROJECT SUMMARY**

Summary Description	Bare Total	Contingency	Total Cost	Basis
Mechanical Contractor	\$ 922,412	30%	\$ 276,724	\$ 1,199,136 See "Digs - Capital" Tab
Electrical Contractor	\$ 1,001,577	30%	\$ 300,473	\$ 1,302,050 See "Elect - Capital" Tab
Material- Pipe	\$ -	30%	\$ -	\$ - See "Digs - Capital" Tab
Material-Valves & Fittings	\$ -	30%	\$ -	\$ - See "Digs - Capital" Tab
Material- Other	\$ -	30%	\$ -	\$ - See "Elect - Capital" Tab
Sub-Total Construction and Materials	\$ 1,923,989		\$ 577,197	\$ 2,501,186

Summary Description	Bare Total	Override	Contingency	Total Cost	Basis
Bellhole Inspection Services	\$ 4,033	3.9%	30%	\$ 1,210	\$ 5,244 See "Digs - Capital" Tab
SCG / SDG&E Labor - Mgmt. & Non Labor	\$ 69,264	3.6%	30%	\$ 20,779	\$ 90,043 Historical %
SCG / SDG&E Labor - Union T/H	\$ 128,000	0.1%	\$ 128,000	30%	\$ 38,400 2 workers for project duration
SCG / SDG&E Labor - Outreach & Public Affairs	\$ 28,860	1.5%	30%	\$ 8,658	\$ 37,518 Historical %
Engineering / Design Services	\$ 15,000	0.8%	\$ 15,000	30%	\$ 4,500 Minimal
PM / Project Services	\$ 148,500	3.5%	\$ 148,500	30%	\$ 44,550 Based on project duration and stage
Construction Management / Inspection	\$ 82,000	2.1%	\$ 82,000	30%	\$ 24,600 Based on project duration
Surveying / As-builts	\$ 20,000	0.2%	\$ 20,000	30%	\$ 6,000 Historical %
Environmental Services	\$ 48,100	2.5%	30%	\$ 14,430	\$ 62,530 Minimal
Pressure Test Certification Services	\$ -	0.1%	\$ -	30%	\$ - Pipe size & duration of sub onsite
Water Storage	\$ 5,772	0.3%	30%	\$ 1,732	\$ 7,504 Historical %
Weld X-Ray / NDE	\$ -	0.1%	\$ -	30%	\$ - Days of welding at \$2200/dy
Land Services	\$ -	0.0%	30%	\$ -	\$ - Assumes not needed
CNG / LNG	\$ -	1.2%	\$ -	30%	\$ - Assumes not needed
Gas Capture / Cross Compression	\$ -	0.8%	\$ -	30%	\$ - Assumes not needed
Miscellaneous Services	\$ 57,720	3.0%	30%	\$ 17,316	\$ 75,036 Historical %
Outreach & Public Affairs	\$ -		30%	\$ -	\$ - Historical %
Permits	\$ 9,620	0.5%	30%	\$ 2,886	\$ 12,506 Historical %
Other Non-Labor Costs	\$ 11,306		\$ 11,306	30%	\$ 3,392 5% of SCG / SDG&E labor
Total Direct Estimated Cost (No Loaders)	\$ 2,552,164			\$ 765,649	\$ 3,317,813

Class 5 Basis Of Estimate

Project Details:

Project Location: Jacobs Ave & South Ave. Orange Cove, CA 93646

High Level Schedule: N/A

Peak Load: None provided

Pipeline Extension Diameter: 2" - 1"

Pipeline Extension Length: 1080 LF

Gas Source: Natural Gas

Collectable:

Scope Of Work:

Phase 3 includes the decommissioning and removal of site equipment and foundations installed during phase 1.

Assumptions:

The following assumptions and clarifications were used in the creation of this estimate based on feedback from the project team:

- Estimating Benchmarking database was utilized to source comparable projects.
- Assumes 5x10s work schedule
- Includes demolition of:
 - Concrete equipment foundations
 - Compound Fencing
 - Bollards
- Includes disposal of debris according to city codes
- Assumes compound location after equipment removal will be left as dirt
- Includes disconnecting power lines
- Includes trucking/hauling equipment needed to lift and transport skids and equipment
- Includes removing all underground PE gas piping installed in phase 1
- Assumes UG Natural gas piping will be capped and abandoned in place from H2 compound to tie in locations
- Assumes UG water piping will be capped and abandoned in place from H2 compound to water canal
- Includes 6.5 acres of solar panel and mounting structure removal
- *Includes 30% contingency - per PM request*

Exclusions and Basis Of Estimate:

- Excluding actuals spent to date
- Excludes Force Mejeur
- Excludes site drainage modifications
- Permanent fencing
- Landscaping
- Handling/removing hazardous materials
- More than 1 mobilization
- Site security
- Excludes water & sewer work
- Re-installing removed equipment and future sites
- Relocation /Storage of Solar Panels
- Electronic Waste Disposal and/or Solar Panels disposal
- Disposal of electrical waste
- Long Term Storage of Used Equipment

WOA Summary

Type	O&M Project	Capital/Plant - New Install	Total Capital/Plant - Removal	TOTALS
Company Labor	\$ 293,960			\$ 293,960
Contract Labor	\$ 2,493,111			\$ 2,493,111
Pipe Costs	\$ -			\$ -
Other Stores Material	\$ -			\$ -
Purchased Material	\$ -			\$ -
Purchased Services	\$ 495,462			\$ 495,462
Paving	\$ 8,075			\$ 8,075
Permits	\$ 12,506			\$ 12,506
Other Direct Costs	\$ 14,698			\$ 14,698
TOTAL DIRECT COSTS	\$ 3,317,813			\$ 3,317,813

Phase 4:

Tasks	# of Staff	Occurrence	Hours Per Staff	Hourly Rate	Estimate	with 30% Contingency
Hydrogen Engineering and Data Team	1	39	8	\$ 90.00	\$ 28,080.00	\$ 36,504.00
Management	3	39	2	\$ 120.00	\$ 28,080.00	\$ 36,504.00
Reporting (Contractor/Third Party)						Tracked through subaccount
					Total	\$ 73,008.00