

**Lakeside-02**

**Appendix A Supporting the Prepared Direct Testimony of  
Daryl Maas**

**(Pilot Project)**

**[PUBLIC VERSION VOLUME 2]**




11.8	5.4	Competition from Energy Uses of Manure	884
11.9	5.4	Weed Seed Survival in Anaerobic Digesters	892
11.10	5.2	Excerpt from SJVAPCD ATC Documenting Lagoon Emissions	898
11.11	5.2	NYSERDA Assessment	914
11.12	5.1/5.2	2017 Carl Moyer Appendix D	949
11.13	5.1/5.2	EPA - Tier 1-3 Exhaust Emissions Standards	979
11.14	5.4	Fresno Pan Evaporation Study	980
<b>12</b>	<b>5.3.2</b>	<b>Docs that Support Vehicle Fuel Sold to State's Major Freight Corridors</b>	<b>981</b>
12.1	5.3.2	Lakeside CNG Map	981
12.2	5.3.2	California Retail Fuel Outlet Annual Reporting (CEC-A15) Results	983
<b>13</b>	<b>5.3.3</b>	<b>CNG Fleet Conversion Documentation</b>	<b>988</b>
13.1	5.3.3	CNG Fleet Conversion Documentation - Letter from JD Heiskill	988
13.2	5.3.3	CNG Fleet Conversion Documentation - Letter from Flyer's Energy	989
<b>14</b>	<b>5.3.4</b>	<b>Letter from Maas Energy Works - Not Applicable</b>	<b>990</b>
<b>15</b>	<b>6.1.7</b>	<b>Support Letters</b>	<b>991</b>
15.1	6.1.7	Support Letter - Rudy Salas, 32nd District Assembly Member	991
15.2	6.1.7	Support Letter - Kings County Economic Development Corporation	992
15.3	6.1.7	Support Letter - Robert Alcazar, CEO of Proteus Inc	994
15.4	6.1.7	Support Letter - Catarino Ramirez, Community Member	995
15.5	6.1.7	Support Letter - Jose Cruz, Community Member	996
15.6	6.1.7	Support Letter - Jose Martinez, Community Member	997
15.7	6.1.7	Support Letter - Luis Lopez, Community Member	998
15.8	6.1.7	Support Letter - Vera Sanchez Ramirez, Community Member	999
<b>16</b>	<b>7.0.2</b>	<b>Site Control Documentation</b>	<b>1000</b>
16.1	7.0.2	Lakeside Pipeline - Grant of Option to Lease Land for Project Hub Site	1000
<b>17</b>		<b>Additional Supporting Documentation</b>	<b>1006</b>
17.1	4.1	Explanation of GHG Inputs and Assumptions - Digester #1 - Decade Centralized	1006
17.2	4.1	Explanation of GHG Inputs and Assumptions - Digester #2 - Clear Lake Dairy	1008
17.3	4.1	Explanation of GHG Inputs and Assumptions - Digester #3 - Dixie Creek Dairy	1009
17.4	4.1	Explanation of GHG Inputs and Assumptions - Digester #4 - Double L Cattle	1010
17.5	4.1	Explanation of GHG Inputs and Assumptions - Digester #5 - High Roller Dairy	1011
17.6	4.1	Explanation of GHG Inputs and Assumptions - Digester #6 - Lakeside Dairy	1012
17.7	4.1	Explanation of GHG Inputs and Assumptions - Digester #7 - Lone Oak Farms #1	1013
17.8	4.1	Explanation of GHG Inputs and Assumptions - Digester #8 - Poplar Lane Dairy	1014
17.9	4.1	Explanation of GHG Inputs and Assumptions - Digester #9 - River Ranch Farms	1015
17.10	4.1	Explanation of GHG Inputs and Assumptions - Entire Cluster - Lakeside Pipeline LLC	1016
17.11	6.2	Lakeside Pipeline Cluster - Kings County Community Engagement Presentation	1020
17.12	6.2	Visalia Times Delta Bilingual Advertisement for Community Engagement Meeting	1038
17.13	6.2	Community Benefits Agreement #1 - Kings County Economic Dev. Corp.	1039
17.13b	6.2	Community Benefits Agreement #2 - Proteus Employment Services	1043
17.14	6.2	U.S. Bureau of Labor Statistics for Kings County	1045
17.15	6.2	US Census Bureau - Individuals Below Poverty in Kings County	1046
17.16	6.2	Example Contract with Local Hiring Requirement	1047
17.17	6.2	Sacramento Regional Research Institute - Stimulus Calculation Tool	1048
17.18	6.2	University of California Agriculture Issues Center - Economic Impact Study	1050



**Lakeside Pipeline Dairy Digester Cluster**

**Decade Centralized Dairy - Digester 1**

*Annotated Manure Treatment Diagram (pre-project)*






**Lakeside Pipeline Dairy Digester Cluster**

**Decade Centralized Dairy - Digester 1**

*Richard Westra Dairy Annotated Manure Treatment Diagram (pre-project)*






**Lakeside Pipeline Dairy Digester Cluster**  
**Clear Lake Dairy - Digester 2**  
*Annotated Manure Treatment Diagram (pre-project)*





**Lakeside Pipeline Dairy Digester Cluster**  
**Dixie Creek Dairy - Digester 3**  
*Annotated Manure Treatment Diagram (pre-project)*






## Lakeside Pipeline Dairy Digester Cluster


### Double L Dairy - Digester 4

Annotated Manure Treatment Diagram (pre-project)





**Lakeside Pipeline Dairy Digester Cluster**  
**High Roller Dairy - Digester 5**  
*Annotated Manure Treatment Diagram (pre-project)*






## Lakeside Pipeline Dairy Digester Cluster

### Lakeside Dairy - Digester 6

Annotated Manure Treatment Diagram (pre-project)






**Lakeside Pipeline Dairy Digester Cluster**

**Lone Oak #1 Dairy - Digester 7**

*Annotated Manure Treatment Diagram (pre-project)*





**Lakeside Pipeline Digester Cluster**  
**Poplar Lane Dairy - Digester 8**  
*Annotated Manure Treatment Diagram (pre-project)*






## Lakeside Pipeline Dairy Digester Cluster

### River Ranch Dairy - Digester 9

Annotated Manure Treatment Diagram (pre-project)





## Lakeside Pipeline Cluster - Digester #1

### Decade Centralized Dairy Digester Pipeline Project

#### Mass Balance Tables

BASELINE																		
Herd Information					Manure Excreted			Collection Rates		Collection Quantities		Solids Removal				To Storage		
Animal Type	Number of Animals	Breed	Housing	Animal Weight (kg)	Volatile Solids Excreted (kg / day / 1000kg mass) <sup>1</sup>	Volatile Solids (lbs/day)	Total Solids (lbs/day) <sup>2</sup>	% TS/VS Deposited on Land	% TS/VS Collected by Manure System	Pounds TS/ Day	Pounds VS/Day	Separation Type	TS/VS Separated (% of Gross Excreted) <sup>3</sup>	Total Solids Removed (lbs/day)	Volatile Solids Removed (lbs/day)	Total Solids (lbs/day)	Volatile Solids (lbs/day)	Total Fluid to Storage (gal/day)
Milk Cow - Decade Dairy	3,000	Holstein	Freestall	680	11.41	51,316	68,421	20%	80%	54,737	41,053	Weeping Wall	36.0%	24,632	18,474	30,105	22,579	
Dry Cow - Decade Dairy	300	Holstein	Open Lot	684	5.56	2,515	3,354	70%	30%	1,006	755	Weeping Wall	13.5%	453	340	553	415	
Heifer - Decade Dairy	1,400	Holstein	Open Lot	407	8.44	10,602	14,136	70%	30%	4,241	3,181	Weeping Wall	13.5%	1,908	1,431	2,333	1,749	
Milk Cow 1 - Richard Westra	1,500	Holstein	Freestall	680	11.41	25,658	34,210	20%	80%	27,368	20,526	None	0.0%	-	-	27,368	20,526	
Milk Cow 2 - Richard Westra	250	Holstein	Open Lot	680	11.41	4,276	5,702	70%	30%	1,711	1,283	None	0.0%	-	-	1,711	1,283	
Dry Cow - Richard Westra	250	Holstein	Open Lot	684	5.56	2,096	2,795	70%	30%	838	629	None	0.0%	-	-	838	629	
Heifer - Richard Westra	1,500	Holstein	Open Lot	407	8.44	11,360	15,146	70%	30%	4,544	3,408	None	0.0%	-	-	4,544	3,408	
	8,200					107,823	143,764			94,445	70,834			26,993	20,245	67,452	50,589	522,500

PROJECT																
Herd Information					Manure Excreted			Collection Rates		Collection Quantities		Solids Removal				
Animal Type	Number of Animals	Breed	Housing	Animal Weight (kg)	Volatile Solids Excreted (kg / day / 1000kg mass) <sup>1</sup>	Volatile Solids (lbs/day)	Total Solids (lbs/day) <sup>2</sup>	% TS/VS Deposited on Land	TS/VS Collected (% of Gross Excreted)	Total Solids (lbs/day)	Volatile Solids (lbs/day)	Separation Type	TS/VS Separated (% of Gross Excreted) <sup>3</sup>	Total Solids Removed (lbs/day)	Volatile Solids Removed (lbs/day)	
Milk Cow - Decade Dairy	3,000	Holstein	Freestall	680	11.41	51,316	68,421	20%	80%	54,737	41,053	Weeping Wall	36.0%	24,632	18,474	
Dry Cow - Decade Dairy	300	Holstein	Open Lot	684	5.56	2,515	3,354	70%	30%	1,006	755	Weeping Wall	13.5%	453	340	
Heifer - Decade Dairy	1,400	Holstein	Open Lot	407	8.44	10,602	14,136	70%	30%	4,241	3,181	Weeping Wall	13.5%	1,908	1,431	
Milk Cow 1 - Richard Westra	1,500	Holstein	Freestall	680	11.41	25,658	34,210	20%	80%	27,368	20,526	Vibrating Screen	12.0%	4,105	3,079	
Milk Cow 2 - Richard Westra	250	Holstein	Open Lot	680	11.41	4,276	5,702	70%	30%	1,711	1,283	Vibrating Screen	4.5%	257	192	
Dry Cow - Richard Westra	250	Holstein	Open Lot	684	5.56	2,096	2,795	70%	30%	838	629	Vibrating Screen	4.5%	126	94	
Heifer - Richard Westra	1,500	Holstein	Open Lot	407	8.44	11,360	15,146	70%	30%	4,544	3,408	Vibrating Screen	4.5%	682	511	
	8,200					107,823	143,764			94,445	70,834			32,162	24,121	

	Digester Influent				Digestion					Digester Effluent		
Animal Type	TS/VS Entering Digester (% of Gross Excreted )	TS Entering Digester (lbs/day)	VS Entering Digester (lbs/day)	Total Fluid Entering Digester (gal/day)	VS Destruction Rate <sup>4</sup>	VS Destroyed (lbs/day)	SCF Biogas / lbs VS Destroyed	Biogas Production (scf/day @ 60% CH4)	Biogas Production (MMBTU/yr)	TS Exiting Digester (lbs/day)	VS Exiting Digester (lbs/day)	Total Fluid Exiting Digester (gal/day)
Milk Cow - Decade Dairy	44.0%	30,105	22,579		42%	9,483	14.3	135,609	29,698	20,622	13,096	
Dry Cow - Decade Dairy	16.5%	553	415		42%	174	14.3	2,493	546	379	241	
Heifer - Decade Dairy	16.5%	2,333	1,749		42%	735	14.3	10,507	2,301	1,598	1,015	
Milk Cow 1 - Richard Westra	68.0%	23,263	17,447		42%	7,328	14.3	104,789	22,949	15,935	10,119	
Milk Cow 2 - Richard Westra	25.5%	1,454	1,090		42%	458	14.3	6,549	1,434	996	632	
Dry Cow - Richard Westra	25.5%	713	534		42%	224	14.3	3,210	703	488	310	
Heifer - Richard Westra	25.5%	3,862	2,897		42%	1,217	14.3	17,398	3,810	2,646	1,680	
		62,283	46,712	522,500		19,619		280,554	61,441	42,664	27,093	520,148

Separator Efficiency Table*	
Type	VS Removal Rate (% of Gross Collected)
No Solid Separation	0%
Weeping Wall	45%
Stationary Screen	17%
Vibrating Screen	15%

\*Per ARB's GHG Calculator

<sup>1</sup> Per ARB's GHG Calculator

<sup>2</sup> Assumes 75% of Totals Solids is Volatile

<sup>3</sup> TS/VS Separated shown as a "% of gross manure excreted" to match ARB's GHG Calculator. Separator efficiencies shown as a "% of gross manure collected" also referenced in the Separator Efficiency Table

<sup>4</sup> Calculated by Project Engineer, Craig Hartman of Hartman Engineering, based on site specific design and HRT



**Clear Lake Dairy Digester Pipeline Project**  
Mass Balance Tables

BASELINE																		
Herd Information					Manure Excreted			Collection Rates		Collection Quantities		Solids Removal				To Storage		
Animal Type	Number of Animals	Breed	Housing	Animal Weight (kg)	Volatile Solids Excreted (kg / day / 1000kg mass) <sup>1</sup>	Volatile Solids (lbs/day)	Total Solids (lbs/day) <sup>2</sup>	% TS/VS Deposited on Land	% TS/VS Collected by Manure System	Pounds TS/ Day	Pounds VS/Day	Separation Type	TS/VS Separated (% of Gross Excreted) <sup>3</sup>	Total Solids Removed (lbs/day)	Volatile Solids Removed (lbs/day)	Total Solids (lbs/day)	Volatile Solids (lbs/day)	Total Fluid to Storage (gal/day)
Milking Cow	2,050	Holstein	Freestall	680	11.41	35,066	46,754	20%	80%	37,403	28,053	Stationary Screen	13.6%	6,359	4,769	31,045	23,284	
Dry Cow	400	Holstein	Open Lot	684	5.56	3,354	4,472	70%	30%	1,341	1,006	Stationary Screen	5.1%	228	171	1,113	835	
Heifer	2,000	Holstein	Open Lot	407	8.44	15,146	20,195	70%	30%	6,058	4,544	Stationary Screen	5.1%	1,030	772	5,029	3,771	
	<b>4,450</b>					<b>53,566</b>	<b>71,421</b>			<b>44,803</b>	<b>33,603</b>			<b>7,617</b>	<b>5,712</b>	<b>37,187</b>	<b>27,890</b>	<b>266,500</b>

PROJECT															
Herd Information					Manure Excreted			Collection Rates		Collection Quantities		Solids Removal			
Animal Type	Number of Animals	Breed	Housing	Animal Weight (kg)	Volatile Solids Excreted (kg / day / 1000kg mass) <sup>1</sup>	Volatile Solids (lbs/day)	Total Solids (lbs/day) <sup>2</sup>	% TS/VS Deposited on Land	TS/VS Collected (% of Gross Excreted)	Total Solids (lbs/day)	Volatile Solids (lbs/day)	Separation Type	TS/VS Separated (% of Gross Excreted) <sup>3</sup>	Total Solids Removed (lbs/day)	Volatile Solids Removed (lbs/day)
Milking Cow	2,050	Holstein	Freestall	680	11.41	35,066	46,754	20%	80%	37,403	28,053	Stationary Screen	13.6%	6,359	4,769
Dry Cow	400	Holstein	Open Lot	684	5.56	3,354	4,472	70%	30%	1,341	1,006	Stationary Screen	5.1%	228	171
Heifer	2,000	Holstein	Open Lot	407	8.44	15,146	20,195	70%	30%	6,058	4,544	Stationary Screen	5.1%	1,030	772
						<b>53,566</b>	<b>71,421</b>			<b>44,803</b>	<b>33,603</b>			<b>7,617</b>	<b>5,712</b>

Digester Influent				Digestion					Digester Effluent		
TS/VS Entering Digester (% of Gross Excreted )	TS Entering Digester (lbs/day)	VS Entering Digester (lbs/day)	Total Fluid Entering Digester (gal/day)	VS Destruction Rate <sup>4</sup>	VS Destroyed (lbs/day)	SCF Biogas / lbs VS Destroyed	Biogas Production (scf/day @ 60% CH4)	Biogas Production (MMBTU/yr)	TS Exiting Digester (lbs/day)	VS Exiting Digester (lbs/day)	Total Fluid Exiting Digester (gal/day)
66.4%	31,045	23,284		38%	8,848	14.3	126,523	27,709	22,197	14,436	
24.9%	1,113	835		38%	317	14.3	4,538	994	796	518	
24.9%	5,029	3,771		38%	1,433	14.3	20,494	4,488	3,595	2,338	
	37,187	27,890	266,500		10,598		151,555	33,190	26,589	17,292	265,229

Separator Efficiency Table*	
Type	VS Removal Rate (% of Gross Collected)
No Solid Separation	0%
Weeping Wall	45%
Stationary Screen	17%
Vibrating Screen	15%

\*Per ARB's GHG Calculator

<sup>1</sup> Per ARB's GHG Calculator<sup>2</sup> Assumes 75% of Totals Solids is Volatile<sup>3</sup> TS/VS Separated shown as a "% of gross manure excreted" to match ARB's GHG Calculator. Separator efficiencies shown as a "% of gross manure collected" also referenced in the Separator Efficiency Table<sup>4</sup> Calculated by Project Engineer based on site specific design and HRT



**Dixie Creek Dairy Digester Pipeline Project**  
Mass Balance Tables

BASELINE																		
Herd Information					Manure Excreted			Collection Rates		Collection Quantities		Solids Removal				To Storage		
Animal Type	Number of Animals	Breed	Housing	Animal Weight (kg)	Volatile Solids Excreted (kg / day / 1000kg mass) <sup>1</sup>	Volatile Solids (lbs/day)	Total Solids (lbs/day) <sup>2</sup>	% TS/VS Deposited on Land	% TS/VS Collected by Manure System	Pounds TS/ Day	Pounds VS/Day	Separation Type	TS/VS Separated (% of Gross Excreted) <sup>3</sup>	Total Solids Removed (lbs/day)	Volatile Solids Removed (lbs/day)	Total Solids (lbs/day)	Volatile Solids (lbs/day)	Total Fluid to Storage (gal/day)
Milking Cow	4,600	Holstein	Freestall	680	11.41	78,684	104,912	20%	80%	83,930	62,947	Stationary Screen	13.6%	14,268	10,701	69,662	52,246	
Milking Cow	400	Holstein	Open Lot	680	11.41	6,842	9,123	70%	30%	2,737	2,053	Stationary Screen	5.1%	465	349	2,272	1,704	
Dry Cow	750	Holstein	Open Lot	684	5.56	6,288	8,384	70%	30%	2,515	1,886	Stationary Screen	5.1%	428	321	2,088	1,566	
Heifer	500	Holstein	Open Lot	407	8.44	3,787	5,049	70%	30%	1,515	1,136	Stationary Screen	5.1%	257	193	1,257	943	
						<b>95,601</b>	<b>127,468</b>			<b>90,696</b>	<b>68,022</b>			<b>15,418</b>	<b>11,564</b>	<b>75,278</b>	<b>56,458</b>	<b>750,000</b>

PROJECT																
Herd Information					Manure Excreted			Collection Rates		Collection Quantities		Solids Removal				
Animal Type	Number of Animals	Breed	Housing	Animal Weight (kg)	Volatile Solids Excreted (kg / day / 1000kg mass) <sup>1</sup>	Volatile Solids (lbs/day)	Total Solids (lbs/day) <sup>2</sup>	% TS/VS Deposited on Land	% TS/VS Collected (% of Gross Excreted)	Total Solids (lbs/day)	Volatile Solids (lbs/day)	Separation Type	TS/VS Separated (% of Gross Excreted) <sup>3</sup>	Total Solids Removed (lbs/day)	Volatile Solids Removed (lbs/day)	
Milking Cow	4,600	Holstein	Freestall	680	11.41	78,684	104,912	20%	80%	83,930	62,947	Stationary Screen	13.6%	14,268	10,701	
Milking Cow	400	Holstein	Open Lot	680	11.41	6,842	9,123	70%	30%	2,737	2,053	Stationary Screen	5.1%	465	349	
Dry Cow	750	Holstein	Open Lot	684	5.56	6,288	8,384	70%	30%	2,515	1,886	Stationary Screen	5.1%	428	321	
Heifer	500	Holstein	Open Lot	407	8.44	3,787	5,049	70%	30%	1,515	1,136	Stationary Screen	5.1%	257	193	
						<b>95,601</b>	<b>127,468</b>			<b>90,696</b>	<b>68,022</b>			<b>15,418</b>	<b>11,564</b>	

Digester Influent				Digestion					Digester Effluent		
TS/VS Entering Digester (% of Gross Excreted )	TS Entering Digester (lbs/day)	VS Entering Digester (lbs/day)	Total Fluid Entering Digester (gal/day)	VS Destruction Rate <sup>4</sup>	VS Destroyed (lbs/day)	SCF Biogas / lbs VS Destroyed	Biogas Production (scf/day @ 60% CH4)	Biogas Production (MMBTU/yr)	TS Exiting Digester (lbs/day)	VS Exiting Digester (lbs/day)	Total Fluid Exiting Digester (gal/day)
66.4%	69,662	52,246		38%	19,854	14.3	283,906	62,175	49,808	32,393	
24.9%	2,272	1,704		38%	647	14.3	9,258	2,027	1,624	1,056	
24.9%	2,088	1,566		38%	595	14.3	8,508	1,863	1,493	971	
24.9%	1,257	943		38%	358	14.3	5,123	1,122	899	585	
	75,278	56,458	750,000		21,454		306,795	67,188	53,824	35,004	747,428

Separator Efficiency Table*	
Type	VS Removal Rate (% of Gross Collected)
No Solid Separation	0%
Weeping Wall	45%
Stationary Screen	17%
Vibrating Screen	15%

\*Per ARB's GHG Calculator

<sup>1</sup> Per ARB's GHG Calculator<sup>2</sup> Assumes 75% of Totals Solids is Volatile<sup>3</sup> TS/VS Separated shown as a "% of gross manure excreted" to match ARB's GHG Calculator. Separator efficiencies shown as a "% of gross manure collected" also referenced in the Separator Efficiency Table<sup>4</sup> Calculated by Project Engineer based on site specific design and HRT



**Double L Dairy Digester Pipeline Project**  
Mass Balance Tables

BASELINE																		
Herd Information					Manure Excreted			Collection Rates		Collection Quantities		Solids Removal				To Storage		
Animal Type	Number of Animals	Breed	Housing	Animal Weight (kg)	Volatile Solids Excreted (kg / day / 1000kg mass) <sup>1</sup>	Volatile Solids (lbs/day)	Total Solids (lbs/day) <sup>2</sup>	% TS/VS Deposited on Land	% TS/VS Collected by Manure System	Pounds TS/ Day	Pounds VS/Day	Separation Type	TS/VS Separated (% of Gross Excreted) <sup>3</sup>	Total Solids Removed (lbs/day)	Volatile Solids Removed (lbs/day)	Total Solids (lbs/day)	Volatile Solids (lbs/day)	Total Fluid to Storage (gal/day)
Milking Cow	2,590	Holstein	Freestall	680	11.41	44,303	59,070	20%	80%	47,256	35,442	Stationary Screen	13.6%	8,034	6,025	39,223	29,417	
Dry Cow	239	Holstein	Open Lot	684	5.56	2,004	2,672	70%	30%	802	601	Stationary Screen	5.1%	136	102	665	499	
Heifer	2,640	Holstein	Open Lot	407	8.44	19,993	26,657	70%	30%	7,997	5,998	Stationary Screen	5.1%	1,360	1,020	6,638	4,978	
						<b>66,299</b>	<b>88,399</b>			<b>56,055</b>	<b>42,041</b>					<b>46,525</b>	<b>34,894</b>	<b>388,500</b>

PROJECT															
Herd Information					Manure Excreted			Collection Rates		Collection Quantities		Solids Removal			
Animal Type	Number of Animals	Breed	Housing	Animal Weight (kg)	Volatile Solids Excreted (kg / day / 1000kg mass) <sup>1</sup>	Volatile Solids (lbs/day)	Total Solids (lbs/day) <sup>2</sup>	% TS/VS Deposited on Land	TS/VS Collected (% of Gross Excreted)	Total Solids (lbs/day)	Volatile Solids (lbs/day)	Separation Type	TS/VS Separated (% of Gross Excreted) <sup>3</sup>	Total Solids Removed (lbs/day)	Volatile Solids Removed (lbs/day)
Milking Cow	2,590	Holstein	Freestall	680	11.41	44,303	59,070	20%	80%	47,256	35,442	Stationary Screen	13.6%	8,034	6,025
Dry Cow	239	Holstein	Open Lot	684	5.56	2,004	2,672	70%	30%	802	601	Stationary Screen	5.1%	136	102
Heifer	2,640	Holstein	Open Lot	407	8.44	19,993	26,657	70%	30%	7,997	5,998	Stationary Screen	5.1%	1,360	1,020
						<b>66,299</b>	<b>88,399</b>			<b>56,055</b>	<b>42,041</b>				

Digester Influent				Digestion					Digester Effluent		
TS/VS Entering Digester (% of Gross Excreted )	TS Entering Digester (lbs/day)	VS Entering Digester (lbs/day)	Total Fluid Entering Digester (gal/day)	VS Destruction Rate <sup>4</sup>	VS Destroyed (lbs/day)	SCF Biogas / lbs VS Destroyed	Biogas Production (scf/day @ 60% CH4)	Biogas Production (MMBTU/yr)	TS Exiting Digester (lbs/day)	VS Exiting Digester (lbs/day)	Total Fluid Exiting Digester (gal/day)
66.4%	39,223	29,417		54%	15,885	14.3	227,157	49,747	23,337	13,532	
24.9%	665	499		54%	269	14.3	3,853	844	396	230	
24.9%	6,638	4,978		54%	2,688	14.3	38,442	8,419	3,949	2,290	
	<b>46,525</b>	<b>34,894</b>	<b>388,500</b>		<b>18,843</b>		<b>269,452</b>	<b>59,010</b>	<b>27,683</b>	<b>16,051</b>	<b>386,241</b>

Separator Efficiency Table*	
Type	VS Removal Rate (% of Gross Collected)
No Solid Separation	0%
Weeping Wall	45%
Stationary Screen	17%
Vibrating Screen	15%

\*Per ARB's GHG Calculator

<sup>1</sup> Per ARB's GHG Calculator<sup>2</sup> Assumes 75% of Totals Solids is Volatile<sup>3</sup> TS/VS Separated shown as a "% of gross manure excreted" to match ARB's GHG Calculator. Separator efficiencies shown as a "% of gross manure collected" also referenced in the Separator Efficiency Table<sup>4</sup> Calculated by Project Engineer based on site specific design and HRT



**High Roller Dairy Digester Pipeline**  
Mass Balance Tables

BASELINE																		
Herd Information					Manure Excreted			Collection Rates		Collection Quantities		Solids Removal				To Storage		
Animal Type	Number of Animals	Breed	Housing	Animal Weight (kg)	Volatile Solids Excreted (kg / day / 1000kg mass) <sup>1</sup>	Volatile Solids (lbs/day)	Total Solids (lbs/day) <sup>2</sup>	% TS/VS Deposited on Land	% TS/VS Collected by Manure System	Pounds TS/ Day	Pounds VS/Day	Separation Type	TS/VS Separated (% of Gross Excreted) <sup>3</sup>	Total Solids Removed (lbs/day)	Volatile Solids Removed (lbs/day)	Total Solids (lbs/day)	Volatile Solids (lbs/day)	Total Fluid to Storage (gal/day)
Milking Cow	1,900	Jersey	Freestall	680	11.41	32,500	43,333	20%	80%	34,667	26,000	Vibrating Screen	12.0%	5,200	3,900	29,467	22,100	
Dry Cow	265	Jersey	Open Lot	684	5.56	2,222	2,962	70%	30%	889	667	Vibrating Screen	4.5%	133	100	755	567	
Heifer	1,975	Jersey	Open Lot	407	8.44	14,957	19,942	70%	30%	5,983	4,487	Vibrating Screen	4.5%	897	673	5,085	3,814	
						<b>49,679</b>	<b>66,238</b>			<b>41,538</b>	<b>31,154</b>					<b>35,307</b>	<b>26,480</b>	<b>228,000</b>

PROJECT															
Herd Information					Manure Excreted			Collection Rates		Collection Quantities		Solids Removal			
Animal Type	Number of Animals	Breed	Housing	Animal Weight (kg)	Volatile Solids Excreted (kg / day / 1000kg mass) <sup>1</sup>	Volatile Solids (lbs/day)	Total Solids (lbs/day) <sup>2</sup>	% TS/VS Deposited on Land	TS/VS Collected (% of Gross Excreted)	Total Solids (lbs/day)	Volatile Solids (lbs/day)	Separation Type	TS/VS Separated (% of Gross Excreted) <sup>3</sup>	Total Solids Removed (lbs/day)	Volatile Solids Removed (lbs/day)
Milking Cow	1,900	Jersey	Freestall	680	11.41	32,500	43,333	20%	80%	34,667	26,000	Vibrating Screen	12.0%	5,200	3,900
Dry Cow	265	Jersey	Open Lot	684	5.56	2,222	2,962	70%	30%	889	667	Vibrating Screen	4.5%	133	100
Heifer	1,975	Jersey	Open Lot	407	8.44	14,957	19,942	70%	30%	5,983	4,487	Vibrating Screen	4.5%	897	673
						<b>49,679</b>	<b>66,238</b>			<b>41,538</b>	<b>31,154</b>				

Digester Influent				Digestion					Digester Effluent		
TS/VS Entering Digester (% of Gross Excreted )	TS Entering Digester (lbs/day)	VS Entering Digester (lbs/day)	Total Fluid Entering Digester (gal/day)	VS Destruction Rate <sup>4</sup>	VS Destroyed (lbs/day)	SCF Biogas / lbs VS Destroyed	Biogas Production (scf/day @ 60% CH4)	Biogas Production (MMBTU/yr)	TS Exiting Digester (lbs/day)	VS Exiting Digester (lbs/day)	Total Fluid Exiting Digester (gal/day)
68.0%	29,467	22,100		42%	9,282	14.3	132,732	29,068	20,185	12,818	
25.5%	755	567		42%	238	14.3	3,403	745	517	329	
25.5%	5,085	3,814		42%	1,602	14.3	22,907	5,017	3,483	2,212	
	<b>35,307</b>	<b>26,480</b>	<b>228,000</b>		<b>11,122</b>		<b>159,042</b>	<b>34,830</b>	<b>24,186</b>	<b>15,359</b>	<b>226,666</b>

Separator Efficiency Table*	
Type	VS Removal Rate (% of Gross Collected)
No Solid Separation	0%
Weeping Wall	45%
Stationary Screen	17%
Vibrating Screen	15%

\*Per ARB's GHG Calculator

<sup>1</sup> Per ARB's GHG Calculator<sup>2</sup> Assumes 75% of Totals Solids is Volatile<sup>3</sup> TS/VS Separated shown as a "% of gross manure excreted" to match ARB's GHG Calculator. Separator efficiencies shown as a "% of gross manure collected" also referenced in the Separator Efficiency Table<sup>4</sup> Calculated by Project Engineer based on site specific design and HRT



**Lakeside Dairy Digester Pipeline Project**  
Mass Balance Tables

BASELINE																		
Herd Information					Manure Excreted			Collection Rates		Collection Quantities		Solids Removal				To Storage		
Animal Type	Number of Animals	Breed	Housing	Animal Weight (kg)	Volatile Solids Excreted (kg / day / 1000kg mass) <sup>1</sup>	Volatile Solids (lbs/day)	Total Solids (lbs/day) <sup>2</sup>	% TS/VS Deposited on Land	% TS/VS Collected by Manure System	Pounds TS/ Day	Pounds VS/Day	Separation Type	TS/VS Separated (% of Gross Excreted) <sup>3</sup>	Total Solids Removed (lbs/day)	Volatile Solids Removed (lbs/day)	Total Solids (lbs/day)	Volatile Solids (lbs/day)	Total Fluid to Storage (gal/day)
Milking Cow	3,965	Holstein	Freestall	680	11.41	67,822	90,430	20%	80%	72,344	54,258	Stationary Screen	13.6%	12,298	9,224	60,045	45,034	
Dry Cow	442	Holstein	Open Lot	684	5.56	3,706	4,941	70%	30%	1,482	1,112	Stationary Screen	5.1%	252	189	1,230	923	
Heifer	3,676	Holstein	Open Lot	407	8.44	27,839	37,118	70%	30%	11,135	8,352	Stationary Screen	5.1%	1,893	1,420	9,242	6,932	
						<b>99,367</b>	<b>132,489</b>			<b>84,961</b>	<b>63,721</b>			<b>14,443</b>	<b>10,833</b>	<b>70,518</b>	<b>52,889</b>	<b>594,750</b>

PROJECT															
Herd Information					Manure Excreted			Collection Rates		Collection Quantities		Solids Removal			
Animal Type	Number of Animals	Breed	Housing	Animal Weight (kg)	Volatile Solids Excreted (kg / day / 1000kg mass) <sup>1</sup>	Volatile Solids (lbs/day)	Total Solids (lbs/day) <sup>2</sup>	% TS/VS Deposited on Land	% TS/VS Collected (% of Gross Excreted)	Total Solids (lbs/day)	Volatile Solids (lbs/day)	Separation Type	TS/VS Separated (% of Gross Excreted) <sup>3</sup>	Total Solids Removed (lbs/day)	Volatile Solids Removed (lbs/day)
Milking Cow	3,965	Holstein	Freestall	680	11.41	67,822	90,430	20%	80%	72,344	54,258	Stationary Screen	13.6%	12,298	9,224
Dry Cow	442	Holstein	Open Lot	684	5.56	3,706	4,941	70%	30%	1,482	1,112	Stationary Screen	5.1%	252	189
Heifer	3,676	Holstein	Open Lot	407	8.44	27,839	37,118	70%	30%	11,135	8,352	Stationary Screen	5.1%	1,893	1,420
						<b>99,367</b>	<b>132,489</b>			<b>84,961</b>	<b>63,721</b>			<b>14,443</b>	<b>10,833</b>

Digester Influent				Digestion					Digester Effluent		
TS/VS Entering Digester (% of Gross Excreted )	TS Entering Digester (lbs/day)	VS Entering Digester (lbs/day)	Total Fluid Entering Digester (gal/day)	VS Destruction Rate <sup>4</sup>	VS Destroyed (lbs/day)	SCF Biogas / lbs VS Destroyed	Biogas Production (scf/day @ 60% CH <sub>4</sub> )	Biogas Production (MMBTU/yr)	TS Exiting Digester (lbs/day)	VS Exiting Digester (lbs/day)	Total Fluid Exiting Digester (gal/day)
66.4%	60,045	45,034		42%	18,914	14.3	270,474	59,234	41,131	26,120	
24.9%	1,230	923		42%	388	14.3	5,542	1,214	843	535	
24.9%	9,242	6,932		42%	2,911	14.3	41,632	9,117	6,331	4,020	
	<b>70,518</b>	<b>52,889</b>	<b>594,750</b>		<b>22,213</b>		<b>317,648</b>	<b>69,565</b>	<b>48,305</b>	<b>30,675</b>	<b>592,087</b>

Separator Efficiency Table*	
Type	VS Removal Rate (% of Gross Collected)
No Solid Separation	0%
Weeping Wall	45%
Stationary Screen	17%
Vibrating Screen	15%

\*Per ARB's GHG Calculator

<sup>1</sup> Per ARB's GHG Calculator<sup>2</sup> Assumes 75% of Totals Solids is Volatile<sup>3</sup> TS/VS Separated shown as a "% of gross manure excreted" to match ARB's GHG Calculator. Separator efficiencies shown as a "% of gross manure collected" also referenced in the Separator Efficiency Table<sup>4</sup> Calculated by Project Engineer based on site specific design and HRT



**Lone Oak #1 Dairy Digester Pipeline Project**  
Mass Balance Tables

BASELINE																		
Herd Information					Manure Excreted			Collection Rates		Collection Quantities		Solids Removal				To Storage		
Animal Type	Number of Animals	Breed	Housing	Animal Weight (kg)	Volatile Solids Excreted (kg / day / 1000kg mass) <sup>1</sup>	Volatile Solids (lbs/day)	Total Solids (lbs/day) <sup>2</sup>	% TS/VS Deposited on Land	% TS/VS Collected by Manure System	Pounds TS/ Day	Pounds VS/Day	Separation Type	TS/VS Separated (% of Gross Excreted) <sup>3</sup>	Total Solids Removed (lbs/day)	Volatile Solids Removed (lbs/day)	Total Solids (lbs/day)	Volatile Solids (lbs/day)	Total Fluid to Storage (gal/day)
Milking Cow	4,200	Holstein	Freestall	680	11.41	71,842	95,789	20%	80%	76,631	57,474	None	0.0%	-	-	76,631	57,474	
Dry Cow	700	Holstein	Open Lot	684	5.56	5,869	7,825	70%	30%	2,348	1,761	None	0.0%	-	-	2,348	1,761	
Heifer	4,500	Holstein	Open Lot	407	8.44	34,079	45,438	70%	30%	13,631	10,224	None	0.0%	-	-	13,631	10,224	
						<b>111,790</b>	<b>149,053</b>			<b>92,611</b>	<b>69,458</b>					<b>92,611</b>	<b>69,458</b>	<b>462,000</b>

PROJECT															
Herd Information					Manure Excreted			Collection Rates		Collection Quantities		Solids Removal			
Animal Type	Number of Animals	Breed	Housing	Animal Weight (kg)	Volatile Solids Excreted (kg / day / 1000kg mass) <sup>1</sup>	Volatile Solids (lbs/day)	Total Solids (lbs/day) <sup>2</sup>	% TS/VS Deposited on Land	TS/VS Collected (% of Gross Excreted)	Total Solids (lbs/day)	Volatile Solids (lbs/day)	Separation Type	TS/VS Separated (% of Gross Excreted) <sup>3</sup>	Total Solids Removed (lbs/day)	Volatile Solids Removed (lbs/day)
Milking Cow	4,200	Holstein	Freestall	680	11.41	71,842	95,789	20%	80%	76,631	57,474	Vibrating Screen	12.0%	11,495	8,621
Dry Cow	700	Holstein	Open Lot	684	5.56	5,869	7,825	70%	30%	2,348	1,761	Vibrating Screen	4.5%	352	264
Heifer	4,500	Holstein	Open Lot	407	8.44	34,079	45,438	70%	30%	13,631	10,224	Vibrating Screen	4.5%	2,045	1,534
						111,790	149,053			92,611	69,458			13,892	10,419

Digester Influent				Digestion					Digester Effluent		
TS/VS Entering Digester (% of Gross Excreted )	TS Entering Digester (lbs/day)	VS Entering Digester (lbs/day)	Total Fluid Entering Digester (gal/day)	VS Destruction Rate <sup>4</sup>	VS Destroyed (lbs/day)	SCF Biogas / lbs VS Destroyed	Biogas Production (scf/day @ 60% CH4)	Biogas Production (MMBTU/yr)	TS Exiting Digester (lbs/day)	VS Exiting Digester (lbs/day)	Total Fluid Exiting Digester (gal/day)
68.0%	65,137	48,853	462,000	42%	20,518	14.3	293,408	64,256	44,619	28,334	459,027
25.5%	1,995	1,497		42%	629	14.3	8,989	1,968	1,367	868	
25.5%	11,587	8,690		42%	3,650	14.3	52,193	11,430	7,937	5,040	
	<b>78,719</b>	<b>59,039</b>	<b>462,000</b>		<b>24,796</b>		<b>354,589</b>	<b>77,655</b>	<b>53,922</b>	<b>34,243</b>	<b>459,027</b>

Separator Efficiency Table*	
Type	VS Removal Rate (% of Gross Collected)
No Solid Separation	0%
Weeping Wall	45%
Stationary Screen	17%
Vibrating Screen	15%

\*Per ARB's GHG Calculator

<sup>1</sup> Per ARB's GHG Calculator<sup>2</sup> Assumes 75% of Totals Solids is Volatile<sup>3</sup> TS/VS Separated shown as a "% of gross manure excreted" to match ARB's GHG Calculator. Separator efficiencies shown as a "% of gross manure collected" also referenced in the Separator Efficiency Table<sup>4</sup> Calculated by Project Engineer based on site specific design and HRT



**Poplar Lane Dairy Digester Pipeline Project**  
Mass Balance Tables

BASELINE																		
Herd Information					Manure Excreted			Collection Rates		Collection Quantities		Solids Removal				To Storage		
Animal Type	Number of Animals	Breed	Housing	Animal Weight (kg)	Volatile Solids Excreted (kg / day / 1000kg mass) <sup>1</sup>	Volatile Solids (lbs/day)	Total Solids (lbs/day) <sup>2</sup>	% TS/VS Deposited on Land	% TS/VS Collected by Manure System	Pounds TS/ Day	Pounds VS/Day	Separation Type	TS/VS Separated (% of Gross Excreted) <sup>3</sup>	Total Solids Removed (lbs/day)	Volatile Solids Removed (lbs/day)	Total Solids (lbs/day)	Volatile Solids (lbs/day)	Total Fluid to Storage (gal/day)
Milking Cow	2,126	Holstein	Freestall	680	11.41	36,366	48,488	20%	80%	38,790	29,093	Stationary Screen	13.6%	6,594	4,946	32,196	24,147	
Dry Cow	284	Holstein	Open Lot	684	5.56	2,381	3,175	70%	30%	952	714	Stationary Screen	5.1%	162	121	791	593	
Heifer	2,115	Holstein	Open Lot	407	8.44	16,017	21,356	70%	30%	6,407	4,805	Stationary Screen	5.1%	1,089	817	5,318	3,988	
						<b>54,764</b>	<b>73,018</b>			<b>46,149</b>	<b>34,612</b>					<b>38,304</b>	<b>28,728</b>	<b>287,010</b>

PROJECT															
Herd Information					Manure Excreted			Collection Rates		Collection Quantities		Solids Removal			
Animal Type	Number of Animals	Breed	Housing	Animal Weight (kg)	Volatile Solids Excreted (kg / day / 1000kg mass) <sup>1</sup>	Volatile Solids (lbs/day)	Total Solids (lbs/day) <sup>2</sup>	% TS/VS Deposited on Land	TS/VS Collected (% of Gross Excreted)	Total Solids (lbs/day)	Volatile Solids (lbs/day)	Separation Type	TS/VS Separated (% of Gross Excreted) <sup>3</sup>	Total Solids Removed (lbs/day)	Volatile Solids Removed (lbs/day)
Milking Cow	2,126	Holstein	Freestall	680	11.41	36,366	48,488	20%	80%	38,790	29,093	Stationary Screen	13.6%	6,594	4,946
Dry Cow	284	Holstein	Open Lot	684	5.56	2,381	3,175	70%	30%	952	714	Stationary Screen	5.1%	162	121
Heifer	2,115	Holstein	Open Lot	407	8.44	16,017	21,356	70%	30%	6,407	4,805	Stationary Screen	5.1%	1,089	817
						54,764	73,018			46,149	34,612			7,845	5,884

Digester Influent				Digestion					Digester Effluent		
TS/VS Entering Digester (% of Gross Excreted )	TS Entering Digester (lbs/day)	VS Entering Digester (lbs/day)	Total Fluid Entering Digester (gal/day)	VS Destruction Rate <sup>4</sup>	VS Destroyed (lbs/day)	SCF Biogas / lbs VS Destroyed	Biogas Production (scf/day @ 60% CH4)	Biogas Production (MMBTU/yr)	TS Exiting Digester (lbs/day)	VS Exiting Digester (lbs/day)	Total Fluid Exiting Digester (gal/day)
66.4%	32,196	24,147		54%	13,039	14.3	186,462	40,835	19,156	11,108	
24.9%	791	593		54%	320	14.3	4,578	1,003	470	273	
24.9%	5,318	3,988		54%	2,154	14.3	30,797	6,745	3,164	1,835	
	<b>38,304</b>	<b>28,728</b>	<b>287,010</b>		<b>15,513</b>		<b>221,837</b>	<b>48,582</b>	<b>22,791</b>	<b>13,215</b>	<b>285,150</b>

Separator Efficiency Table*	
Type	VS Removal Rate (% of Gross Collected)
No Solid Separation	0%
Weeping Wall	45%
Stationary Screen	17%
Vibrating Screen	15%

\*Per ARB's GHG Calculator

<sup>1</sup> Per ARB's GHG Calculator<sup>2</sup> Assumes 75% of Totals Solids is Volatile<sup>3</sup> TS/VS Separated shown as a "% of gross manure excreted" to match ARB's GHG Calculator. Separator efficiencies shown as a "% of gross manure collected" also referenced in the Separator Efficiency Table<sup>4</sup> Calculated by Project Engineer based on site specific design and HRT



**River Ranch Dairy Digester Pipeline**  
Mass Balance Tables

BASELINE																		
Herd Information					Manure Excreted			Collection Rates		Collection Quantities		Solids Removal				To Storage		
Animal Type	Number of Animals	Breed	Housing	Animal Weight (kg)	Volatile Solids Excreted (kg / day / 1000kg mass) <sup>1</sup>	Volatile Solids (lbs/day)	Total Solids (lbs/day) <sup>2</sup>	% TS/VS Deposited on Land	% TS/VS Collected by Manure System	Pounds TS/ Day	Pounds VS/Day	Separation Type	TS/VS Separated (% of Gross Excreted) <sup>3</sup>	Total Solids Removed (lbs/day)	Volatile Solids Removed (lbs/day)	Total Solids (lbs/day)	Volatile Solids (lbs/day)	Total Fluid to Storage (gal/day)
Milking Cow	5,258	Holstein	Freestall	680	11.41	89,939	119,919	20%	80%	95,935	71,951	Weeping Wall	36.0%	43,171	32,378	52,764	39,573	
Dry Cow	548	Holstein	Open Lot	684	5.56	4,595	6,126	70%	30%	1,838	1,378	Weeping Wall	13.5%	827	620	1,011	758	
Heifer	5,787	Holstein	Open Lot	407	8.44	43,825	58,434	70%	30%	17,530	13,148	Weeping Wall	13.5%	7,889	5,916	9,642	7,231	
						143,114	190,819			117,205	87,904			52,742	39,557	64,463	48,347	

PROJECT															
Herd Information					Manure Excreted			Collection Rates		Collection Quantities		Solids Removal			
Animal Type	Number of Animals	Breed	Housing	Animal Weight (kg)	Volatile Solids Excreted (kg / day / 1000kg mass) <sup>1</sup>	Volatile Solids (lbs/day)	Total Solids (lbs/day) <sup>2</sup>	% TS/VS Deposited on Land	TS/VS Collected (% of Gross Excreted)	Total Solids (lbs/day)	Volatile Solids (lbs/day)	Separation Type	TS/VS Separated (% of Gross Excreted) <sup>3</sup>	Total Solids Removed (lbs/day)	Volatile Solids Removed (lbs/day)
Milking Cow	5,258	Holstein	Freestall	680	11.41	89,939	119,919	20%	80%	95,935	71,951	Weeping Wall	36.0%	43,171	32,378
Dry Cow	548	Holstein	Open Lot	684	5.56	4,595	6,126	70%	30%	1,838	1,378	Weeping Wall	13.5%	827	620
Heifer	5,787	Holstein	Open Lot	407	8.44	43,825	58,434	70%	30%	17,530	13,148	Weeping Wall	13.5%	7,889	5,916
						143,114	190,819			117,205	87,904			52,742	39,557


Digester Influent				Digestion					Digester Effluent		
TS/VS Entering Digester (% of Gross Excreted )	TS Entering Digester (lbs/day)	VS Entering Digester (lbs/day)	Total Fluid Entering Digester (gal/day)	VS Destruction Rate <sup>4</sup>	VS Destroyed (lbs/day)	SCF Biogas / lbs VS Destroyed	Biogas Production (scf/day @ 60% CH4)	Biogas Production (MMBTU/yr)	TS Exiting Digester (lbs/day)	VS Exiting Digester (lbs/day)	Total Fluid Exiting Digester (gal/day)
44.0%	52,764	39,573		52%	20,578	14.3	294,267	64,444	32,186	18,995	
16.5%	1,011	758		52%	394	14.3	5,637	1,235	617	364	
16.5%	9,642	7,231		52%	3,760	14.3	53,771	11,776	5,881	3,471	
	64,463	48,347	830,400		25,141		359,510	78,733	39,322	23,207	827,386

Separator Efficiency Table*	
Type	VS Removal Rate (% of Gross Collected)
No Solid Separation	0%
Weeping Wall	45%
Stationary Screen	17%
Vibrating Screen	15%

\*Per ARB's GHG Calculator

<sup>1</sup> Per ARB's GHG Calculator<sup>2</sup> Assumes 75% of Totals Solids is Volatile<sup>3</sup> TS/VS Separated shown as a "% of gross manure excreted" to match ARB's GHG Calculator. Separator efficiencies shown as a "% of gross manure collected" also referenced in the Separator Efficiency Table<sup>4</sup> Calculated by Project Engineer based on site specific design and HRT





General Notes

Attachment 2 - Drawing #1

All pipeline is within private property except certain Public Right of Way crossings marked by

HDPE SDR 21, 10", 9 PSI


HDPE SDR 21, 8", 10 PSI

HDPE SDR 21, 6", 11 PSI

HDPE SDR 21, 4", 13 PSI

Potential Future Expansions

Southern California Gas Company Pipeline



**MAAS**  
ENERGY WORKS

Firm Address

3711 Meadowview Dr.  
Redding, CA, 96002

Project Name and Address

Lakeside Pipeline Project


Date  
6/8/18

Drawn By  
Hudson Davis

Version

2.7





General Notes	
Attachment #2 - Drawing #2	
Biogas Pipeline	
Southern California Gas Transmission Line	
Southern California Gas Pipeline Extension	
Area Leased and Operated by Southern California Gas	
Area Owned and Operated by Lakeside Pipeline, LLC	
Firm Address 3711 Meadowview Dr. Redding, CA, 96002	
Project Name and Address Lakeside Pipeline Point of Receipt and Clean Up Equipment Drawing	
Date 5/3/18	Version 2.7
Drawn By Nathan Nisly	



# DECADE DAIRY DIGESTER

## BENCHMARK

THE TOPOGRAPHIC SURVEY WAS PERFORMED UTILIZING GLOBAL POSITIONING SYSTEM OBSERVATIONS. DISTANCES AND NUMBERS SHOWN ARE TO BE CONSIDERED GROUND VALUES. BENCHMARK AND CONTROL SHOWN ON CONTROL PLAN SHEET. THE BENCHMARK AND VERTICAL ELEVATIONS WERE DERIVED FROM THE NGS ONLINE POSITIONING SERVICE (OPUS), AND IS SHOWN ON THE NAVD 88 DATUM UTILITIZING THE GEOID 09 AS THE VERTICAL MODEL.

## PRESERVATION OF MONUMENTS

PURSUANT TO SECTIONS 8771(B) AND 8771(C) OF THE GOVERNMENT CODE, ANY MONUMENTS THAT CONTROL THE LOCATION OF BOUNDARIED, OR OTHERWISE PROVIDE HORIZONTAL OR VERTICAL SURVEY CONTROL WITHIN THE CONSTRUCTION AREA, SHALL BE LOCATED AND REFERENCED PRIOR TO CONSTRUCTION, AND A CORNER RECORD OR RECORD OF SURVEY OF THE REFERENCES SHALL BE FILED WITH THE COUNTY SURVEYOR.

PERMANENT MONUMENTATION SHALL BE SET TO PERPETUATE THE LOCATION OF ANY MONUMENT WHICH COULD BE DAMAGED OR DESTROYED, AND A CORNER RECORD OR RECORD OF SURVEY SHALL BE FILED WITH THE COUNTY SURVEYOR PRIOR TO THE RECORDING OF A CERTIFICATE OF COMPLETION FOR THE PROJECT.

## DUST CONTROL NOTES

CONTRACTOR IS REQUIRED TO COMPLY WITH PROJECT APPROVED DUST CONTROL PLAN

## STORMWATER (SWPPP) NOTES

CONTRACTOR IS REQUIRED TO COMPLY WITH PROJECT APPROVED STORMWATER POLLUTION PREVENTION PLAN




VICINITY MAP

SCALE 1" : 2 MI

## SHEET REFERENCE


### SECTIONS:

SECTION NAME  
SHEET NUMBER



### DETAILS:

DETAIL NAME  
SHEET NUMBER



## CONTACT INFO

ENGINEER:  
CRAIG HARTMAN, RCE 73837  
HARTMAN ENGINEERING, INC.  
3121 W. CERES CT.  
VISALIA, CA 93291  
(559) 563-0181

DAIRY CONTACT:  
ERIC WESTRA  
3313 AVE 256  
TULARE, CA 93274

## SHEET INDEX

### GENERAL NOTES

- A.1 COVER SHEET
- A.2 GENERAL NOTES
- A.3 SITE PLAN - DAIRY
- A.4 SITE PLAN - DIGESTER

### CIVIL DRAWINGS

- C.1 GRADING DETAILS

### DIGESTER DRAWINGS

- D.1 COVER SYSTEM
- D.2 SLURRY SYSTEM
- D.3 MIXERS
- D.4 DETAILS

### LINER DRAWINGS

- L.1 LINER - DETAILS
- L.2 LINER - DETAILS
- L.3 LINER - DETAILS

PROJECT:

DECADE  
DAIRY  
DIGESTER

CLIENT:  
DECADE DAIRY  
3313 AVE 256  
TULARE, CA 93274

COVER SHEET

REVISION LOG:



Know what's below.  
Call before you dig.

PLOT DATE: 01/08/18

JOB NO.: 17003

SCALE: AS SHOWN

SHEET NO.: A.1 0107



SPECIFICATIONS FOR ENGINEERED FILL MATERIAL OF ABOVE GRADE EMBANKMENTS OR AS REQUIRED

TEST PARAMETER	TEST METHOD	FREQUENCY	ACCEPTANCE CRITERIA
Compaction Curves	ASTM D1557 (Modified Proctor)	Change in material	N/A
Grain Size Distribution	ASTM D422 (Sieve)	Change in material	At least 30% passing No. 200 U.S. Standard Sieve. Per Specifications (1)
Soil Classification	ASTM D2487 (USCS)	Change in material	Suitable for compaction (1)
Maximum Particle Size	ASTM D422 (Sieve)	Change in material	½ inch, ¼ top 6 inches
Maximum Water soluble Sulfate (SO <sup>4-</sup> ) in Soil (Concrete Slab locations)	ASTM C1580	Change in material	0.2% by weight
Site Preparation Specifications:			
1. Clearing: Prior to earthwork operations, the area to be developed should be stripped of vegetation, organic topsoil, and cleared of cow waste and miscellaneous debris from the proposed construction areas. Deeper clearing may be required in localized areas. The actual depth of clearing should be reviewed by a licensed Geotechnical Engineer at the time of construction. The limits of stripping and clearing should be at least five feet bey ond the limits of construction.			
2. Compaction: The scarified subgrade and subsequent fill placed at the site should be moisture conditioned to near optimum moisture content, and compacted to at least and 90 percent for 2:1 side slope pond of maximum dry density as determined by ASTM test method D1557.			
3. Material for fill: Fill should consist of select material. Native soil, free from organic, vegetation, and rocks or cobbles larger than three inches, may be used as fill at the site. Import material must be reviewed by licensed Geotechnical Engineer prior to transport to the site.			
4. Fill placement: Fill material should be moisture-conditioned to +/- 2% of the optimum moisture content prior to compaction. Fill material with excessive moisture should be allowed to dry prior to compaction or be mixed with dry soil to bring the fill to a workable moisture content. Fill should be placed in lev el lifts not exceeding a loose, uncompacted thickness of eight inches, and compacted as engineered fill.			
Sub-grade requirements for fill only:			
-Over Excavate for minimum 1 ft. to meet Engineered Fill Borrow Material Guidelines and Pond Liner Sub-grade requirements			
-Well mixed soil			
-6 in max lifts			
-Upper 6 inches is of fine-finished soil particles no greater than ¼ in. +			
Notes:			
1 Field tests shall not be required, but fill borrow material specifications must meet the acceptance criteria outlined in Table 1.			
2 Refer to Geotechnical Report			

NOTES:

THE APPROVED WORK PLAN WHICH INCLUDES THE CONSTRUCTION QUALITY ASSURANCE PLAN, OPERATION, MAINTENANCE AND MONITORING PLAN, CONSTRUCTION DRAWINGS, AND SOILS REPORT TOGETHER AS A PACKAGE ARE THE COMPLETE SPECIFICATIONS REQUIRED FOR CONSTRUCTION OF THE POND AND LINER SYSTEM.

FILL TEST SPECIFICATIONS FOR SUB-GRADE

TEST PARAMETER	TEST METHOD (1)	FREQUENCY	ACCEPTANCE CRITERIA
Uncompacted Lift Thickness	Visual Observation	Continuous	8-in. (1)
Construction Oversight	Visual Observation	Continuous	Maximum particle size 1/2 inch.
In-Place Moisture Alternative Method	ASTM D2216 (Oven Dry)	1 per every 10 Nuclear tests	+/-2% of Optimum Moisture Content per ASTM D1557
In-Place Moisture Rapid Field Methods (2, 3, 4)	ASTM D6938 (Nuclear Method)	3 per acre per lift, min. 2 per day	+/-2% of Optimum Moisture Content per ASTM D1557
In-Place Density Alternate Method	ASTM D2937(Drive Cylinder)	1 per every 10 Nuclear tests	90% of Maximum Dry Density per ASTM D1557
In-Place Density Rapid Field Methods (1)	ASTM D6938 (Nuclear Method)	3 per acre per lift, min. 2 per day	90% of Maximum Dry Density per ASTM D1557
Subgrade Thickness	Surveying Measurement	At 50-foot centers	Minimum 1 ft. (1)
Clod Size	Visual Observation	Continuous	Per Specification

Notes:

See earthwork section for anchor trench, excavation, backfill, and compaction requirements.

1 ASTM Test Method, unless otherwise noted. Results of all tests performed to be reported as per method reporting criteria.

2 The sub-grade shall be scarified to a depth of 1 ft. lower than finished grade, compacted, and tested in accordance with the requirements of this table.

3 Must be verified by ASTM D2216 (Oven) overnight method once every day or once per change in material

4 Must be verified by ASTM D2937 (Dry Cylinder) twice per day or per change in material

5 Calibration Procedure: ASTM D7013-04: Standard Guide for Nuclear Surface Moisture and Density Gauge Calibration Facility Set-up

POND SPECIFICATIONS FOR SUBGRADES CUT BELOW GROUND (For Slopes 2:1 or shallower)

**Side Slopes:** The certified Civil Engineer/CQA Chief Officer shall walk final side slopes after cut by heavy equipment and confirm no SW or SP soils and no loose soils. All SW, SP, or soils that are not amenable to a firm and unyielding subgrade shall be removed and replaced down to a minimum 3 ft. below sloped surface. Any soils removed and replaced shall meet the Engineered Fill requirements in Table 1.

**Pond Bottom:** 1. An as-built survey of the pond bottom shall take place after subgrade construction to insure minimum slopes are achieved. Pond Bottom shall be tested per criteria below. Any soils not meeting the requirements below (i.e. that is not firm and unyielding) shall be removed and replaced down to a minimum 2 ft. Any soils removed and replaced shall meet the Engineered Fill requirements in Table 1. The Civil Engineer may make determination of soils meeting requirements or not based upon visual inspection which shall be included in the Subgrade Certification Report and signed and sealed by a Civil Engineer and CQA Officer.

TEST PARAMETER	TEST METHOD (1)	FREQUENCY	ACCEPTANCE CRITERIA
In-Place Density Rapid Field Methods (1)	ASTM D6938 (Nuclear)	3 per acre	90% of Maximum Dry Density per ASTM D1557
In-Place Moisture Rapid Field Methods (2, 3, 4)	ASTM D6938 (Nuclear Methods)	3 per acre per lift, min. 2 per day	+/-2% of Optimum Moisture Content per ASTM D1557
Construction Oversight	Visual Observation	Continuous	Maximum particle size 1/2 inch.
Subgrade Slope	Surveying Measurement	200 ft. maximum grid	Min 1%

60 MIL HDPE GEOMEMBRANE CONSTRUCTION QUALITY ASSURANCE (CQA)

TEST PARAMETER	TEST METHOD	FREQUENCY	ACCEPTANCE CRITERIA
Thickness (min. ave.) -Lowest individual for 8 out of 10 values -Lowest individual for any of the 10 values	ASTM D5994	1 per lot or 1 per 70,000 ft <sup>2</sup> , whichever is greater	Nom. (-5%)  -10%  -15%
Tensile Properties -yield strength -break strength -strain at yeild -break strength	ASTM D6693 Type IV	1 per lot or 1 per 70,000 ft <sup>2</sup> , whichever is greater	≥126 lb./in. ≥90 lb./in. ≥12% ≥100%
Puncture Resistance	ASTM D4833	1 per lot or 1 per 70,000 ft <sup>2</sup> , whichever is greater	108 lb. (min.)
Tear Resistance	ASTM D1004, Die C	1 per lot or 1 per 70,000 ft <sup>2</sup> , whichever is greater	42 lb. (min.)
Interface Shear -60-mil HDPE/subgrade soil -Drainage geocomposite	ASTM D5321 ASTM D6243	2 tests or 1 per 200,000 ft <sup>2</sup> , whichever is greater	
Seam Shear	ASTM D6392	1 test per 500 lineal feet or per GRI GM-14 and 20.	95% of min. yield strength
Seam Peel -Extrusion -Fusion	ASTM D6392	1 test per 500 lineal feet or per GRI GM-14 and 20.	72% yield & ftb (1)
Non-destructive Seam Test	ASTM D5820 (Pressure Test)	Continuous	35 psi for 5 min.
	ASTM D5641 (Vacuum Box)		5 psi for 15 sec.
	ASTM D5641 (Spark Test)		No Spark
Electric Leak Location	ASTM D7002 (Water Puddle)	Once on constructed liner	Max 1 mm. diameter hole sensitivity
	ASTM D6747 (Selection Process)		
	ASTM D7007 (Water /Earth)		Max 6 mm. diameter hole sensitivity
	ASTM D7240 (Spark Test 2011)		
Notes:			
ftb: Film Tear Bond			



113 N. CHURCH ST,  
SUITE 521  
VISALIA, CA 93291  
(559) 563-0181



PROJECT:

DECADE  
DAIRY  
DIGESTER

CLIENT:  
DECADE DAIRY  
3313 AVE 256  
TULARE, CA 93274

GENERAL NOTES  
CONSTRUCTION

REVISION LOG:


PLOT DATE: 01/08/18

JOB NO.: 17003

SCALE: AS SHOWN

SHEET NO.: A2 0108





113 N. CHURCH ST,  
SUITE 521  
VISALIA, CA 93291  
(559) 563-0181



PROJECT:

DECADE  
DAIRY  
DIGESTER

CLIENT:  
DECADE DAIRY  
3313 AVE 256  
TULARE, CA 93274

SITE PLAN  
DAIRY

REVISION LOG:

PLOT DATE: 01/08/18

JOB NO.: 17003

SCALE: AS SHOWN

SHEET NO.: A3 0109





113 N. CHURCH ST,  
SUITE 521  
VISALIA, CA 93291  
(559) 563-0181



PROJECT:

## DECADE DAIRY DIGESTER

CLIENT:  
DECADE DAIRY  
3313 AVE 256  
TULARE, CA 93274

## SITE PLAN

DIGESTER



REVISION LOG:

PLOT DATE: 01/08/18


JOB NO.: 17003

SCALE: AS SHOWN

SHEET NO.: A4 0110








A ANCHOR TRENCH / SUMP PROFILE VIEW


N.T.S.

DIMENSION TABLE (FT.)	
LETTER	POND
L	1.7'
M.1	2.7'
U	20'
R	1.5'
S	3'
T	3'
X	30'
Y	30'
Z	5.5'



B SUMP PLAN VIEW

N.T.S.



C SIDE SLOPE TRENCH

N.T.S.



113 N. CHURCH ST,  
SUITE 521  
VISALIA, CA 93291  
(559) 563-0181



PROJECT:

DECADE  
DAIRY  
DIGESTER

CLIENT:  
DECADE DAIRY  
3313 AVE 256  
TULARE, CA 93274

GRADING DETAIL  
DIGESTER

REVISION LOG:


PLOT DATE: 01/08/18

JOB NO.: 17003

SCALE: AS SHOWN

SHEET NO.: C.1 0111






**A BALLAST TUBE DETAIL**


N.T.S.

DESCRIPTION	LOCATION	MATERIAL	THICKNESS (MIN)	TOP FINISH	BOTTOM FINISH
COVER	TOP	HDPE	80 MIL	SMOOTH	SMOOTH



**C HDPE COVER-SMOOTH WELDS**


N.T.S.




**B BIO-GAS PIPING DETAIL**

N.T.S.

- NOTES:
1. GAS VENTS AROUND PERIPHERY OF LAGOON @ MAX. 40' O.C.
  2. STRAP NOT WELDED TO BIO-GAS HEADER PIPE.
  3. WRAP 60 MIL PRIMARY LINER OVER CONCRETE & EXTRUSION WELD.



113 N. CHURCH ST,  
SUITE 521  
VISALIA, CA 93291  
(559) 563-0181



PROJECT:

**DECADE  
DAIRY  
DIGESTER**

CLIENT:  
DECADE DAIRY  
3313 AVE 256  
TULARE, CA 93274

COVER SYSTEM  
DIGESTER

REVISION LOG:


PLOT DATE: 01/08/18

JOB NO.: 17003


SCALE: AS SHOWN

SHEET NO.: D.1 0112







**A SLUDGE REMOVAL PIPE ANCHOR DETAIL**  
NOTE: ANCHOR TO BE USED ON HORIZONTAL SURFACES ONLY, AT BOTTOM OF LAGOON N.T.S.



**B TYPICAL PIPE STRAP-DOWN DETAIL**  
NOTE: MAXIMUM 10' O.C. SPACING BETWEEN PIPE STRAP-DOWNS, U.N.O. N.T.S.



**C TYPICAL SLUDGE PIPE-PROFILE**  
N.T.S.



**D BAFFLE SECTION**  
N.T.S.



113 N. CHURCH ST,  
SUITE 521  
VISALIA, CA 93291  
(559) 563-0181



PROJECT:  
**DECADE DAIRY  
DIGESTER**


CLIENT:  
DECADE DAIRY  
3313 AVE 256  
TULARE, CA 93274

SLURRY REMOVAL  
SYSTEM  
DIGESTER

REVISION LOG:


PLOT DATE: 01/08/18  
JOB NO.: 17003  
SCALE: AS SHOWN  
SHEET NO.: D2 0118






MIXER - HATCH

N.T.S.




AIR INJECTION & MIXER HATCH

N.T.S.




MIXER - PLAN VIEW

N.T.S.




MIXER - ISOMETRIC W/FLOAT IN PLACE

N.T.S.



MIXER - ISOMETRIC

N.T.S.



MIXER - SIDE VIEW

N.T.S.

MIXER - FRONT VIEW

N.T.S.



113 N. CHURCH ST,  
SUITE 521  
VISALIA, CA 93291  
(559) 563-0181



PROJECT:

**DECADE  
DAIRY  
DIGESTER**

CLIENT:  
DECADE DAIRY  
3313 AVE 256  
TULARE, CA 93274

MIXER  
DETAILS

REVISION LOG:



PLOT DATE: 01/08/18

JOB NO.: 17003

SCALE: AS SHOWN


SHEET NO.: D.3 0114  
pg 112






MOISTURE TRAP DETAIL

N.T.S.




BIO-GAS VALVE

N.T.S.




BALL VALVE JUNCTION

N.T.S.




BOLLARD DETAIL

N.T.S.



113 N. CHURCH ST,  
SUITE 521  
VISALIA, CA 93291  
(559) 563-0181



PROJECT:

DECADE  
DAIRY  
DIGESTER

CLIENT:  
DECADE DAIRY  
3313 AVE 256  
TULARE, CA 93274

DETAILS

REVISION LOG:


PLOT DATE: 01/08/18

JOB NO.: 17003


SCALE: AS SHOWN

SHEET NO.: D4 0115





113 N. CHURCH ST,  
SUITE 521  
VISALIA, CA 93291  
(559) 563-0181



PROJECT:

**DECADE  
DAIRY  
DIGESTER**

CLIENT:  
DECADE DAIRY  
3313 AVE 256  
TULARE, CA 93274

GENERAL NOTES  
LINER  
DETAILS


REVISION LOG:

PLOT DATE: 01/08/18


JOB NO.: 17003

SCALE: AS SHOWN

SHEET NO.: L1 0116




**FRONT VIEW**




**SIDE VIEW**

**LCRS, LYSIMETER AND DRAINAGE SUMP PROFILE**




**DIGESTER ANCHOR TRENCH DETAIL**

NOTES: 1. CONTRACTOR TO USE ANCHOR SYSTEM OR PROVIDE DETAILS AND DESIGN FOR ALTERNATIVE TO BE APPROVED BY ENGINEER. N.T.S.



**HDPE CROSS SECTION**

N.T.S.




**TYPICAL PERFORATION DETAIL**

N.T.S.




OPTIONAL TIER 1 DOUBLE LINER-LAYERING SYSTEM WITH DRAIN LINER VERIFY WITH OWNER


SMOOTH/STUDDED/ 60-NET-60 LINER LAYERS					
DESCRIPTION	LOCATION	MATERIAL	THICKNESS (MIN)	TOP FINISH	BOTTOM FINISH
PRIMARY LINER	TOP	HDPE	60 MIL	SMOOTH	SMOOTH CONDUCTIVE
DRAINAGE NET	MIDDLE	HDPE	200 MIL	N/A	N/A
SECONDARY LINER	BOTTOM	HDPE	60 MIL	SMOOTH	SMOOTH




**A** DOUBLE LAYER 60-NET-60  
DOUBLE LAYER WITH DRAIN LINER N.T.S.



**B** HDPE LINER-SMOOTH WELDS N.T.S.




**C** 3'X3' DRAIN PATCH WELD N.T.S.



DRAIN LINER SMOOTH END WELD PATCH


**C** 3'X3' DRAIN PATCH WELD N.T.S.

**D** AGRU DRAIN LINER END/END WELD  
NOTE: AGRU DRAIN LINER DOES NOT HAVE STUDS ALONG THE EDGE SO EDGE/EDGE SEAMS DO NOT REQUIRE DRINGING OR CAP. N.T.S.



2' WIDE STRIP OF 200 MIL GEONET. TACK WELD AT 8'

**C** 3'X3' DRAIN PATCH



NOTE: CQA OFFICER IS RESPONSIBLE TO ADD PATCHES AS NEEDED FOR FLOW

**E** AGRU DRAIN LINER CROSS SEAM NET PLAN VIEW  
NOTE: TYPICAL OF ALL DRAIN LINERS N.T.S.



113 N. CHURCH ST,  
SUITE 521  
VISALIA, CA 93291  
(559) 563-0181




PROJECT:  
**DECADE DAIRY  
DIGESTER**

CLIENT:  
DECADE DAIRY  
3313 AVE 256  
TULARE, CA 93274


LINER  
DETAILS

PLOT DATE:	01/08/18
JOB NO.:	17003
SCALE:	AS SHOWN
SHEET NO.:	D2 0117






**A BOOT SKIRT** N.T.S.



**B BOOTLESS PIPE PENETRATION** N.T.S.



**C VENT ORIFICE (ISOMETRIC VIEW)** N.T.S.



113 N. CHURCH ST.  
SUITE 521  
VISALIA, CA 93291  
(559) 563-0181



PROJECT:

**DECADE  
DAIRY  
DIGESTER**

CLIENT:  
DECADE DAIRY  
3313 AVE 256  
TULARE, CA 93274

L I N E R  
D E T A I L S

REVISION LOG:

PLOT DATE: 01/08/18

JOB NO.: 17003

SCALE: AS SHOWN

SHEET NO.: L3 0118



# CLEAR LAKE DAIRY DIGESTER

## BENCHMARK

THE TOPOGRAPHIC SURVEY WAS PERFORMED UTILIZING GLOBAL POSITIONING SYSTEM OBSERVATIONS. DISTANCES AND NUMBERS SHOWN ARE TO BE CONSIDERED GROUND VALUES. BENCHMARK AND CONTROL SHOWN ON CONTROL PLAN SHEET. THE BENCHMARK AND VERTICAL ELEVATIONS WERE DERIVED FROM THE NGS ONLINE POSITIONING SERVICE (OPUS), AND IS SHOWN ON THE NAVD 88 DATUM UTILITIZING THE GEOID 09 AS THE VERTICAL MODEL.

## PRESERVATION OF MONUMENTS

PURSUANT TO SECTIONS 8771(B) AND 8771(C) OF THE GOVERNMENT CODE, ANY MONUMENTS THAT CONTROL THE LOCATION OF BOUNDARIED, OR OTHERWISE PROVIDE HORIZONTAL OR VERTICAL SURVEY CONTROL WITHIN THE CONSTRUCTION AREA, SHALL BE LOCATED AND REFERENCED PRIOR TO CONSTRUCTION, AND A CORNER RECORD OR RECORD OF SURVEY OF THE REFERENCES SHALL BE FILED WITH THE COUNTY SURVEYOR.


PERMANENT MONUMENTATION SHALL BE SET TO PERPETUATE THE LOCATION OF ANY MONUMENT WHICH COULD BE DAMAGED OR DESTROYED, AND A CORNER RECORD OR RECORD OF SURVEY SHALL BE FILED WITH THE COUNTY SURVEYOR PRIOR TO THE RECORDING OF A CERTIFICATE OF COMPLETION FOR THE PROJECT.

## DUST CONTROL NOTES

CONTRACTOR IS REQUIRED TO COMPLY WITH PROJECT APPROVED DUST CONTROL PLAN

## STORMWATER (SWPPP) NOTES

CONTRACTOR IS REQUIRED TO COMPLY WITH PROJECT APPROVED STORMWATER POLLUTION PREVENTION PLAN




VICINITY MAP

SCALE 1" : 2 MI

## SHEET REFERENCE

### SECTIONS:

SECTION NAME  
SHEET NUMBER



### DETAILS:

DETAIL NAME  
SHEET NUMBER



B  
C.3

## CONTACT INFO

ENGINEER:  
CRAIG HARTMAN, RCE 73837  
HARTMAN ENGINEERING, INC.  
3121 W. CERES CT.  
VISALIA, CA 93291  
(559) 563-0181

## SHEET INDEX

### GENERAL NOTES

- A.1 COVER SHEET
- A.2 GENERAL NOTES
- A.3 SITE PLAN - DAIRY
- A.4 SITE PLAN - DIGESTER

### CIVIL DRAWINGS


- C.1 GRADING DETAILS

### DIGESTER DRAWINGS

- D.1 COVER SYSTEM
- D.2 SLURRY SYSTEM
- D.3 MIXERS
- D.4 DETAILS

### LINER DRAWINGS

- L.1 LINER - DETAILS
- L.2 LINER - DETAILS
- L.3 LINER - DETAILS



113 N. CHURCH ST,  
SUITE 521  
VISALIA, CA 93291  
(559) 563-0181



### PROJECT:

**CLEAR LAKE  
DAIRY  
DIGESTER**

### CLIENT:

DECADE DAIRY  
3313 AVE 256  
TULARE, CA 93274

COVER SHEET

REVISION LOG:



Know what's below.  
Call before you dig.

PLOT DATE: 06/15/2018

JOB NO.: 17003

SCALE: AS SHOWN

SHEET NO.: A.1 0119



SPECIFICATIONS FOR ENGINEERED FILL MATERIAL OF ABOVE GRADE EMBANKMENTS OR AS REQUIRED

TEST PARAMETER	TEST METHOD	FREQUENCY	ACCEPTANCE CRITERIA
Compaction Curves	ASTM D1557 (Modified Proctor)	Change in material	N/A
Grain Size Distribution	ASTM D422 (Sieve)	Change in material	At least 30% passing No. 200 U.S. Standard Sieve. Per Specifications (1)
Soil Classification	ASTM D2487 (USCS)	Change in material	Suitable for compaction
Maximum Particle Size	ASTM D422 (Sieve)	Change in material	½ inch, ¼ top 6 inches
Maximum Water soluble Sulfate (SO <sup>-</sup> ) in Soil (Concrete Slab locations)	ASTM C1580	Change in material	0.2% by weight

Site Preparation Specifications:
1. Clearing: Prior to earthwork operations, the area to be developed should be stripped of vegetation, organic topsoil, and cleared of cow waste and miscellaneous debris from the proposed construction areas. Deeper clearing may be required in localized areas. The actual depth of clearing should be reviewed by a licensed Geotechnical Engineer at the time of construction. The limits of stripping and clearing should be at least five feet beyond the limits of construction.
2. Compaction: The scarified subgrade and subsequent fill placed at the site should be moisture conditioned to near optimum moisture content, and compacted to at least and 90 percent for 2:1 side slope pond of maximum dry density as determined by ASTM test method D1557.
3. Material for fill: Fill should consist of select material. Native soil, free from organic, vegetation, and rocks or cobbles larger than three inches, may be used as fill at the site. Import material must be reviewed by licensed Geotechnical Engineer prior to transport to the site.
4. Fill placement: Fill material should be moisture-conditioned to +/- 2% of the optimum moisture content prior to compaction. Fill material with excessive moisture should be allowed to dry prior to compaction or be mixed with dry soil to bring the fill to a workable moisture content. Fill should be placed in level lifts not exceeding a loose, uncompacted thickness of eight inches, and compacted as engineered fill.
Sub-grade requirements for fill only:
-Over Excavate for minimum 1 ft. to meet Engineered Fill Borrow Material Guidelines and Pond Liner Sub-grade requirements
-Well mixed soil
-6 in max. lifts
-Upper 6 inches is of fine-finished soil particles no greater than ¼ in. +
Notes:
Field tests shall not be required, but fill borrow material specifications must meet the acceptance criteria outlined in Table 1.
Refer to Geotechnical Report

FILL TEST SPECIFICATIONS FOR SUB-GRADE

TEST PARAMETER	TEST METHOD	FREQUENCY	ACCEPTANCE CRITERIA
Uncompacted Lift Thickness	Visual Observation	Continuous	8-in.
Construction Oversight	Visual Observation	Continuous	Maximum particle size 1/2 inch.
In-Place Moisture Alternative Method	ASTM D2216 (Oven Dry)	1 per every 10 Nuclear tests	+/- 2% of Optimum Moisture Content per ASTM D1557
In-Place Moisture Rapid Field Methods	ASTM D6938 (Nuclear Method)	3 per acre per lift, min. 2 per day	+/- 2% of Optimum Moisture Content per ASTM D1557
In-Place Density Alternate Method	ASTM D2937 (Drive Cylinder)	1 per every 10 Nuclear tests	90% of Maximum Dry Density per ASTM D1557
In-Place Density Rapid Field Methods	ASTM D6938 (Nuclear Method)	3 per acre per lift, min. 2 per day	90% of Maximum Dry Density per ASTM D1557
Subgrade Thickness	Surveying Measurement	At 50-foot centers	Minimum 1 ft.
Clod Size	Visual Observation	Continuous	Per Specification

Notes:
See earthwork section for anchor trench, excavation, backfill, and compaction requirements.
ASTM Test Method, unless otherwise noted. Results of all tests performed to be reported as per method reporting criteria.
The sub-grade shall be scarified to a depth of 1 ft. lower than finished grade, compacted, and tested in accordance with the requirements of this table.
Must be verified by ASTM D2216 (Oven) overnight method once every day or once per change in material
Must be verified by ASTM D2937 (Dry Cylinder) twice per day or per change in material
Calibration Procedure: ASTM D7013-04: Standard Guide for Nuclear Surface Moisture and Density Gauge Calibration Facility Setup

POND SPECIFICATIONS FOR SUBGRADES CUT BELOW GROUND (For Slopes 2:1 or shallower)
Side Slopes: The certified Civil Engineer/CQA Chief Officer shall walk final side slopes after cut by heavy equipment and confirm no SW or SP soils and no loose soils. All SW, SP, or soils that are not amenable to a firm and unyielding subgrade shall be removed and replaced down to a minimum 3 ft. below sloped surface. Any soils removed and replaced shall meet the Engineered Fill requirements in Table 1.
Pond Bottom: 1. An as-built survey of the pond bottom shall take place after subgrade construction to insure minimum slopes are achieved. Pond Bottom shall be tested per criteria below. Any soils not meeting the requirements below (i.e. that is not firm and unyielding) shall be removed and replaced down to a minimum 2 ft. Any soils removed and replaced shall meet the Engineered Fill requirements in Table 1. The Civil Engineer may make determination of soils meeting requirements or not based upon visual inspection which shall be included in the Subgrade Certification Report and signed and sealed by a Civil Engineer and CQA Officer.

TEST PARAMETER	TEST METHOD	FREQUENCY	ACCEPTANCE CRITERIA
In-Place Density Rapid Field Methods	ASTM D6938 (Nuclear)	3 per acre	90% of Maximum Dry Density per ASTM D1557
In-Place Moisture Rapid Field Methods	ASTM D6938 (Nuclear Methods)	3 per acre per lift, min. 2 per day	+/- 2% of Optimum Moisture Content per ASTM D1557
Construction Oversight	Visual Observation	Continuous	Maximum particle size 1/2 inch.
Subgrade Slope	Surveying Measurement	200 ft. maximum grid	Min 1%

60 MIL HDPE GEOMEMBRANE CONSTRUCTION QUALITY ASSURANCE (CQA)

TEST PARAMETER	TEST METHOD	FREQUENCY	ACCEPTANCE CRITERIA
Thickness (min. ave.) -Lowest individual for 8 out of 10 values -Lowest individual for any of the 10 values	ASTM D5994	1 per lot or 1 per 70,000 ft2, whichever is greater	Nom. (-5%) -10% -15%
Tensile Properties -yield strength -break strength -strain at yield -break strength	ASTM D6693 Type IV	1 per lot or 1 per 70,000 ft2, whichever is greater	≥126 lb./in. ≥90 lb./in. ≥12% ≥100%
Puncture Resistance	ASTM D4833	1 per lot or 1 per 70,000 ft <sup>2</sup> , whichever is greater	108 lb. (min.)
Tear Resistance	ASTM D1004, Die C	1 per lot or 1 per 70,000 ft2, whichever is greater	42 lb. (min.)
Interface Shear -60-mil HDPE/subgrade soil -Drainage geocomposite	ASTM D5321 ASTM D6243	2 tests or 1 per 200,000 ft2, whichever is greater	
Seam Shear	ASTM D6392	1 test per 500 lineal feet or per GRI GM-14 and 20.	95% of min. yield strength
Seam Peel -Extrusion -Fusion	ASTM D6392	1 test per 500 lineal feet or per GRI GM-14 and 20.	72% yield & ftb (1)
Non-destructive Seam Test	ASTM D5820 (Pressure Test)	Continuous	35 psi for 5 min.
	ASTM D5641 (Vacuum Box)		5 psi for 15 sec.
	ASTM D5641 (Spark Test)		No Spark
Electric Leak Location	ASTM D7002 (Water Puddle)	Once on constructed liner	Max 1 mm. diameter hole sensitivity
	ASTM D6747 (Selection Process)		
	ASTM D7007 (Water /Earth)		Max 6 mm. diameter hole sensitivity
	ASTM D7240 (Spark Test 2011)		

Notes:
ftb: Film Tear Bond



113 N. CHURCH ST,  
SUITE 521  
VISALIA, CA 93291  
(559) 563-0181



PROJECT:  
**CLEARLAKE DAIRY DIGESTER**  
  
CLIENT:  
DECADE DAIRY  
3313 AVE 256  
TULARE, CA 93274

GENERAL NOTES  
CONSTRUCTION

REVISION LOG:

PLOT DATE:	06/15/2018
JOB NO.:	17003
SCALE:	AS SHOWN
SHEET NO.:	A2 0120





113 N. CHURCH ST,  
SUITE 521  
VISALIA, CA 93291  
(559) 563-0181



PROJECT:

**CLEAR LAKE  
DAIRY  
DIGESTER**

CLIENT:

DECADE DAIRY  
3313 AVE 256  
TULARE, CA 93274

**SITE PLAN**  
DAIRY

REVISION LOG:


PLOT DATE: 06/15/2018

JOB NO.: 17003

SCALE: AS SHOWN

SHEET NO.: A3 0121





113 N. CHURCH ST,  
SUITE 521  
VISALIA, CA 93291  
(559) 563-0181



PROJECT:  
**CLEAR LAKE  
DAIRY  
DIGESTER**


CLIENT:  
DECADE DAIRY  
3313 AVE 256  
TULARE, CA 93274

SITE PLAN  
DIGESTER

REVISION LOG:	

PLOT DATE:	06/15/2018
JOB NO.:	17003
SCALE:	AS SHOWN
SHEET NO.:	A4 0122






**A** ANCHOR TRENCH / SUMP PROFILE VIEW


N.T.S.

DIMENSION TABLE (FT.)	
LETTER	POND
L	1.7'
M	2.7'
U	20'
R	1.5'
S	3'
T	3'
X	30'
Y	30'
Z	5.5'



**B** SUMP PLAN VIEW

N.T.S.



**C** SIDE SLOPE TRENCH

N.T.S.



113 N. CHURCH ST,  
SUITE 521  
VISALIA, CA 93291  
(559) 563-0181



PROJECT:

**CLEARLAKE  
DAIRY  
DIGESTER**

CLIENT:  
DECADE DAIRY  
3313 AVE 256  
TULARE, CA 93274

GRADING DETAIL  
DIGESTER

REVISION LOG:


PLOT DATE: 06/15/2018

JOB NO.: 17003

SCALE: AS SHOWN

SHEET NO.: C.1 0128






**A BALLAST TUBE DETAIL**


N.T.S.

DESCRIPTION	LOCATION	MATERIAL	THICKNESS (MIN)	TOP FINISH	BOTTOM FINISH
COVER	TOP	HDPE	80 MIL	SMOOTH	SMOOTH



**C HDPE COVER-SMOOTH WELDS**

N.T.S.



**B BIO-GAS PIPING DETAIL**

N.T.S.

- NOTES:
1. GAS VENTS AROUND PERIPHERY OF LAGOON @ MAX. 40' O.C.
  2. STRAP NOT WELDED TO BIO-GAS HEADER PIPE.
  3. WRAP 60 MIL PRIMARY LINER OVER CONCRETE & EXTRUSION WELD.



113 N. CHURCH ST,  
SUITE 521  
VISALIA, CA 93291  
(559) 563-0181



PROJECT:

**CLEARLAKE  
DAIRY  
DIGESTER**

CLIENT:  
DECADE DAIRY  
3313 AVE 256  
TULARE, CA 93274

COVER SYSTEM  
DIGESTER

REVISION LOG:


PLOT DATE: 06/15/2018

JOB NO.: 17003


SCALE: AS SHOWN

SHEET NO.: D.1 0124







**A SLUDGE REMOVAL PIPE ANCHOR DETAIL**  
 NOTE: ANCHOR TO BE USED ON HORIZONTAL SURFACES ONLY, AT BOTTOM OF LAGOON N.T.S.



**B TYPICAL PIPE STRAP-DOWN DETAIL**  
 NOTE: MAXIMUM 10' O.C. SPACING BETWEEN PIPE STRAP-DOWNS, U.N.O. N.T.S.



**C TYPICAL SLUDGE PIPE-PROFILE**  
 N.T.S.



**D BAFFLE SECTION**  
 N.T.S.



113 N. CHURCH ST,  
 SUITE 521  
 VISALIA, CA 93291  
 (559) 563-0181



PROJECT:  
**CLEARLAKE DAIRY DIGESTER**

CLIENT:  
 DECADE DAIRY  
 3313 AVE 256  
 TULARE, CA 93274


SLURRY REMOVAL

DIGESTER

REVISION LOG:


PLOT DATE:	06/15/2018
JOB NO.:	17003
SCALE:	AS SHOWN
SHEET NO.:	D2 0125






**MIXER - HATCH**

N.T.S.




**AIR INJECTION & MIXER HATCH**

N.T.S.




**MIXER - PLAN VIEW**

N.T.S.




**MIXER - ISOMETRIC W/FLOAT IN PLACE**

N.T.S.



**MIXER - ISOMETRIC**

N.T.S.



**MIXER - SIDE VIEW**

N.T.S.

**MIXER - FRONT VIEW**

N.T.S.



113 N. CHURCH ST,  
SUITE 521  
VISALIA, CA 93291  
(559) 563-0181



PROJECT:

**CLEARLAKE  
DAIRY  
DIGESTER**

CLIENT:  
DECADE DAIRY  
3313 AVE 256  
TULARE, CA 93274

MIXER  
DETAILS

REVISION LOG:


PLOT DATE: 06/15/2018

JOB NO.: 17003

SCALE: AS SHOWN


SHEET NO.: D.3 0126






MOISTURE TRAP DETAIL

N.T.S.





BALL VALVE JUNCTION

N.T.S.



BIO-GAS VALVE

N.T.S.



BOLLARD DETAIL

N.T.S.



113 N. CHURCH ST,  
SUITE 521  
VISALIA, CA 93291  
(559) 563-0181



PROJECT:

**CLEARLAKE  
DAIRY  
DIGESTER**

CLIENT:  
DECADE DAIRY  
3313 AVE 256  
TULARE, CA 93274

DETAILS

REVISION LOG:


PLOT DATE: 06/15/2018

JOB NO.: 17003


SCALE: AS SHOWN

SHEET NO.: D4 0127






**FRONT VIEW**



**DIGESTER ANCHOR TRENCH DETAIL**


NOTES: 1. CONTRACTOR TO USE ANCHOR SYSTEM OR PROVIDE DETAILS AND DESIGN FOR ALTERNATIVE TO BE APPROVED BY ENGINEER. N.T.S.



**SIDE VIEW**


**LCRS, LYSIMETER AND DRAINAGE SUMP PROFILE**

N.T.S.



**HDPE CROSS SECTION**

N.T.S.




**TYPICAL PERFORATION DETAIL**

N.T.S.



113 N. CHURCH ST,  
SUITE 521  
VISALIA, CA 93291  
(559) 563-0181



PROJECT:  
**CLEARLAKE  
DAIRY  
DIGESTER**

CLIENT:  
DECADE DAIRY  
3313 AVE 256  
TULARE, CA 93274

GENERAL NOTES  
LINER  
DETAILS


REVISION LOG:

PLOT DATE:	06/15/2018
JOB NO.:	17003
SCALE:	AS SHOWN
SHEET NO.:	L1 0128




OPTIONAL TIER 1 DOUBLE LINER-LAYERING SYSTEM WITH DRAIN LINER VERIFY WITH OWNER


SMOOTH/STUDDED/ 60-NET-60 LINER LAYERS					
DESCRIPTION	LOCATION	MATERIAL	THICKNESS (MIN)	TOP FINISH	BOTTOM FINISH
PRIMARY LINER	TOP	HDPE	60 MIL	SMOOTH	SMOOTH CONDUCTIVE
DRAINAGE NET	MIDDLE	HDPE	200 MIL	N/A	N/A
SECONDARY LINER	BOTTOM	HDPE	60 MIL	SMOOTH	SMOOTH




**A** DOUBLE LAYER 60-NET-60  
DOUBLE LAYER WITH DRAIN LINER N.T.S.



HOT WEDGE DOUBLE FUSION WELD




**B** HDPE LINER-SMOOTH WELDS N.T.S.



DRAIN LINER SMOOTH END WELD PATCH


**C** 3'X3' DRAIN PATCH WELD N.T.S.

**D** AGRU DRAIN LINER END/END WELD  
NOTE: AGRU DRAIN LINER DOES NOT HAVE STUDS ALONG THE EDGE SO EDGE/EDGE SEAMS DO NOT REQUIRE DRINGING OR CAP. N.T.S.



2' WIDE STRIP OF 200 MIL  
GEONET. TACK WELD AT 8'

**C**  
**P.3** 3'X3' DRAIN PATCH



NOTE: CQA OFFICER IS RESPONSIBLE TO ADD PATCHES AS NEEDED FOR FLOW

**E** AGRU DRAIN LINER CROSS SEAM NET PLAN VIEW  
NOTE: TYPICAL OF ALL DRAIN LINERS N.T.S.



113 N. CHURCH ST,  
SUITE 521  
VISALIA, CA 93291  
(559) 563-0181



PROJECT:  
**CLEARLAKE  
DAIRY  
DIGESTER**

CLIENT:  
DECADE DAIRY  
3313 AVE 256  
TULARE, CA 93274

REVISION LOG:	LINER DETAILS	
	NO.	DESCRIPTION
	1	ISSUED FOR PERMIT

PLOT DATE:	06/15/2018
JOB NO.:	17003
SCALE:	AS SHOWN
SHEET NO.:	D2 0129







# DIXIE CREEK DAIRY DIGESTER

## BENCHMARK

THE TOPOGRAPHIC SURVEY WAS PERFORMED UTILIZING GLOBAL POSITIONING SYSTEM OBSERVATIONS. DISTANCES AND NUMBERS SHOWN ARE TO BE CONSIDERED GROUND VALUES. BENCHMARK AND CONTROL SHOWN ON CONTROL PLAN SHEET. THE BENCHMARK AND VERTICAL ELEVATIONS WERE DERIVED FROM THE NGS ONLINE POSITIONING SERVICE (OPUS), AND IS SHOWN ON THE NAVD 88 DATUM UTILITIZING THE GEOID 09 AS THE VERTICAL MODEL.

## PRESERVATION OF MONUMENTS

PURSUANT TO SECTIONS 8771(B) AND 8771(C) OF THE GOVERNMENT CODE, ANY MONUMENTS THAT CONTROL THE LOCATION OF BOUNDARIED, OR OTHERWISE PROVIDE HORIZONTAL OR VERTICAL SURVEY CONTROL WITHIN THE CONSTRUCTION AREA, SHALL BE LOCATED AND REFERENCED PRIOR TO CONSTRUCTION, AND A CORNER RECORD OR RECORD OF SURVEY OF THE REFERENCES SHALL BE FILED WITH THE COUNTY SURVEYOR.

PERMANENT MONUMENTATION SHALL BE SET TO PERPETUATE THE LOCATION OF ANY MONUMENT WHICH COULD BE DAMAGED OR DESTROYED, AND A CORNER RECORD OR RECORD OF SURVEY SHALL BE FILED WITH THE COUNTY SURVEYOR PRIOR TO THE RECORDING OF A CERTIFICATE OF COMPLETION FOR THE PROJECT.

## DUST CONTROL NOTES

CONTRACTOR IS REQUIRED TO COMPLY WITH GOOD HOUSE KEEPING PRACTICES

## STORMWATER (SWPPP) NOTES

CONTRACTOR IS REQUIRED TO COMPLY WITH GOOD HOUSE KEEPING PRACTICES



VICINITY MAP

SCALE 1" : 2 MI

## SHEET INDEX

### GENERAL NOTES

- A.1 COVER SHEET
- A.2 GENERAL NOTES
- A.3 SITE PLAN - DAIRY
- A.4 SITE PLAN - DIGESTER

### CIVIL DRAWINGS

- C.1 GRADING PLAN
- C.2 CROSS SECTIONS
- C.3 GRADING DETAILS

### DIGESTER DRAWINGS

- D.1 COVER SYSTEM
- D.2 SLURRY SYSTEM
- D.3 MIXERS
- D.4 DETAILS


### LINER DRAWINGS

- L.1 LINER - DETAILS
- L.2 LINER - DETAILS
- L.3 LINER - DETAILS

## SHEET REFERENCE

### SECTIONS:

SECTION NAME  
SHEET NUMBER



### DETAILS:

DETAIL NAME  
SHEET NUMBER



B  
C.3

## CONTACT INFO

ENGINEER:  
CRAIG HARTMAN, RCE 73837  
HARTMAN ENGINEERING, INC.  
3121 W. CERES CT.  
VISALIA, CA 93291  
(559) 563-0181

DAIRY CONTACT:  
BERNARD TE VELDE JR  
3601 CA-198  
HANFORD, CA 93230



113 N. CHURCH ST,  
SUITE 521  
VISALIA, CA 93291  
(559) 563-0181



### PROJECT:

DIXIE CREEK

DAIRY  
DIGESTER

### CLIENT:

BERNARD TE VELDE  
3601 CA-198  
HANFORD, CA 93230

REVISION LOG:

PLOT DATE: 01/08/18

JOB NO.: 17003

SCALE: AS SHOWN

SHEET NO.: A.1



SPECIFICATIONS FOR ENGINEERED FILL MATERIAL OF ABOVE GRADE EMBANKMENTS OR AS REQUIRED

TEST PARAMETER	TEST METHOD	FREQUENCY	ACCEPTANCE CRITERIA
Compaction Curves	ASTM D1557 (Modified Proctor)	Change in material	N/A
Grain Size Distribution	ASTM D422 (Sieve)	Change in material	At least 30% passing No. 200 U.S. Standard Sieve. Per Specifications (1)
Soil Classification	ASTM D2487 (USCS)	Change in material	Suitable for compaction <sup>(2,3)</sup>
Maximum Particle Size	ASTM D422 (Sieve)	Change in material	½ inch, ¼ top 6 inches
Maximum Water soluble Sulfate (SO <sup>4-</sup> ) in Soil (Concrete Slab locations)	ASTM C1580	Change in material	0.2% by weight
Site Preparation Specifications:			
1. Clearing: Prior to earthwork operations, the area to be developed should be stripped of vegetation, organic topsoil, and cleared of cow waste and miscellaneous debris from the proposed construction areas. Deeper clearing may be required in localized areas. The actual depth of clearing should be reviewed by a licensed Geotechnical Engineer at the time of construction. The limits of stripping and clearing should be at least five feet bey ond the limits of construction.			
2. Compaction: The scarified subgrade and subsequent fill placed at the site should be moisture conditioned to near optimum moisture content, and compacted to at least and 90 percent for 2:1 side slope pond of maximum dry density as determined by ASTM test method D1557.			
3. Material for fill: Fill should consist of select material. Nativ e soil, free from organic, vegetation, and rocks or cobbles larger than three inches, may be used as fill at the site. Import material must be reviewed by licensed Geotechnical Engineer prior to transport to the site.			
4. Fill placement: Fill material should be moisture-conditioned to +/- 2% of the optimum moisture content prior to compaction. Fill material with excessiv e moisture should be allowed to dry prior to compaction or be mixed with dry soil to bring the fill to a workable moisture content. Fill should be placed in level lifts not exceeding a loose, uncompacted thickness of eight inches, and compacted as engineered fill.			
Sub-grade requirements for fill only :			
-Over Excavate for minimum 1 ft. to meet Engineered Fill Borrow Material Guidelines and Pond Liner Sub-grade requirements			
-Well mixed soil			
-6 in max lifts			
-Upper 6 inches is of fine-finished soil particles no greater than ¼ in.+			
Notes:			
Field tests shall not be required, but fill borrow material specifications must meet the acceptance criteria outlined in Table 1.			
Refer to Geotechnical Report			

FILL TEST SPECIFICATIONS FOR SUB-GRADE

TEST PARAMETER	TEST METHOD <sup>(1,2)</sup>	FREQUENCY	ACCEPTANCE CRITERIA
Uncompacted Lift Thickness	Visual Observation	Continuous	8-in. <sup>(1,2)</sup>
Construction Oversight	Visual Observation	Continuous	Maximum particle size 1/2 inch.
In-Place Moisture Alternate Method	ASTM D2216 (Oven Dry)	1 per every 10 Nuclear tests	+/-2% of Optimum Moisture Content per ASTM D1557
In-Place Moisture Rapid Field Methods <sup>(1,2,3,4)</sup>	ASTM D6938 <sup>(3,4,5)</sup> (Nuclear Method)	3 per acre per lift, min. 2 per day	+/-2% of Optimum Moisture Content per ASTM D1557
In-Place Density Alternat e Method	ASTM D2937(Drive Cylinder)	1 per every 10 Nuclear tests	90% of Maximum Dry Density per ASTM D1557
In-Place Density Rapid Field Methods <sup>(1,2)</sup>	ASTM D6938 <sup>(3,4,5)</sup> (Nuclear Method)	3 per acre per lift, min. 2 per day	90% of Maximum Dry Density per ASTM D1557
Subgrade Thickness	Surveying Measurement	At 50-foot centers	Minimum 1 ft. <sup>(1,2)</sup>
Clod Size	Visual Observation	Continuous	Per Specification

Notes:

See earthwork section for anchor trench, excavation, backfill, and compaction requirements.

<sup>1</sup> ASTM Test Method, unless otherwise noted. Results of all tests performed to be reported as per method reporting criteria.

<sup>2</sup> The sub-grade shall be scarified to a depth of 1 ft. lower than finished grade, compacted, and tested in accordance with the requirements of this table.

<sup>3</sup> Must be verified by ASTM D2216 (Oven) overnight method once every day or once per change in material

<sup>4</sup> Must be verified by ASTM D2937 (Dry Cylinder) twice per day or per change in material

<sup>5</sup> Calibration Procedure: ASTM D7013-04: Standard Guide for Nuclear Surface Moisture and Density Gauge Calibration Facility Set-up

POND SPECIFICATIONS FOR SUBGRADES CUT BELOW GROUND (For Slopes 2:1 or shallower)

**Side Slopes:** The certified Civil Engineer/CQA Chief Officer shall walk final side slopes after cut by heavy equipment and confirm no SW or SP soils and no loose soils. All SW, SP, or soils that are not amenable to a firm and unyielding subgrade shall be removed and replaced down to a minimum 3 ft. below sloped surface. Any soils removed and replaced shall meet the Engineered Fill requirements in Table 1.

**Pond Bottom:** 1. An as-built survey of the pond bottom shall take place after subgrade construction to insure minimum slopes are achieved. Pond Bottom shall be tested per criteria below. Any soils not meeting the requirements below (i.e. that is not firm and unyielding) shall be removed and replaced down to a minimum 2 ft. Any soils removed and replaced shall meet the Engineered Fill requirements in Table 1. The Civil Engineer may make determination of soils meeting requirements or not based upon visual inspection which shall be included in the Subgrade Certification Report and signed and sealed by a Civil Engineer and CQA Officer.

TEST PARAMETER	TEST METHOD <sup>(1,2)</sup>	FREQUENCY	ACCEPTANCE CRITERIA
In-Place Density Rapid Field Methods <sup>(1,2)</sup>	ASTM D6938 <sup>(3,4,5)</sup> (Nuclear)	3 per acre	90% of Maximum Dry Density per ASTM D1557
In-Place Moisture Rapid Field Methods <sup>(1,2,3,4)</sup>	ASTM D6938 <sup>(3,4,5)</sup> (Nuclear Methods)	3 per acre per lift, min. 2 per day	+/-2% of Optimum Moisture Content per ASTM D1557
Construction Oversight	Visual Observation	Continuous	Maximum particle size 1/2 inch.
Subgrade Slope	Surveying Measurement	200 ft. maximum grid	Min 1%

60 MIL HDPE GEOMEMBRANE CONSTRUCTION QUALITY ASSURANCE (CQA)

TEST PARAMETER	TEST METHOD	FREQUENCY	ACCEPTANCE CRITERIA
Thickness (min. ave.) -Lowest individual for 8 out of 10 values -Lowest individual for any of the 10 values	ASTM D5994	1 per lot or 1 per 70,000 ft <sup>2</sup> , whichever is greater	Nom. (-5%)  -10%  -15%
Tensile Properties -yield strength -break strength -strain at yeild -break strength	ASTM D6693 Type IV	1 per lot or 1 per 70,000 ft <sup>2</sup> , whichever is greater	≥126 lb./in. ≥90 lb./in. ≥12% ≥100%
Puncture Resistance	ASTM D4833	1 per lot or 1 per 70,000 ft <sup>2</sup> , whichever is greater	108 lb. (min.)
Tear Resistance	ASTM D1004, Die C	1 per lot or 1 per 70,000 ft <sup>2</sup> , whichever is greater	42 lb. (min.)
Interface Shear -60-mil HDPE/subgrade soil -Drainage geocomposite	ASTM D5321 ASTM D6243	2 tests or 1 per 200,000 ft <sup>2</sup> , whichever is greater	
Seam Shear	ASTM D6392	1 test per 500 lineal feet or per GRI GM-14 and 20.	95% of min. yield strength
Seam Peel -Extrusion -Fusion	ASTM D6392	1 test per 500 lineal feet or per GRI GM-14 and 20.	72% yield & ffb (1)
Non-destructive Seam Test	ASTM D5820 (Pressure Test)	Continuous	35 psi for 5 min.
	ASTM D5641 (Vacuum Box)		5 psi for 15 sec.
	ASTM D5641 (Spark Test)		No Spark
Electric Leak Location	ASTM D7002 (Water Puddle)	Once on constructed liner	Max 1 mm. diameter hole sensitivity
	ASTM D6747 (Selection Process)		
	ASTM D7007 (Water /Earth)		Max 6 mm. diameter hole sensitivity
	ASTM D7240 (Spark Test 2011)		
Notes: ffb: Film Tear Bond			

NOTES:

THE APPROVED WORK PLAN WHICH INCLUDES THE CONSTRUCTION QUALITY ASSURANCE PLAN, OPERATION, MAINTENANCE AND MONITORING PLAN, CONSTRUCTION DRAWINGS, AND SOILS REPORT TOGETHER AS A PACKAGE ARE THE COMPLETE SPECIFICATIONS REQUIRED FOR CONSTRUCTION OF THE POND AND LINER SYSTEM.



113 N. CHURCH ST,  
SUITE 521  
VISALIA, CA 93291  
(559) 563-0181



PROJECT:

DIXIE CREEK

DAIRY  
DIGESTER

CLIENT:  
BERNARD TE VELDE  
3601 CA-198  
HANFORD, CA 93230

GENERAL NOTES  
CONSTRUCTION

REVISION LOG:


PLOT DATE: 01/08/18

JOB NO.: 17003


SCALE: AS SHOWN

SHEET NO.: A.2  
132 0132





HW 198



113 N. CHURCH ST,  
SUITE 521  
VISALIA, CA 93291  
(559) 563-0181



PROJECT:

DIXIE CREEK

DAIRY  
DIGESTER

CLIENT:  
BERNARD TE VELDE  
3601 CA-198  
HANFORD, CA 93230

SITE PLAN

DIGESTER

REVISION LOG:


PLOT DATE: 01/08/18

JOB NO.: 17003

SCALE: AS SHOWN

SHEET NO.: A.3





113 N. CHURCH ST,  
SUITE 521  
VISALIA, CA 93291  
(559) 563-0181



PROJECT:  
**DIXIE CREEK**

**DAIRY  
DIGESTER**

CLIENT:  
BERNARD TE VELDE  
3601 CA-198  
HANFORD, CA 93230

SITE PLAN  
DAIRY

REVISION LOG:

PLOT DATE:	01/08/18
JOB NO.:	17003
SCALE:	AS SHOWN
SHEET NO.:	A.4





113 N. CHURCH ST,  
SUITE 521  
VISALIA, CA 93291  
(559) 563-0181



PROJECT:  
**DIXIE CREEK**  
  
**DAIRY**  
**DIGESTER**

CLIENT:  
BERNARD TE VELDE  
3601 CA-198  
HANFORD, CA 93230


GRADING PLAN

DIGESTER

REVISION LOG:

PLOT DATE:	01/08/18
JOB NO.:	17003
SCALE:	AS SHOWN
SHEET NO.:	C.1

PS 122 0135



GRADING NOTES:

- 1.CONTRACTOR SHALL INFORM ENGINEER OF ANY DISCREPANCIES OR ERRORS IN PLANS PRIOR TO CONSTRUCTION.
2. CONTRACTOR SHALL MEET SPECIFICATIONS OF TABLE 2 WITHIN THE APPROVED CONSTRUCTION QUALITY CONTROL PLAN.
3. CONTRACTOR SHALL SMOOTH DRUM ROLL FINAL SURFACE AND REMOVE ANY ROCK OR MATERIAL GREATER THAN 1/2 INCH.





113 N. CHURCH ST,  
SUITE 521  
VISALIA, CA 93291  
(559) 563-0181



PROJECT:  
**DIXIE CREEK**  
  
**DAIRY**  
**DIGESTER**  
  
CLIENT:  
BERNARD TE VELDE  
3601 CA-198  
HANFORD, CA 93230



GRADING SECTIONS

DIGESTER


REVISION LOG:

PLOT DATE: 01/08/18  
JOB NO.: 17003  
SCALE: AS SHOWN  
SHEET NO.: C.2

PS 124 0136








**A** ANCHOR TRENCH / SUMP PROFILE VIEW


N.T.S.

DIMENSION TABLE (FT.)	
LETTER	POND
L	1.7'
M.1	2.7'
U	20'
R	1.5'
S	3'
T	3'
X	30'
Y	30'
Z	5.5'



**B** SUMP PLAN VIEW

N.T.S.




**C** SIDE SLOPE TRENCH

N.T.S.



113 N. CHURCH ST,  
SUITE 521  
VISALIA, CA 93291  
(559) 563-0181



PROJECT:

**DIXIE CREEK**

**DAIRY  
DIGESTER**

CLIENT:  
BERNARD TE VELDE  
3601 CA-198  
HANFORD, CA 93230

GRADING DETAIL  
DIGESTER

REVISION LOG:


PLOT DATE: 01/08/18

JOB NO.: 17003

SCALE: AS SHOWN

SHEET NO.: C.3






**A BALLAST TUBE DETAIL**


N.T.S.

DESCRIPTION	LOCATION	MATERIAL	THICKNESS (MIN)	TOP FINISH	BOTTOM FINISH
COVER	TOP	HDPE	80 MIL	SMOOTH	SMOOTH



**C HDPE COVER-SMOOTH WELDS**

N.T.S.



**B BIO-GAS PIPING DETAIL**

NOTES:

1. GAS VENTS AROUND PERIPHERY OF LAGOON @ MAX. 40' O.C.
2. STRAP NOT WELDED TO BIO-GAS HEADER PIPE.
3. WRAP 60 MIL PRIMARY LINER OVER CONCRETE & EXTRUSION WELD.

N.T.S.



113 N. CHURCH ST,  
SUITE 521  
VISALIA, CA 93291  
(559) 563-0181



PROJECT:

**DIXIE CREEK**

**DAIRY  
DIGESTER**

CLIENT:  
BERNARD TE VELDE  
3601 CA-198  
HANFORD, CA 93230

COVER SYSTEM  
DIGESTER

REVISION LOG:


PLOT DATE: 01/08/18

JOB NO.: 17003


SCALE: AS SHOWN

SHEET NO.: D.1







**A SLUDGE REMOVAL PIPE ANCHOR DETAIL**  
NOTE: ANCHOR TO BE USED ON HORIZONTAL SURFACES ONLY, AT BOTTOM OF LAGOON N.T.S.



**B TYPICAL PIPE STRAP-DOWN DETAIL**  
NOTE: MAXIMUM 10' O.C. SPACING BETWEEN PIPE STRAP-DOWNS, U.N.O. N.T.S.



**C TYPICAL SLUDGE PIPE-PROFILE**  
N.T.S.



**D BAFFLE SECTION**  
N.T.S.



113 N. CHURCH ST,  
SUITE 521  
VISALIA, CA 93291  
(559) 563-0181



PROJECT:

**DIXIE CREEK**

**DAIRY  
DIGESTER**

CLIENT:  
BERNARD TE VELDE  
3601 CA-198  
HANFORD, CA 93230

SLURRY REMOVAL  
SYSTEM  
DIGESTER

REVISION LOG:


PLOT DATE: 01/08/18

JOB NO.: 17003

SCALE: AS SHOWN


SHEET NO.: D.2






**MIXER - HATCH**

N.T.S.




**AIR INJECTION & MIXER HATCH**

N.T.S.




**MIXER - PLAN VIEW**

N.T.S.




**MIXER - ISOMETRIC W/FLOAT IN PLACE**

N.T.S.




**MIXER - ISOMETRIC**

N.T.S.




**MIXER - SIDE VIEW**

N.T.S.



**MIXER - FRONT VIEW**

N.T.S.



113 N. CHURCH ST,  
SUITE 521  
VISALIA, CA 93291  
(559) 563-0181



PROJECT:

**DIXIE CREEK**

**DAIRY  
DIGESTER**

CLIENT:  
BERNARD TE VELDE  
3601 CA-198  
HANFORD, CA 93230

MIXER  
DETAILS

REVISION LOG:


PLOT DATE: 01/08/18

JOB NO.: 17003

SCALE: AS SHOWN


SHEET NO.: D.3






**MOISTURE TRAP DETAIL**

N.T.S.




**BIO-GAS VALVE**

N.T.S.



**BALL VALVE JUNCTION**

N.T.S.



**BOLLARD DETAIL**

N.T.S.



113 N. CHURCH ST,  
SUITE 521  
VISALIA, CA 93291  
(559) 563-0181



PROJECT:

**DIXIE CREEK**

**DAIRY  
DIGESTER**

CLIENT:  
BERNARD TE VELDE  
3601 CA-198  
HANFORD, CA 93230

DETAILS

REVISION LOG:

PLOT DATE: 01/08/18

JOB NO.: 17003

SCALE: AS SHOWN


SHEET NO.: D.4




GENERAL NOTES  
LINER  
DETAILS

REVISION LOG:

PLOT DATE:	01/08/18
JOB NO.:	17003
SCALE:	AS SHOWN
SHEET NO.:	L.1




**FRONT VIEW**




**SIDE VIEW**

**LCRS, LYSIMETER AND DRAINAGE SUMP PROFILE**




**DIGESTER ANCHOR TRENCH DETAIL**

NOTES: 1. CONTRACTOR TO USE ANCHOR SYSTEM OR PROVIDE DETAILS AND DESIGN FOR ALTERNATIVE TO BE APPROVED BY ENGINEER. N.T.S.



**HDPE CROSS SECTION**

N.T.S.



**TYPICAL PERFORATION DETAIL**


N.T.S.

A





OPTIONAL TIER 1 DOUBLE LINER-LAYERING SYSTEM WITH DRAIN LINER VERIFY WITH OWNER


SMOOTH/STUDDED/ 60-NET-60 LINER LAYERS					
DESCRIPTION	LOCATION	MATERAIL	THICKNESS (MIN)	TOP FINISH	BOTTOM FINISH
PRIMARY LINER	TOP	HDPE	60 MIL	SMOOTH	SMOOTH CONDUCTIVE
DRAINAGE NET	MIDDLE	HDPE	200 MIL	N/A	N/A
SECONDARY LINER	BOTTOM	HDPE	60 MIL	SMOOTH	SMOOTH



**A** DOUBLE LAYER 60-NET-60 DOUBLE LAYER WITH DRAIN LINER N.T.S.




**B** HDPE LINER-SMOOTH WELDS N.T.S.



DRAIN LINER SMOOTH END WELD PATCH

**C** 3'X3' DRAIN PATCH WELD N.T.S.


3.3 - Engineered Digester Site Plan and Design - Dixie Creek Dairy



**D** AGRU DRAIN LINER END/END WELD N.T.S.  
NOTE: AGRU DRAIN LINER DOES NOT HAVE STUDS ALONG THE EDGE SO EDGE/EDGE SEAMS DO NOT REQUIRE DRINGING OR CAP.

2' WIDE STRIP OF 200 MIL GEONET. TACK WELD AT 8'

**C** 3'X3' DRAIN PATCH P.3



NOTE: CQA OFFICER IS RESPONSIBLE TO ADD PATCHES AS NEEDED FOR FLOW

**E** AGRU DRAIN LINER CROSS SEAM NET PLAN VIEW N.T.S.

1.2 - Lakeside Pipeline LLC - Application - 2018 Solicitation SB 1383 Dairy Pilot Projects

THIS IS AN ORIGINAL UNPUBLISHED WORK AND MAY NOT BE DUPLICATED, PUBLISHED OR OTHERWISE USED WITHOUT THE WRITTEN CONSENT OF HARTMAN ENGINEERING INC. ©



113 N. CHURCH ST,  
SUITE 521  
VISALIA, CA 93291  
(559) 563-0181



PROJECT:

DIXIE CREEK

DAIRY  
DIGESTER

CLIENT:  
BERNARD TE VELDE  
3601 CA-198  
HANFORD, CA 93230

LINER  
DETAILS

REVISION LOG:

PLOT DATE: 01/08/18


JOB NO.: 17003

SCALE: AS SHOWN


SHEET NO.: L2

111 0143






**A BOOT SKIRT** N.T.S.



**B BOOTLESS PIPE PENETRATION**

LINER FASTENING



**C VENT ORIFICE (ISOMETRIC VIEW)**



113 N. CHURCH ST,  
SUITE 521  
VISALIA, CA 93291  
(559) 563-0181



PROJECT:

**DIXIE CREEK**

**DAIRY  
DIGESTER**

CLIENT:  
BERNARD TE VELDE  
3601 CA-198  
HANFORD, CA 93230

LINER  
DETAILS

REVISION LOG:

PLOT DATE: 01/08/18

JOB NO.: 17003

SCALE: AS SHOWN

SHEET NO.: L3



# DOUBLE L DAIRY DIGESTER

## BENCHMARK

THE TOPOGRAPHIC SURVEY WAS PERFORMED UTILIZING GLOBAL POSITIONING SYSTEM OBSERVATIONS. DISTANCES AND NUMBERS SHOWN ARE TO BE CONSIDERED GROUND VALUES. BENCHMARK AND CONTROL SHOWN ON CONTROL PLAN SHEET. THE BENCHMARK AND VERTICAL ELEVATIONS WERE DERIVED FROM THE NGS ONLINE POSITIONING SERVICE (OPUS), AND IS SHOWN ON THE NAVD 88 DATUM UTILITIZING THE GEOID 09 AS THE VERTICAL MODEL.

## PRESERVATION OF MONUMENTS

PURSUANT TO SECTIONS 8771(B) AND 8771(C) OF THE GOVERNMENT CODE, ANY MONUMENTS THAT CONTROL THE LOCATION OF BOUNDARIED, OR OTHERWISE PROVIDE HORIZONTAL OR VERTICAL SURVEY CONTROL WITHIN THE CONSTRUCTION AREA, SHALL BE LOCATED AND REFERENCED PRIOR TO CONSTRUCTION, AND A CORNER RECORD OR RECORD OF SURVEY OF THE REFERENCES SHALL BE FILED WITH THE COUNTY SURVEYOR.

PERMANENT MONUMENTATION SHALL BE SET TO PERPETUATE THE LOCATION OF ANY MONUMENT WHICH COULD BE DAMAGED OR DESTROYED, AND A CORNER RECORD OR RECORD OF SURVEY SHALL BE FILED WITH THE COUNTY SURVEYOR PRIOR TO THE RECORDING OF A CERTIFICATE OF COMPLETION FOR THE PROJECT.

## DUST CONTROL NOTES

CONTRACTOR IS REQUIRED TO COMPLY WITH GOOD HOUSE KEEPING PRACTICES

## STORMWATER (SWPPP) NOTES

CONTRACTOR IS REQUIRED TO COMPLY WITH GOOD HOUSE KEEPING PRACTICES



VICINITY MAP

SCALE 1" : 2 MI

## SHEET INDEX

### GENERAL NOTES

- A.1 COVER SHEET
- A.2 GENERAL NOTES
- A.3 SITE PLAN - DAIRY
- A.4 SITE PLAN - DIGESTER

### CIVIL DRAWINGS

- C.1 GRADING PLAN
- C.2 CROSS SECTIONS
- C.3 GRADING DETAILS

### DIGESTER DRAWINGS

- D.1 COVER SYSTEM
- D.2 SLURRY SYSTEM
- D.3 MIXERS
- D.4 DETAILS


### LINER DRAWINGS

- L.1 LINER - DETAILS
- L.2 LINER - DETAILS
- L.3 LINER - DETAILS

## SHEET REFERENCE

### SECTIONS:

SECTION NAME  
SHEET NUMBER



### DETAILS:

DETAIL NAME  
SHEET NUMBER



B  
C.3

## CONTACT INFO

ENGINEER:  
CRAIG HARTMAN, RCE 73837  
HARTMAN ENGINEERING, INC.  
3121 W. CERES CT.  
VISALIA, CA 93291  
(559) 563-0181

DAIRY CONTACT:  
RON VANDERWEERD  
10234 LANSING AVE  
HANFORD, CA 93230



113 N. CHURCH ST,  
SUITE 521  
VISALIA, CA 93291  
(559) 563-0181



PROJECT:

DOUBLE L

DAIRY  
DIGESTER

CLIENT:

RON VANDERWEERD  
10234 LANSING AVE  
HANFORD, CA 93230

REVISION LOG:

PLOT DATE: 01/08/18

JOB NO.: 17003

SCALE: AS SHOWN

SHEET NO.: A.1



SPECIFICATIONS FOR ENGINEERED FILL MATERIAL OF ABOVE GRADE EMBANKMENTS OR AS REQUIRED

TEST PARAMETER	TEST METHOD	FREQUENCY	ACCEPTANCE CRITERIA
Compaction Curves	ASTM D1557 (Modified Proctor)	Change in material	N/A
Grain Size Distribution	ASTM D422 (Sieve)	Change in material	At least 30% passing No. 200 U.S. Standard Sieve. Per Specifications (1)
Soil Classification	ASTM D2487 (USCS)	Change in material	Suitable for compaction (2,3)
Maximum Particle Size	ASTM D422 (Sieve)	Change in material	½ inch, ¼ top 6 inches
Maximum Water soluble Sulfate (SO <sup>4-</sup> ) in Soil (Concrete Slab locations)	ASTM C1580	Change in material	0.2% by weight
Site Preparation Specifications:			
1. Clearing: Prior to earthwork operations, the area to be developed should be stripped of vegetation, organic topsoil, and cleared of cow waste and miscellaneous debris from the proposed construction areas. Deeper clearing may be required in localized areas. The actual depth of clearing should be reviewed by a licensed Geotechnical Engineer at the time of construction. The limits of stripping and clearing should be at least five feet bey ond the limits of construction.			
2. Compaction: The scarified subgrade and subsequent fill placed at the site should be moisture conditioned to near optimum moisture content, and compacted to at least and 90 percent for 2:1 side slope pond of maximum dry density as determined by ASTM test method D1557.			
3. Material for fill: Fill should consist of select material. Native soil, free from organic, vegetation, and rocks or cobbles larger than three inches, may be used as fill at the site. Import material must be reviewed by licensed Geotechnical Engineer prior to transport to the site.			
4. Fill placement: Fill material should be moisture-conditioned to +/- 2% of the optimum moisture content prior to compaction. Fill material with excessiv e moisture should be allowed to dry prior to compaction or be mixed with dry soil to bring the fill to a workable moisture content. Fill should be placed in level lifts not exceeding a loose, uncompacted thickness of eight inches, and compacted as engineered fill.			
Sub-grade requirements for fill only :			
-Over Excavate for minimum 1 ft. to meet Engineered Fill Borrow Material Guidelines and Pond Liner Sub-grade requirements			
-Well mixed soil			
-6 in max lifts			
-Upper 6 inches is of fine-finished soil particles no greater than ¼ in.+			
Notes:			
Field tests shall not be required, but fill borrow material specifications must meet the acceptance criteria outlined in Table 1.			
Refer to Geotechnical Report			

FILL TEST SPECIFICATIONS FOR SUB-GRADE

TEST PARAMETER	TEST METHOD (1)	FREQUENCY	ACCEPTANCE CRITERIA
Uncompacted Lift Thickness	Visual Observation	Continuous	8-in.(2)
Construction Oversight	Visual Observation	Continuous	Maximum particle size 1/2 inch.
In-Place Moisture Alternative Method	ASTM D2216 (Oven Dry)	1 per every 10 Nuclear tests	+/-2% of Optimum Moisture Content per ASTM D1557
In-Place Moisture Rapid Field Methods (3,4,5)	ASTM D6938 (Nuclear Method)	3 per acre per lift, min. 2 per day	+/-2% of Optimum Moisture Content per ASTM D1557
In-Place Density Alternat e Method	ASTM D2937(Drive Cylinder)	1 per every 10 Nuclear tests	90% of Maximum Dry Density per ASTM D1557
In-Place Density Rapid Field Methods (1)	ASTM D6938 (Nuclear Method)	3 per acre per lift, min. 2 per day	90% of Maximum Dry Density per ASTM D1557
Subgrade Thickness	Surveying Measurement	At 50-foot centers	Minimum 1 ft.(5)
Clod Size	Visual Observation	Continuous	Per Specification

Notes:

See earthwork section for anchor trench, excavation, backfill, and compaction requirements.

(1) ASTM Test Method, unless otherwise noted. Results of all tests performed to be reported as per method reporting criteria.

(2) The sub-grade shall be scarified to a depth of 1 ft. lower than finished grade, compacted, and tested in accordance with the requirements of this table.

(3) Must be verified by ASTM D2216 (Oven) overnight method once every day or once per change in material

(4) Must be verified by ASTM D2937 (Dry Cylinder) twice per day or per change in material

(5) Calibration Procedure: ASTM D7013-04: Standard Guide for Nuclear Surface Moisture and Density Gauge Calibration Facility Set-up

POND SPECIFICATIONS FOR SUBGRADES CUT BELOW GROUND (For Slopes 2:1 or shallower)

**Side Slopes:** The certified Civil Engineer/CQA Chief Officer shall walk final side slopes after cut by heavy equipment and confirm no SW or SP soils and no loose soils. All SW, SP, or soils that are not amenable to a firm and unyielding subgrade shall be removed and replaced down to a minimum 3 ft. below sloped surface. Any soils removed and replaced shall meet the Engineered Fill requirements in Table 1.

**Pond Bottom:** 1. An as-built survey of the pond bottom shall take place after subgrade construction to insure minimum slopes are achieved. Pond Bottom shall be tested per criteria below. Any soils not meeting the requirements below (i.e. that is not firm and unyielding) shall be removed and replaced down to a minimum 2 ft. Any soils removed and replaced shall meet the Engineered Fill requirements in Table 1. The Civil Engineer may make determination of soils meeting requirements or not based upon visual inspection which shall be included in the Subgrade Certification Report and signed and sealed by a Civil Engineer and CQA Officer.

TEST PARAMETER	TEST METHOD (1)	FREQUENCY	ACCEPTANCE CRITERIA
In-Place Density Rapid Field Methods (1)	ASTM D6938 (Nuclear)	3 per acre	90% of Maximum Dry Density per ASTM D1557
In-Place Moisture Rapid Field Methods (3,4,5)	ASTM D6938 (Nuclear Methods)	3 per acre per lift, min. 2 per day	+/-2% of Optimum Moisture Content per ASTM D1557
Construction Oversight	Visual Observation	Continuous	Maximum particle size 1/2 inch.
Subgrade Slope	Surveying Measurement	200 ft. maximum grid	Min 1%

60 MIL HDPE GEOMEMBRANE CONSTRUCTION QUALITY ASSURANCE (CQA)

TEST PARAMETER	TEST METHOD	FREQUENCY	ACCEPTANCE CRITERIA
Thickness (min. ave.) -Lowest individual for 8 out of 10 values -Lowest individual for any of the 10 values	ASTM D5994	1 per lot or 1 per 70,000 ft <sup>2</sup> , whichever is greater	Nom. (-5%)  -10%  -15%
Tensile Properties -yield strength -break strength -strain at yeild -break strength	ASTM D6693 Type IV	1 per lot or 1 per 70,000 ft <sup>2</sup> , whichever is greater	≥126 lb./in. ≥90 lb./in. ≥12% ≥100%
Puncture Resistance	ASTM D4833	1 per lot or 1 per 70,000 ft <sup>2</sup> , whichever is greater	108 lb. (min.)
Tear Resistance	ASTM D1004, Die C	1 per lot or 1 per 70,000 ft <sup>2</sup> , whichever is greater	42 lb. (min.)
Interface Shear -60-mil HDPE/subgrade soil -Drainage geocomposite	ASTM D5321 ASTM D6243	2 tests or 1 per 200,000 ft <sup>2</sup> , whichever is greater	
Seam Shear	ASTM D6392	1 test per 500 lineal feet or per GRI GM-14 and 20.	95% of min. yield strength
Seam Peel -Extrusion -Fusion	ASTM D6392	1 test per 500 lineal feet or per GRI GM-14 and 20.	72% yield & ffb (1)
Non-destructive Seam Test	ASTM D5820 (Pressure Test)	Continuous	35 psi for 5 min.
	ASTM D5641 (Vacuum Box)		5 psi for 15 sec.
	ASTM D5641 (Spark Test)		No Spark
Electric Leak Location	ASTM D7002 (Water Puddle)	Once on constructed liner	Max 1 mm. diameter hole sensitivity
	ASTM D6747 (Selection Process)		
	ASTM D7007 (Water /Earth)		Max 6 mm. diameter hole sensitivity
	ASTM D7240 (Spark Test 2011)		
Notes: ffb: Film Tear Bond			

NOTES:

THE APPROVED WORK PLAN WHICH INCLUDES THE CONSTRUCTION QUALITY ASSURANCE PLAN, OPERATION, MAINTENANCE AND MONITORING PLAN, CONSTRUCTION DRAWINGS, AND SOILS REPORT TOGETHER AS A PACKAGE ARE THE COMPLETE SPECIFICATIONS REQUIRED FOR CONSTRUCTION OF THE POND AND LINER SYSTEM.



113 N. CHURCH ST,  
SUITE 521  
VISALIA, CA 93291  
(559) 563-0181



PROJECT:

DOUBLE L

DAIRY  
DIGESTER

CLIENT:  
RON VANDERWEERD  
10234 LANSING AVE  
HANFORD, CA 93230

GENERAL NOTES  
CONSTRUCTION

REVISION LOG:


PLOT DATE: 01/08/18

JOB NO.: 17003

SCALE: AS SHOWN

SHEET NO.: A.2  
114 0146





113 N. CHURCH ST,  
SUITE 521  
VISALIA, CA 93291  
(559) 563-0181




PROJECT:  
**DOUBLE L**  
  
**DAIRY  
DIGESTER**  
  
CLIENT:  
RON VANDERWEERD  
10234 LANSING AVE  
HANFORD, CA 93230

SITE PLAN	DIGESTER	REVISION LOG:			

PLOT DATE:	01/08/18
JOB NO.:	17003
SCALE:	AS SHOWN
SHEET NO.:	A.3





113 N. CHURCH ST,  
SUITE 521  
VISALIA, CA 93291  
(559) 563-0181



PROJECT:  
**DOUBLE L**

**DAIRY  
DIGESTER**


CLIENT:  
RON VANDERWEERD  
10234 LANSING AVE  
HANFORD, CA 93230

S I T E   P L A N  
D A I R Y



REVISION LOG:

PLOT DATE:	01/08/18
JOB NO.:	17003
SCALE:	AS SHOWN
SHEET NO.:	A.4





- GRADING NOTES:**
1. CONTRACTOR SHALL INFORM ENGINEER OF ANY DISCREPANCIES OR ERRORS IN PLANS PRIOR TO CONSTRUCTION.
  2. CONTRACTOR SHALL MEET SPECIFICATIONS OF TABLE 2 WITHIN THE APPROVED CONSTRUCTION QUALITY CONTROL PLAN.
  3. CONTRACTOR SHALL SMOOTH DRUM ROLL FINAL SURFACE AND REMOVE ANY ROCK OR MATERIAL GREATER THAN  $\frac{1}{2}$  INCH.



113 N. CHURCH ST,  
SUITE 521  
VISALIA, CA 93291  
(559) 563-0181






PROJECT:  
**DOUBLE L**  
  
**DAIRY  
DIGESTER**  
  
CLIENT:  
RON VANDERWEERD  
10234 LANSING AVE  
HANFORD, CA 93230

GRADING PLAN	DIGESTER	REVISION LOG:	

PLOT DATE:	01/08/18
JOB NO.:	17003
SCALE:	AS SHOWN
SHEET NO.:	C.1





113 N. CHURCH ST,  
SUITE 521  
VISALIA, CA 93291  
(559) 563-0181



PROJECT:  
**DOUBLE L**

**DAIRY  
DIGESTER**

CLIENT:  
RON VANDERWEERD  
10234 LANSING AVE  
HANFORD, CA 93230


GRADING SECTIONS

DIGESTER

REVISION LOG:

PLOT DATE:	01/08/18
JOB NO.:	17003
SCALE:	AS SHOWN
SHEET NO.:	C.2






**A ANCHOR TRENCH / SUMP PROFILE VIEW**


N.T.S.

DIMENSION TABLE (FT.)	
LETTER	POND
L	1.7'
M.1	2.7'
U	20'
R	1.5'
S	3'
T	3'
X	30'
Y	30'
Z	5.5'



**B SUMP PLAN VIEW**

N.T.S.



**C SIDE SLOPE TRENCH**

N.T.S.



113 N. CHURCH ST,  
SUITE 521  
VISALIA, CA 93291  
(559) 563-0181



PROJECT:

**DOUBLE L**

**DAIRY  
DIGESTER**




CLIENT:  
RON VANDERWEERD  
10234 LANSING AVE  
HANFORD, CA 93230

GRADING DETAIL  
DIGESTER


REVISION LOG:

PLOT DATE:	01/08/18
JOB NO.:	17003
SCALE:	AS SHOWN
SHEET NO.:	C.3





- NOTES:
1. GAS VENTS AROUND PERIPHERY OF LAGOON @ MAX. 40' O.C.
  2. STRAP NOT WELDED TO BIO-GAS HEADER PIPE.
  3. WRAP 60 MIL PRIMARY LINER OVER CONCRETE & EXTRUSION WELD.



113 N. CHURCH ST,  
SUITE 521  
VISALIA, CA 93291  
(559) 563-0181



PROJECT:

**DOUBLE L**

**DAIRY  
DIGESTER**

CLIENT:  
RON VANDERWEERD  
10234 LANSING AVE  
HANFORD, CA 93230

COVER SYSTEM  
DIGESTER

REVISION LOG:


PLOT DATE: 01/08/18

JOB NO.: 17003


SCALE: AS SHOWN

SHEET NO.: D.1







**A SLUDGE REMOVAL PIPE ANCHOR DETAIL**  
NOTE: ANCHOR TO BE USED ON HORIZONTAL SURFACES ONLY, AT BOTTOM OF LAGOON N.T.S.



**B TYPICAL PIPE STRAP-DOWN DETAIL**  
NOTE: MAXIMUM 10' O.C. SPACING BETWEEN PIPE STRAP-DOWNS, U.N.O. N.T.S.



**C TYPICAL SLUDGE PIPE-PROFILE**  
N.T.S.



**D BAFFLE SECTION**  
N.T.S.



113 N. CHURCH ST,  
SUITE 521  
VISALIA, CA 93291  
(559) 563-0181



PROJECT:  
**DOUBLE L**

**DAIRY  
DIGESTER**


CLIENT:  
RON VANDERWEERD  
10234 LANSING AVE  
HANFORD, CA 93230

SLURRY REMOVAL  
SYSTEM  
DIGESTER

REVISION LOG:


PLOT DATE: 01/08/18  
JOB NO.: 17003  
SCALE: AS SHOWN  
SHEET NO.: D.2






**MIXER - HATCH**

N.T.S.




**AIR INJECTION & MIXER HATCH**

N.T.S.




**MIXER - PLAN VIEW**

N.T.S.




**MIXER - ISOMETRIC W/FLOAT IN PLACE**

N.T.S.



**MIXER - ISOMETRIC**

N.T.S.



**MIXER - SIDE VIEW**

N.T.S.

**MIXER - FRONT VIEW**

N.T.S.



113 N. CHURCH ST,  
SUITE 521  
VISALIA, CA 93291  
(559) 563-0181



PROJECT:

**DOUBLE L**

**DAIRY  
DIGESTER**

CLIENT:  
RON VANDERWEERD  
10234 LANSING AVE  
HANFORD, CA 93230

MIXER  
DETAILS

REVISION LOG:


PLOT DATE: 01/08/18

JOB NO.: 17003

SCALE: AS SHOWN


SHEET NO.: D.3






MOISTURE TRAP DETAIL

N.T.S.




BIO-GAS VALVE

N.T.S.



BALL VALVE JUNCTION

N.T.S.



BOLLARD DETAIL

N.T.S.



113 N. CHURCH ST,  
SUITE 521  
VISALIA, CA 93291  
(559) 563-0181



PROJECT:

DOUBLE L

DAIRY  
DIGESTER

CLIENT:  
RON VANDERWEERD  
10234 LANSING AVE  
HANFORD, CA 93230

DETAILS

REVISION LOG:


PLOT DATE: 01/08/18

JOB NO.: 17003


SCALE: AS SHOWN

SHEET NO.: D.4






**FRONT VIEW**




**SIDE VIEW**

**LCRS, LYSIMETER AND DRAINAGE SUMP PROFILE**




**DIGESTER ANCHOR TRENCH DETAIL**

NOTES: 1. CONTRACTOR TO USE ANCHOR SYSTEM OR PROVIDE DETAILS AND DESIGN FOR ALTERNATIVE TO BE APPROVED BY ENGINEER. N.T.S.



**HDPE CROSS SECTION**

N.T.S.



**TYPICAL PERFORATION DETAIL**

N.T.S.

A

B  
L.1


C  
L.1

D  
L.1





OPTIONAL TIER 1 DOUBLE LINER-LAYERING SYSTEM WITH DRAIN LINER VERIFY WITH OWNER


SMOOTH/STUDDED/ 60-NET-60 LINER LAYERS					
DESCRIPTION	LOCATION	MATERAIL	THICKNESS (MIN)	TOP FINISH	BOTTOM FINISH
PRIMARY LINER	TOP	HDPE	60 MIL	SMOOTH	SMOOTH CONDUCTIVE
DRAINAGE NET	MIDDLE	HDPE	200 MIL	N/A	N/A
SECONDARY LINER	BOTTOM	HDPE	60 MIL	SMOOTH	SMOOTH



**A** DOUBLE LAYER 60-NET-60 DOUBLE LAYER WITH DRAIN LINER N.T.S.




**B** HDPE LINER-SMOOTH WELDS N.T.S.




**D** AGRU DRAIN LINER END/END WELD N.T.S.

**C** 3'X3' DRAIN PATCH WELD N.T.S.

1.1 - Engineered Project Site Plan and Design - Double L Cattle



**E** AGRU DRAIN LINER CROSS SEAM NET PLAN VIEW N.T.S.




**F** AGRU DRAIN LINER CROSS SEAM NET PLAN VIEW N.T.S.

**E** AGRU DRAIN LINER CROSS SEAM NET PLAN VIEW N.T.S.

1.2 - Lakeside Pipeline LLC - Application - 2018 Solicitation SB 1383 Dairy Pilot Projects



113 N. CHURCH ST,  
SUITE 521  
VISALIA, CA 93291  
(559) 563-0181



PROJECT:  
**DOUBLE L**  
**DAIRY**  
**DIGESTER**  
CLIENT:  
RON VANDERWEERD  
10234 LANSING AVE  
HANFORD, CA 93230


LINER DETAILS	
REVISION LOG:	

PLOT DATE:	01/08/18
JOB NO.:	17003
SCALE:	AS SHOWN
SHEET NO.:	L2

1.1 - Engineered Project Site Plan and Design - Double L Cattle

THIS IS AN ORIGINAL UNPUBLISHED WORK AND MAY NOT BE DUPLICATED, PUBLISHED OR OTHERWISE USED WITHOUT THE WRITTEN CONSENT OF HARTMAN ENGINEERING INC. ©





LINE R  
DETAILS

REVISION LOG:

SHEET NO.: L.3

N.T.S.

1.2 - Lakeside Pipeline LLC - Application - 2018 Solicitation SB 1383 Dairy Pilot Projects

THIS IS AN ORIGINAL UNPUBLISHED WORK AND MAY NOT BE DUPLICATED, PUBLISHED OR OTHERWISE USED WITHOUT THE WRITTEN CONSENT OF HARTMAN ENGINEERING INC. ©



# HIGH ROLLER DAIRY DIGESTER

## BENCHMARK

THE TOPOGRAPHIC SURVEY WAS PERFORMED UTILIZING GLOBAL POSITIONING SYSTEM OBSERVATIONS. DISTANCES AND NUMBERS SHOWN ARE TO BE CONSIDERED GROUND VALUES. BENCHMARK AND CONTROL SHOWN ON CONTROL PLAN SHEET. THE BENCHMARK AND VERTICAL ELEVATIONS WERE DERIVED FROM THE NGS ONLINE POSITIONING SERVICE (OPUS), AND IS SHOWN ON THE NAVD 88 DATUM UTILITIZING THE GEOID 09 AS THE VERTICAL MODEL.

## PRESERVATION OF MONUMENTS

PURSUANT TO SECTIONS 8771(B) AND 8771(C) OF THE GOVERNMENT CODE, ANY MONUMENTS THAT CONTROL THE LOCATION OF BOUNDARIED, OR OTHERWISE PROVIDE HORIZONTAL OR VERTICAL SURVEY CONTROL WITHIN THE CONSTRUCTION AREA, SHALL BE LOCATED AND REFERENCED PRIOR TO CONSTRUCTION, AND A CORNER RECORD OR RECORD OF SURVEY OF THE REFERENCES SHALL BE FILED WITH THE COUNTY SURVEYOR.


PERMANENT MONUMENTATION SHALL BE SET TO PERPETUATE THE LOCATION OF ANY MONUMENT WHICH COULD BE DAMAGED OR DESTROYED, AND A CORNER RECORD OR RECORD OF SURVEY SHALL BE FILED WITH THE COUNTY SURVEYOR PRIOR TO THE RECORDING OF A CERTIFICATE OF COMPLETION FOR THE PROJECT.

## DUST CONTROL NOTES

CONTRACTOR IS REQUIRED TO COMPLY WITH GOOD HOUSE KEEPING PRACTICES

## STORMWATER (SWPPP) NOTES

CONTRACTOR IS REQUIRED TO COMPLY WITH GOOD HOUSE KEEPING PRACTICES



VICINITY MAP

SCALE 1" : 2 MI

## SHEET INDEX

### GENERAL NOTES

- A.1 COVER SHEET
- A.2 GENERAL NOTES
- A.3 SITE PLAN - DAIRY
- A.4 SITE PLAN - DIGESTER

### CIVIL DRAWINGS

- C.1 GRADING PLAN
- C.2 CROSS SECTIONS
- C.3 GRADING DETAILS

### DIGESTER DRAWINGS

- D.1 COVER SYSTEM
- D.2 SLURRY SYSTEM
- D.3 MIXERS
- D.4 DETAILS


### LINER DRAWINGS

- L.1 LINER - DETAILS
- L.2 LINER - DETAILS
- L.3 LINER - DETAILS

## SHEET REFERENCE

### SECTIONS:

SECTION NAME  
SHEET NUMBER



### DETAILS:

DETAIL NAME  
SHEET NUMBER



B  
C.3

## CONTACT INFO

ENGINEER:  
CRAIG HARTMAN, RCE 73837  
HARTMAN ENGINEERING, INC.  
3121 W. CERES CT.  
VISALIA, CA 93291  
(559) 563-0181

DAIRY CONTACT:  
JAKE DE JONG  
14782 8TH AVE  
HANFORD, CA 93230



113 N. CHURCH ST,  
SUITE 521  
VISALIA, CA 93291  
(559) 563-0181



PROJECT:

HIGH ROLLER

DAIRY  
DIGESTER

CLIENT:

JAKE DE JONG  
14782 8TH AVE  
HANFORD, CA 93230

REVISION LOG:

PLOT DATE: 01/20/19

JOB NO.: 17003

SCALE: AS SHOWN

SHEET NO.: A.1



SPECIFICATIONS FOR ENGINEERED FILL MATERIAL OF ABOVE GRADE EMBANKMENTS OR AS REQUIRED

TEST PARAMETER	TEST METHOD	FREQUENCY	ACCEPTANCE CRITERIA
Compaction Curves	ASTM D1557 (Modified Proctor)	Change in material	N/A
Grain Size Distribution	ASTM D422 (Sieve)	Change in material	At least 30% passing No. 200 U.S. Standard Sieve. Per Specifications (1)
Soil Classification	ASTM D2487 (USCS)	Change in material	Suitable for compaction <sup>(2,3)</sup>
Maximum Particle Size	ASTM D422 (Sieve)	Change in material	½ inch, ¼ top 6 inches
Maximum Water soluble Sulfate (SO <sup>4-</sup> ) in Soil (Concrete Slab locations)	ASTM C1580	Change in material	0.2% by weight
Site Preparation Specifications:			
1. Clearing: Prior to earthwork operations, the area to be developed should be stripped of vegetation, organic topsoil, and cleared of cow waste and miscellaneous debris from the proposed construction areas. Deeper clearing may be required in localized areas. The actual depth of clearing should be reviewed by a licensed Geotechnical Engineer at the time of construction. The limits of stripping and clearing should be at least five feet bey ond the limits of construction.			
2. Compaction: The scarified subgrade and subsequent fill placed at the site should be moisture conditioned to near optimum moisture content, and compacted to at least and 90 percent for 2:1 side slope pond of maximum dry density as determined by ASTM test method D1557.			
3. Material for fill: Fill should consist of select material. Nativ e soil, free from organic, vegetation, and rocks or cobbles larger than three inches, may be used as fill at the site. Import material must be reviewed by licensed Geotechnical Engineer prior to transport to the site.			
4. Fill placement: Fill material should be moisture-conditioned to +/- 2% of the optimum moisture content prior to compaction. Fill material with excessiv e moisture should be allowed to dry prior to compaction or be mixed with dry soil to bring the fill to a workable moisture content. Fill should be placed in level lifts not exceeding a loose, uncompacted thickness of eight inches, and compacted as engineered fill.			
Sub-grade requirements for fill only :			
-Over Excavate for minimum 1 ft. to meet Engineered Fill Borrow Material Guidelines and Pond Liner Sub-grade requirements			
-Well mixed soil			
-6 in max lifts			
-Upper 6 inches is of fine-finished soil particles no greater than ¼ in.+			
Notes:			
Field tests shall not be required, but fill borrow material specifications must meet the acceptance criteria outlined in Table 1.			
Refer to Geotechnical Report			

FILL TEST SPECIFICATIONS FOR SUB-GRADE

TEST PARAMETER	TEST METHOD <sup>(1,2)</sup>	FREQUENCY	ACCEPTANCE CRITERIA
Uncompacted Lift Thickness	Visual Observation	Continuous	8-in. <sup>(1,2)</sup>
Construction Oversight	Visual Observation	Continuous	Maximum particle size 1/2 inch.
In-Place Moisture Alternative Method	ASTM D2216 (Oven Dry)	1 per every 10 Nuclear tests	+/-2% of Optimum Moisture Content per ASTM D1557
In-Place Moisture Rapid Field Methods <sup>(1,2,3,4)</sup>	ASTM D6938 <sup>(3,4,5)</sup> (Nuclear Method)	3 per acre per lift, min. 2 per day	+/-2% of Optimum Moisture Content per ASTM D1557
In-Place Density Alternat e Method	ASTM D2937(Drive Cylinder)	1 per every 10 Nuclear tests	90% of Maximum Dry Density per ASTM D1557
In-Place Density Rapid Field Methods <sup>(1,2)</sup>	ASTM D6938 <sup>(3,4,5)</sup> (Nuclear Method)	3 per acre per lift, min. 2 per day	90% of Maximum Dry Density per ASTM D1557
Subgrade Thickness	Surveying Measurement	At 50-foot centers	Minimum 1 ft. <sup>(1,2)</sup>
Clod Size	Visual Observation	Continuous	Per Specification

Notes:

See earthwork section for anchor trench, excavation, backfill, and compaction requirements.

<sup>1</sup> ASTM Test Method, unless otherwise noted. Results of all tests performed to be reported as per method reporting criteria.

<sup>2</sup> The sub-grade shall be scarified to a depth of 1 ft. lower than finished grade, compacted, and tested in accordance with the requirements of this table.

<sup>3</sup> Must be verified by ASTM D2216 (Oven) overnight method once every day or once per change in material

<sup>4</sup> Must be verified by ASTM D2937 (Dry Cylinder) twice per day or per change in material

<sup>5</sup> Calibration Procedure: ASTM D7013-04: Standard Guide for Nuclear Surface Moisture and Density Gauge Calibration Facility Set-up

POND SPECIFICATIONS FOR SUBGRADES CUT BELOW GROUND (For Slopes 2:1 or shallower)

**Side Slopes:** The certified Civil Engineer/CQA Chief Officer shall walk final side slopes after cut by heavy equipment and confirm no SW or SP soils and no loose soils. All SW, SP, or soils that are not amenable to a firm and unyielding subgrade shall be removed and replaced down to a minimum 3 ft. below sloped surface. Any soils removed and replaced shall meet the Engineered Fill requirements in Table 1.

**Pond Bottom:** 1. An as-built survey of the pond bottom shall take place after subgrade construction to insure minimum slopes are achieved. Pond Bottom shall be tested per criteria below. Any soils not meeting the requirements below (i.e. that is not firm and unyielding) shall be removed and replaced down to a minimum 2 ft. Any soils removed and replaced shall meet the Engineered Fill requirements in Table 1. The Civil Engineer may make determination of soils meeting requirements or not based upon visual inspection which shall be included in the Subgrade Certification Report and signed and sealed by a Civil Engineer and CQA Officer.

TEST PARAMETER	TEST METHOD <sup>(1,2)</sup>	FREQUENCY	ACCEPTANCE CRITERIA
In-Place Density Rapid Field Methods <sup>(1,2)</sup>	ASTM D6938 <sup>(3,4,5)</sup> (Nuclear)	3 per acre	90% of Maximum Dry Density per ASTM D1557
In-Place Moisture Rapid Field Methods <sup>(1,2,3,4)</sup>	ASTM D6938 <sup>(3,4,5)</sup> (Nuclear Methods)	3 per acre per lift, min. 2 per day	+/-2% of Optimum Moisture Content per ASTM D1557
Construction Oversight	Visual Observation	Continuous	Maximum particle size 1/2 inch.
Subgrade Slope	Surveying Measurement	200 ft. maximum grid	Min 1%

60 MIL HDPE GEOMEMBRANE CONSTRUCTION QUALITY ASSURANCE (CQA)


TEST PARAMETER	TEST METHOD	FREQUENCY	ACCEPTANCE CRITERIA
Thickness (min. ave.) -Lowest individual for 8 out of 10 values -Lowest individual for any of the 10 values	ASTM D5994	1 per lot or 1 per 70,000 ft <sup>2</sup> , whichever is greater	Nom. (-5%)  -10%  -15%
Tensile Properties -yield strength -break strength -strain at yeild -break strength	ASTM D6693 Type IV	1 per lot or 1 per 70,000 ft <sup>2</sup> , whichever is greater	≥126 lb./in. ≥90 lb./in. ≥12% ≥100%
Puncture Resistance	ASTM D4833	1 per lot or 1 per 70,000 ft <sup>2</sup> , whichever is greater	108 lb. (min.)
Tear Resistance	ASTM D1004, Die C	1 per lot or 1 per 70,000 ft <sup>2</sup> , whichever is greater	42 lb. (min.)
Interface Shear -60-mil HDPE/subgrade soil -Drainage geocomposite	ASTM D5321 ASTM D6243	2 tests or 1 per 200,000 ft <sup>2</sup> , whichever is greater	
Seam Shear	ASTM D6392	1 test per 500 lineal feet or per GRI GM-14 and 20.	95% of min. yield strength
Seam Peel -Extrusion -Fusion	ASTM D6392	1 test per 500 lineal feet or per GRI GM-14 and 20.	72% yield & ffb (1)
Non-destructive Seam Test	ASTM D5820 (Pressure Test)	Continuous	35 psi for 5 min.
	ASTM D5641 (Vacuum Box)		5 psi for 15 sec.
	ASTM D5641 (Spark Test)		No Spark
Electric Leak Location	ASTM D7002 (Water Puddle)	Once on constructed liner	Max 1 mm. diameter hole sensitivity
	ASTM D6747 (Selection Process)		
	ASTM D7007 (Water /Earth)		Max 6 mm. diameter hole sensitivity
	ASTM D7240 (Spark Test 2011)		
Notes: ffb: Film Tear Bond			

NOTES:

THE APPROVED WORK PLAN WHICH INCLUDES THE CONSTRUCTION QUALITY ASSURANCE PLAN, OPERATION, MAINTENANCE AND MONITORING PLAN, CONSTRUCTION DRAWINGS, AND SOILS REPORT TOGETHER AS A PACKAGE ARE THE COMPLETE SPECIFICATIONS REQUIRED FOR CONSTRUCTION OF THE POND AND LINER SYSTEM.



113 N. CHURCH ST,  
SUITE 521  
VISALIA, CA 93291  
(559) 563-0181



PROJECT:

HIGH ROLLER

DAIRY  
DIGESTER

CLIENT:  
JAKE DE JONG  
14782 8TH AVE  
HANFORD, CA 93230

GENERAL NOTES  
CONSTRUCTION

REVISION LOG:

PLOT DATE: 01/20/19

JOB NO.: 17003

SCALE: AS SHOWN

SHEET NO.: A.2  
of 158 0160





113 N. CHURCH ST,  
SUITE 521  
VISALIA, CA 93291  
(559) 563-0181



PROJECT:  
**HIGH ROLLER**

**DAIRY  
DIGESTER**

CLIENT:  
JAKE DE JONG  
14782 8TH AVE  
HANFORD, CA 93230

SITE PLAN

DIGESTER

REVISION LOG:

PLOT DATE: 01/20/19

JOB NO.: 17003

SCALE: AS SHOWN

SHEET NO.: A.3





113 N. CHURCH ST,  
SUITE 521  
VISALIA, CA 93291  
(559) 563-0181



PROJECT:

**HIGH ROLLER**

**DAIRY  
DIGESTER**

CLIENT:  
JAKE DE JONG  
14782 8TH AVE  
HANFORD, CA 93230

SITE PLAN  
DAIRY

REVISION LOG:

PLOT DATE: 01/20/19

JOB NO.: 17003


SCALE: AS SHOWN

SHEET NO.: A.4



GRADING NOTES:

- 1.CONTRACTOR SHALL INFORM ENGINEER OF ANY DISCREPANCIES OR ERRORS IN PLANS PRIOR TO CONSTRUCTION.
2. CONTRACTOR SHALL MEET SPECIFICATIONS OF TABLE 2 WITHIN THE APPROVED CONSTRUCTION QUALITY CONTROL PLAN.
3. CONTRACTOR SHALL SMOOTH DRUM ROLL FINAL SURFACE AND REMOVE ANY ROCK OR MATERIAL GREATER THAN  $\frac{1}{2}$  INCH.



113 N. CHURCH ST,  
SUITE 521  
VISALIA, CA 93291  
(559) 563-0181



PROJECT:  
**HIGH ROLLER**  
  
**DAIRY**  
**DIGESTER**

CLIENT:  
JAKE DE JONG  
14782 8TH AVE  
HANFORD, CA 93230



GRADING PLAN

DIGESTER

REVISION LOG:

PLOT DATE:	01/20/19
JOB NO.:	17003
SCALE:	AS SHOWN
SHEET NO.:	C.1





113 N. CHURCH ST,  
SUITE 521  
VISALIA, CA 93291  
(559) 563-0181



PROJECT:

HIGH ROLLER

DAIRY  
DIGESTER

CLIENT:  
JAKE DE JONG  
14782 8TH AVE  
HANFORD, CA 93230

GRADING SECTIONS

DIGESTER

REVISION LOG:


PLOT DATE: 01/20/19

JOB NO.: 17003

SCALE: AS SHOWN

SHEET NO.: C.2






**A ANCHOR TRENCH / SUMP PROFILE VIEW**


N.T.S.

DIMENSION TABLE (FT.)	
LETTER	POND
L	1.7'
M.1	2.7'
U	20'
R	1.5'
S	3'
T	3'
X	30'
Y	30'
Z	5.5'



**B SUMP PLAN VIEW**

N.T.S.



**C SIDE SLOPE TRENCH**

N.T.S.



113 N. CHURCH ST,  
SUITE 521  
VISALIA, CA 93291  
(559) 563-0181



PROJECT:

**HIGH ROLLER**

**DAIRY  
DIGESTER**

CLIENT:  
JAKE DE JONG  
14782 8TH AVE  
HANFORD, CA 93230

GRADING DETAIL  
DIGESTER

REVISION LOG:




PLOT DATE: 01/20/19

JOB NO.: 17003


SCALE: AS SHOWN

SHEET NO.: C.3 0165





- NOTES:
1. GAS VENTS AROUND PERIPHERY OF LAGOON @ MAX. 40' O.C.
  2. STRAP NOT WELDED TO BIO-GAS HEADER PIPE.
  3. WRAP 60 MIL PRIMARY LINER OVER CONCRETE & EXTRUSION WELD.



113 N. CHURCH ST,  
SUITE 521  
VISALIA, CA 93291  
(559) 563-0181



PROJECT:  
**HIGH ROLLER**  
  
**DAIRY**  
**DIGESTER**

CLIENT:  
JAKE DE JONG  
14782 8TH AVE  
HANFORD, CA 93230

COVER SYSTEM  
DIGESTER


REVISION LOG:

PLOT DATE: 01/20/19  
JOB NO.: 17003  
SCALE: AS SHOWN  
SHEET NO.: D.1











**MIXER - HATCH**

N.T.S.




**AIR INJECTION & MIXER HATCH**

N.T.S.




**MIXER - PLAN VIEW**

N.T.S.




**MIXER - ISOMETRIC W/FLOAT IN PLACE**

N.T.S.




**MIXER - ISOMETRIC**

N.T.S.




**MIXER - SIDE VIEW**

N.T.S.



**MIXER - FRONT VIEW**

N.T.S.



113 N. CHURCH ST,  
SUITE 521  
VISALIA, CA 93291  
(559) 563-0181



PROJECT:

**HIGH ROLLER**

**DAIRY  
DIGESTER**

CLIENT:

JAKE DE JONG  
14782 8TH AVE  
HANFORD, CA 93230

MIXER  
DETAILS

REVISION LOG:

PLOT DATE: 01/20/19


JOB NO.: 17003

SCALE: AS SHOWN

SHEET NO.: D.3


100 0168






**MOISTURE TRAP DETAIL**

N.T.S.




**BIO-GAS VALVE**

N.T.S.



**BALL VALVE JUNCTION**

N.T.S.



**BOLLARD DETAIL**

N.T.S.



113 N. CHURCH ST,  
SUITE 521  
VISALIA, CA 93291  
(559) 563-0181



PROJECT:

**HIGH ROLLER**

**DAIRY  
DIGESTER**

CLIENT:  
JAKE DE JONG  
14782 8TH AVE  
HANFORD, CA 93230

DETAILS

REVISION LOG:


PLOT DATE: 01/20/19

JOB NO.: 17003


SCALE: AS SHOWN

SHEET NO.: D.4






**FRONT VIEW**




**SIDE VIEW**

**LCRS, LYSIMETER AND DRAINAGE SUMP PROFILE**




**DIGESTER ANCHOR TRENCH DETAIL**

NOTES: 1. CONTRACTOR TO USE ANCHOR SYSTEM OR PROVIDE DETAILS AND DESIGN FOR ALTERNATIVE TO BE APPROVED BY ENGINEER. N.T.S.



**HDPE CROSS SECTION**

N.T.S.



**TYPICAL PERFORATION DETAIL**

N.T.S.

A

B  
L.1


C  
L.1

D  
L.1





OPTIONAL TIER 1 DOUBLE LINER-LAYERING SYSTEM WITH DRAIN LINER VERIFY WITH OWNER


SMOOTH/STUDDED/ 60-NET-60 LINER LAYERS					
DESCRIPTION	LOCATION	MATERAIL	THICKNESS (MIN)	TOP FINISH	BOTTOM FINISH
PRIMARY LINER	TOP	HDPE	60 MIL	SMOOTH	SMOOTH CONDUCTIVE
DRAINAGE NET	MIDDLE	HDPE	200 MIL	N/A	N/A
SECONDARY LINER	BOTTOM	HDPE	60 MIL	SMOOTH	SMOOTH



**A** DOUBLE LAYER 60-NET-60 DOUBLE LAYER WITH DRAIN LINER N.T.S.




**B** HDPE LINER-SMOOTH WELDS N.T.S.



DRAIN LINER SMOOTH END WELD PATCH

**C** 3'X3' DRAIN PATCH WELD N.T.S.

1.1.3 - Engineered Project Site Plan and Design - High Roller Dairy




**D** AGRU DRAIN LINER END/END WELD N.T.S.

NOTE: AGRU DRAIN LINER DOES NOT HAVE STUDS ALONG THE EDGE SO EDGE/EDGE SEAMS DO NOT REQUIRE DRINGING OR CAP.

2' WIDE STRIP OF 200 MIL GEONET. TACK WELD AT 8'

**C** 3'X3' DRAIN PATCH P.3



NOTE: CQA OFFICER IS RESPONSIBLE TO ADD PATCHES AS NEEDED FOR FLOW

**E** AGRU DRAIN LINER CROSS SEAM NET PLAN VIEW N.T.S.

NOTE: TYPICAL OF ALL DRAIN LINERS

1.2 - Lakeside Pipeline LLC - Application - 2018 Solicitation SB 1383 Dairy Pilot Projects

THIS IS AN ORIGINAL UNPUBLISHED WORK AND MAY NOT BE DUPLICATED, PUBLISHED OR OTHERWISE USED WITHOUT THE WRITTEN CONSENT OF HARTMAN ENGINEERING INC. ©



113 N. CHURCH ST,  
SUITE 521  
VISALIA, CA 93291  
(559) 563-0181



PROJECT:  
**HIGH ROLLER**

**DAIRY  
DIGESTER**

CLIENT:  
JAKE DE JONG  
14782 8TH AVE  
HANFORD, CA 93230


LINER  
DETAILS

REVISION LOG:


PLOT DATE:	01/20/19
JOB NO.:	17003
SCALE:	AS SHOWN
SHEET NO.:	L2

171






**A** **BOOT SKIRT** N.T.S.



**B** **BOOTLESS PIPE PENETRATION** N.T.S.



**C** **VENT ORIFICE (ISOMETRIC VIEW)** N.T.S.



113 N. CHURCH ST,  
SUITE 521  
VISALIA, CA 93291  
(559) 563-0181



PROJECT:

**HIGH ROLLER**

**DAIRY  
DIGESTER**

CLIENT:  
JAKE DE JONG  
14782 8TH AVE  
HANFORD, CA 93230

LINER  
DETAILS

REVISION LOG:

PLOT DATE: 01/20/19

JOB NO.: 17003

SCALE: AS SHOWN

SHEET NO.: L3



# LAKE SIDE ENERGY DAIRY

## DAIRY DIGESTER

### BENCHMARK

THE TOPOGRAPHIC SURVEY WAS PERFORMED UTILIZING GLOBAL POSITIONING SYSTEM OBSERVATIONS. DISTANCES AND NUMBERS SHOWN ARE TO BE CONSIDERED GROUND VALUES. BENCHMARK AND CONTROL SHOWN ON CONTROL PLAN SHEET. THE BENCHMARK AND VERTICAL ELEVATIONS WERE DERIVED FROM THE NGS ONLINE POSITIONING SERVICE (OPUS), AND IS SHOWN ON THE NAVD 88 DATUM UTILITIZING THE GEOID 09 AS THE VERTICAL MODEL.

### PRESERVATION OF MONUMENTS

PURSUANT TO SECTIONS 8771(B) AND 8771(C) OF THE GOVERNMENT CODE, ANY MONUMENTS THAT CONTROL THE LOCATION OF BOUNDARIED, OR OTHERWISE PROVIDE HORIZONTAL OR VERTICAL SURVEY CONTROL WITHIN THE CONSTRUCTION AREA, SHALL BE LOCATED AND REFERENCED PRIOR TO CONSTRUCTION, AND A CORNER RECORD OR RECORD OF SURVEY OF THE REFERENCES SHALL BE FILED WITH THE COUNTY SURVEYOR.


PERMANENT MONUMENTATION SHALL BE SET TO PERPETUATE THE LOCATION OF ANY MONUMENT WHICH COULD BE DAMAGED OR DESTROYED, AND A CORNER RECORD OR RECORD OF SURVEY SHALL BE FILED WITH THE COUNTY SURVEYOR PRIOR TO THE RECORDING OF A CERTIFICATE OF COMPLETION FOR THE PROJECT.

### DUST CONTROL NOTES

CONTRACTOR IS REQUIRED TO COMPLY WITH GOOD HOUSE KEEPING PRACTICES

### STORMWATER (SWPPP) NOTES

CONTRACTOR IS REQUIRED TO COMPLY WITH GOOD HOUSE KEEPING PRACTICES



VICINITY MAP

SCALE 1" : 2 MI

### SHEET INDEX

#### GENERAL NOTES

- A.1 COVER SHEET
- A.2 GENERAL NOTES
- A.3 SITE PLAN - DAIRY
- A.4 SITE PLAN - DIGESTER

#### CIVIL DRAWINGS

- C.1 GRADING PLAN
- C.2 CROSS SECTIONS
- C.3 GRADING DETAILS

#### DIGESTER DRAWINGS

- D.1 COVER SYSTEM
- D.2 SLURRY SYSTEM
- D.3 MIXERS
- D.4 DETAILS


#### LINER DRAWINGS

- L.1 LINER - DETAILS
- L.2 LINER - DETAILS
- L.3 LINER - DETAILS

### SHEET REFERENCE

#### SECTIONS:

SECTION NAME  
SHEET NUMBER



#### DETAILS:

DETAIL NAME  
SHEET NUMBER



B  
C.3

### CONTACT INFO

ENGINEER:  
CRAIG HARTMAN, RCE 73837  
HARTMAN ENGINEERING, INC.  
3121 W. CERES CT.  
VISALIA, CA 93291  
(559) 563-0181

DAIRY CONTACT:  
MIKE MONTEIRO  
8606 KENT AVE,  
HANFORD, CA 93230



113 N. CHURCH ST,  
SUITE 521  
VISALIA, CA 93291  
(559) 563-0181



PROJECT:

LAKE SIDE ENERGY

DAIRY  
DIGESTER

CLIENT:  
MIKE MONTEIRO  
8606 KENT AVE,  
HANFORD, CA 93230

REVISION LOG:

PLOT DATE: 01/08/18

JOB NO.: 17003

SCALE: AS SHOWN

SHEET NO.: A.1



SPECIFICATIONS FOR ENGINEERED FILL MATERIAL OF ABOVE GRADE EMBANKMENTS OR AS REQUIRED

TEST PARAMETER	TEST METHOD	FREQUENCY	ACCEPTANCE CRITERIA
Compaction Curves	ASTM D1557 (Modified Proctor)	Change in material	N/A
Grain Size Distribution	ASTM D422 (Sieve)	Change in material	At least 30% passing No. 200 U.S. Standard Sieve. Per Specifications (1)
Soil Classification	ASTM D2487 (USCS)	Change in material	Suitable for compaction (2,3)
Maximum Particle Size	ASTM D422 (Sieve)	Change in material	½ inch, ¼ top 6 inches
Maximum Water soluble Sulfate (SO <sup>4-</sup> ) in Soil (Concrete Slab locations)	ASTM C1580	Change in material	0.2% by weight
Site Preparation Specifications:			
1. Clearing: Prior to earthwork operations, the area to be developed should be stripped of vegetation, organic topsoil, and cleared of cow waste and miscellaneous debris from the proposed construction areas. Deeper clearing may be required in localized areas. The actual depth of clearing should be reviewed by a licensed Geotechnical Engineer at the time of construction. The limits of stripping and clearing should be at least five feet bey ond the limits of construction.			
2. Compaction: The scarified subgrade and subsequent fill placed at the site should be moisture conditioned to near optimum moisture content, and compacted to at least and 90 percent for 2:1 side slope pond of maximum dry density as determined by ASTM test method D1557.			
3. Material for fill: Fill should consist of select material. Native soil, free from organic, vegetation, and rocks or cobbles larger than three inches, may be used as fill at the site. Import material must be reviewed by licensed Geotechnical Engineer prior to transport to the site.			
4. Fill placement: Fill material should be moisture-conditioned to +/- 2% of the optimum moisture content prior to compaction. Fill material with excessiv e moisture should be allowed to dry prior to compaction or be mixed with dry soil to bring the fill to a workable moisture content. Fill should be placed in level lifts not exceeding a loose, uncompacted thickness of eight inches, and compacted as engineered fill.			
Sub-grade requirements for fill only :			
-Over Excavate for minimum 1 ft. to meet Engineered Fill Borrow Material Guidelines and Pond Liner Sub-grade requirements			
-Well mixed soil			
-6 in max lifts			
-Upper 6 inches is of fine-finished soil particles no greater than ¼ in.+			
Notes:			
Field tests shall not be required, but fill borrow material specifications must meet the acceptance criteria outlined in Table 1.			
Refer to Geotechnical Report			

FILL TEST SPECIFICATIONS FOR SUB-GRADE

TEST PARAMETER	TEST METHOD (1)	FREQUENCY	ACCEPTANCE CRITERIA
Uncompacted Lift Thickness	Visual Observation	Continuous	8-in.(2)
Construction Oversight	Visual Observation	Continuous	Maximum particle size 1/2 inch.
In-Place Moisture Alternative Method	ASTM D2216 (Oven Dry)	1 per every 10 Nuclear tests	+/-2% of Optimum Moisture Content per ASTM D1557
In-Place Moisture Rapid Field Methods (3,4,5)	ASTM D6938 (Nuclear Method)	3 per acre per lift, min. 2 per day	+/-2% of Optimum Moisture Content per ASTM D1557
In-Place Density Altern ate Method	ASTM D2937(Drive Cylinder)	1 per every 10 Nuclear tests	90% of Maximum Dry Density per ASTM D1557
In-Place Density Rapid Field Methods (1)	ASTM D6938 (Nuclear Method)	3 per acre per lift, min. 2 per day	90% of Maximum Dry Density per ASTM D1557
Subgrade Thickness	Surveying Measurement	At 50-foot centers	Minimum 1 ft.(5)
Clod Size	Visual Observation	Continuous	Per Specification

Notes:

See earthwork section for anchor trench, excavation, backfill, and compaction requirements.

(1) ASTM Test Method, unless otherwise noted. Results of all tests performed to be reported as per method reporting criteria.

(2) The sub-grade shall be scarified to a depth of 1 ft. lower than finished grade, compacted, and tested in accordance with the requirements of this table.

(3) Must be verified by ASTM D2216 (Oven) overnight method once every day or once per change in material

(4) Must be verified by ASTM D2937 (Dry Cylinder) twice per day or per change in material

(5) Calibration Procedure: ASTM D7013-04: Standard Guide for Nuclear Surface Moisture and Density Gauge Calibration Facility Set-up

POND SPECIFICATIONS FOR SUBGRADES CUT BELOW GROUND (For Slopes 2:1 or shallower)

**Side Slopes:** The certified Civil Engineer/CQA Chief Officer shall walk final side slopes after cut by heavy equipment and confirm no SW or SP soils and no loose soils. All SW, SP, or soils that are not amenable to a firm and unyielding subgrade shall be removed and replaced down to a minimum 3 ft. below sloped surface. Any soils removed and replaced shall meet the Engineered Fill requirements in Table 1.

**Pond Bottom:** 1. An as-built survey of the pond bottom shall take place after subgrade construction to insure minimum slopes are achieved. Pond Bottom shall be tested per criteria below. Any soils not meeting the requirements below (i.e. that is not firm and unyielding) shall be removed and replaced down to a minimum 2 ft. Any soils removed and replaced shall meet the Engineered Fill requirements in Table 1. The Civil Engineer may make determination of soils meeting requirements or not based upon visual inspection which shall be included in the Subgrade Certification Report and signed and sealed by a Civil Engineer and CQA Officer.

TEST PARAMETER	TEST METHOD (1)	FREQUENCY	ACCEPTANCE CRITERIA
In-Place Density Rapid Field Methods (1)	ASTM D6938 (Nuclear)	3 per acre	90% of Maximum Dry Density per ASTM D1557
In-Place Moisture Rapid Field Methods (3,4,5)	ASTM D6938 (Nuclear Methods)	3 per acre per lift, min. 2 per day	+/-2% of Optimum Moisture Content per ASTM D1557
Construction Oversight	Visual Observation	Continuous	Maximum particle size 1/2 inch.
Subgrade Slope	Surveying Measurement	200 ft. maximum grid	Min 1%

60 MIL HDPE GEOMEMBRANE CONSTRUCTION QUALITY ASSURANCE (CQA)

TEST PARAMETER	TEST METHOD	FREQUENCY	ACCEPTANCE CRITERIA
Thickness (min. ave.) -Lowest individual for 8 out of 10 values -Lowest individual for any of the 10 values	ASTM D5994	1 per lot or 1 per 70,000 ft <sup>2</sup> , whichever is greater	Nom. (-5%)  -10%  -15%
Tensile Properties -yield strength -break strength -strain at yeild -break strength	ASTM D6693 Type IV	1 per lot or 1 per 70,000 ft <sup>2</sup> , whichever is greater	≥126 lb./in. ≥90 lb./in. ≥12% ≥100%
Puncture Resistance	ASTM D4833	1 per lot or 1 per 70,000 ft <sup>2</sup> , whichever is greater	108 lb. (min.)
Tear Resistance	ASTM D1004, Die C	1 per lot or 1 per 70,000 ft <sup>2</sup> , whichever is greater	42 lb. (min.)
Interface Shear -60-mil HDPE/subgrade soil -Drainage geocomposite	ASTM D5321 ASTM D6243	2 tests or 1 per 200,000 ft <sup>2</sup> , whichever is greater	
Seam Shear	ASTM D6392	1 test per 500 lineal feet or per GRI GM-14 and 20.	95% of min. yield strength
Seam Peel -Extrusion -Fusion	ASTM D6392	1 test per 500 lineal feet or per GRI GM-14 and 20.	72% yield & ffb (1)
Non-destructive Seam Test	ASTM D5820 (Pressure Test)	Continuous	35 psi for 5 min.
	ASTM D5641 (Vacuum Box)		5 psi for 15 sec.
	ASTM D5641 (Spark Test)		No Spark
Electric Leak Location	ASTM D7002 (Water Puddle)	Once on constructed liner	Max 1 mm. diameter hole sensitivity
	ASTM D6747 (Selection Process)		
	ASTM D7007 (Water /Earth)		Max 6 mm. diameter hole sensitivity
	ASTM D7240 (Spark Test 2011)		
Notes: ffb: Film Tear Bond			



113 N. CHURCH ST,  
SUITE 521  
VISALIA, CA 93291  
(559) 563-0181



PROJECT:  
**LAKESIDE ENERGY**

**DAIRY  
DIGESTER**

CLIENT:  
**MIKE MONTEIRO**  
8606 KENT AVE,  
HANFORD, CA 93230

GENERAL NOTES CONSTRUCTION	REVISION LOG:				

PLOT DATE:	01/08/18
JOB NO.:	17003
SCALE:	AS SHOWN
SHEET NO.:	A.2





113 N. CHURCH ST,  
SUITE 521  
VISALIA, CA 93291  
(559) 563-0181



PROJECT:  
**LAKESIDE ENERGY**

**DAIRY  
DIGESTER**

CLIENT:  
MIKE MONTEIRO  
8606 KENT AVE,  
HANFORD, CA 93230

SITE PLAN  
DIGESTER

REVISION LOG:

PLOT DATE: 01/08/18

JOB NO.: 17003

SCALE: AS SHOWN

SHEET NO.: A.3

1.2 - Lakeside Pipeline LLC - Application - 2018 Solicitation SB 1383 Dairy Pilot Projects

THIS IS AN ORIGINAL UNPUBLISHED WORK AND MAY NOT BE DUPLICATED, PUBLISHED OR OTHERWISE USED WITHOUT THE WRITTEN CONSENT OF HARTMAN ENGINEERING INC. ©





113 N. CHURCH ST,  
SUITE 521  
VISALIA, CA 93291  
(559) 563-0181



PROJECT:  
**LAKESIDE ENERGY**

**DAIRY  
DIGESTER**

CLIENT:  
MIKE MONTEIRO  
8606 KENT AVE,  
HANFORD, CA 93230

SITE PLAN  
DAIRY



REVISION LOG:

PLOT DATE:	01/08/18
JOB NO.:	17003
SCALE:	AS SHOWN
SHEET NO.:	A.4









113 N. CHURCH ST,  
SUITE 521  
VISALIA, CA 93291  
(559) 563-0181



PROJECT:  
**LAKESIDE ENERGY**

**DAIRY  
DIGESTER**


CLIENT:  
MIKE MONTEIRO  
8606 KENT AVE,  
HANFORD, CA 93230

GRADING SECTIONS

DIGESTER			
REVISION LOG:			

PLOT DATE:	01/08/18
JOB NO.:	17003
SCALE:	AS SHOWN
SHEET NO.:	C.2






**A** ANCHOR TRENCH / SUMP PROFILE VIEW


N.T.S.

DIMENSION TABLE (FT.)	
LETTER	POND
L	1.7'
M.1	2.7'
U	20'
R	1.5'
S	3'
T	3'
X	30'
Y	30'
Z	5.5'



**B** SUMP PLAN VIEW

N.T.S.



**C** SIDE SLOPE TRENCH

N.T.S.



113 N. CHURCH ST,  
SUITE 521  
VISALIA, CA 93291  
(559) 563-0181



PROJECT:

**LAKESIDE ENERGY**

**DAIRY  
DIGESTER**

CLIENT:  
MIKE MONTEIRO  
8606 KENT AVE,  
HANFORD, CA 93230

GRADING DETAIL

DIGESTER

REVISION LOG:


PLOT DATE: 01/08/18

JOB NO.: 17003

SCALE: AS SHOWN

SHEET NO.: C.3






**A BALLAST TUBE DETAIL**


N.T.S.

DESCRIPTION	LOCATION	MATERIAL	THICKNESS (MIN)	TOP FINISH	BOTTOM FINISH
COVER	TOP	HDPE	80 MIL	SMOOTH	SMOOTH



**C HDPE COVER-SMOOTH WELDS**

N.T.S.



**B BIO-GAS PIPING DETAIL**

N.T.S.

- NOTES:
1. GAS VENTS AROUND PERIPHERY OF LAGOON @ MAX. 40' O.C.
  2. STRAP NOT WELDED TO BIO-GAS HEADER PIPE.
  3. WRAP 60 MIL PRIMARY LINER OVER CONCRETE & EXTRUSION WELD.

PROJECT:

**LAKESIDE ENERGY**

**DAIRY  
DIGESTER**

CLIENT:  
MIKE MONTEIRO  
8606 KENT AVE,  
HANFORD, CA 93230

COVER SYSTEM  
DIGESTER

REVISION LOG:





PLOT DATE: 01/08/18

JOB NO.: 17003


SCALE: AS SHOWN

SHEET NO.: D.1  
170 0180











**MIXER - HATCH**

N.T.S.




**AIR INJECTION & MIXER HATCH**

N.T.S.




**MIXER - PLAN VIEW**

N.T.S.




**MIXER - ISOMETRIC W/FLOAT IN PLACE**

N.T.S.




**MIXER - ISOMETRIC**

N.T.S.




**MIXER - SIDE VIEW**

N.T.S.



**MIXER - FRONT VIEW**

N.T.S.



113 N. CHURCH ST,  
SUITE 521  
VISALIA, CA 93291  
(559) 563-0181



PROJECT:

**LAKESIDE ENERGY**

**DAIRY  
DIGESTER**

CLIENT:  
MIKE MONTEIRO  
8606 KENT AVE,  
HANFORD, CA 93230

MIXER  
DETAILS

REVISION LOG:

PLOT DATE: 01/08/18

JOB NO.: 17003

SCALE: AS SHOWN

SHEET NO.: D.3









GENERAL NOTES  
LINER  
DETAILS

REVISION LOG:

PLOT DATE:	01/08/18
JOB NO.:	17003
SCALE:	AS SHOWN
SHEET NO.:	L.1




**FRONT VIEW**




**SIDE VIEW**

**LCRS, LYSIMETER AND DRAINAGE SUMP PROFILE**




**DIGESTER ANCHOR TRENCH DETAIL**

NOTES: 1. CONTRACTOR TO USE ANCHOR SYSTEM OR PROVIDE DETAILS AND DESIGN FOR ALTERNATIVE TO BE APPROVED BY ENGINEER. N.T.S.



**HDPE CROSS SECTION**

N.T.S.



**TYPICAL PERFORATION DETAIL**

N.T.S.

A

B  
L.1


C  
L.1

D  
L.1





OPTIONAL TIER 1 DOUBLE LINER-LAYERING SYSTEM WITH DRAIN LINER VERIFY WITH OWNER


SMOOTH/STUDDED/ 60-NET-60 LINER LAYERS					
DESCRIPTION	LOCATION	MATERIAL	THICKNESS (MIN)	TOP FINISH	BOTTOM FINISH
PRIMARY LINER	TOP	HDPE	60 MIL	SMOOTH	SMOOTH CONDUCTIVE
DRAINAGE NET	MIDDLE	HDPE	200 MIL	N/A	N/A
SECONDARY LINER	BOTTOM	HDPE	60 MIL	SMOOTH	SMOOTH



**A** DOUBLE LAYER 60-NET-60  
DOUBLE LAYER WITH DRAIN LINER N.T.S.




**B** HDPE LINER-SMOOTH WELDS N.T.S.



DRAIN LINER SMOOTH END WELD PATCH

**C** 3'X3' DRAIN PATCH WELD N.T.S.


3.6 - Engineered Digester Site Plan and Design - Lakeside Dairy



**D** AGRU DRAIN LINER END/END WELD  
NOTE: AGRU DRAIN LINER DOES NOT HAVE STUDS ALONG THE EDGE SO EDGE/EDGE SEAMS DO NOT REQUIRE DRINGING OR CAP. N.T.S.

2' WIDE STRIP OF 200 MIL  
GEONET. TACK WELD AT 8'

**C**  
**P.3** 3'X3' DRAIN PATCH



NOTE: CQA OFFICER IS RESPONSIBLE TO ADD PATCHES AS NEEDED FOR FLOW

**E** AGRU DRAIN LINER CROSS SEAM NET PLAN VIEW  
NOTE: TYPICAL OF ALL DRAIN LINERS

1.2 - Lakeside Pipeline LLC - Application - 2018 Solicitation SB 1383 Dairy Pilot Projects

N.T.S.



113 N. CHURCH ST,  
SUITE 521  
VISALIA, CA 93291  
(559) 563-0181



PROJECT:  
LAKESIDE ENERGY

DAIRY  
DIGESTER

CLIENT:  
MIKE MONTEIRO  
8606 KENT AVE,  
HANFORD, CA 93230

LINER  
DETAILS

REVISION LOG:

PLOT DATE: 01/08/18


JOB NO.: 17003

SCALE: AS SHOWN


SHEET NO.: L2

100 0185






**A BOOT SKIRT** N.T.S.




**B BOOTLESS PIPE PENETRATION** N.T.S.



**C VENT ORIFICE (ISOMETRIC VIEW)** N.T.S.



113 N. CHURCH ST,  
SUITE 521  
VISALIA, CA 93291  
(559) 563-0181



PROJECT:

**LAKESIDE ENERGY**

**DAIRY  
DIGESTER**

CLIENT:  
MIKE MONTEIRO  
8606 KENT AVE,  
HANFORD, CA 93230

LINER  
DETAILS

REVISION LOG:

PLOT DATE: 01/08/18

JOB NO.: 17003

SCALE: AS SHOWN

SHEET NO.: L3



# LONE OAK #1

# DAIRY DIGESTER

## BENCHMARK

THE TOPOGRAPHIC SURVEY WAS PERFORMED UTILIZING GLOBAL POSITIONING SYSTEM OBSERVATIONS. DISTANCES AND NUMBERS SHOWN ARE TO BE CONSIDERED GROUND VALUES. BENCHMARK AND CONTROL SHOWN ON CONTROL PLAN SHEET. THE BENCHMARK AND VERTICAL ELEVATIONS WERE DERIVED FROM THE NGS ONLINE POSITIONING SERVICE (OPUS), AND IS SHOWN ON THE NAVD 88 DATUM UTILITIZING THE GEOID 09 AS THE VERTICAL MODEL.

## PRESERVATION OF MONUMENTS

PURSUANT TO SECTIONS 8771(B) AND 8771(C) OF THE GOVERNMENT CODE, ANY MONUMENTS THAT CONTROL THE LOCATION OF BOUNDARIED, OR OTHERWISE PROVIDE HORIZONTAL OR VERTICAL SURVEY CONTROL WITHIN THE CONSTRUCTION AREA, SHALL BE LOCATED AND REFERENCED PRIOR TO CONSTRUCTION, AND A CORNER RECORD OR RECORD OF SURVEY OF THE REFERENCES SHALL BE FILED WITH THE COUNTY SURVEYOR.


PERMANENT MONUMENTATION SHALL BE SET TO PERPETUATE THE LOCATION OF ANY MONUMENT WHICH COULD BE DAMAGED OR DESTROYED, AND A CORNER RECORD OR RECORD OF SURVEY SHALL BE FILED WITH THE COUNTY SURVEYOR PRIOR TO THE RECORDING OF A CERTIFICATE OF COMPLETION FOR THE PROJECT.

## DUST CONTROL NOTES

CONTRACTOR IS REQUIRED TO COMPLY WITH GOOD HOUSE KEEPING PRACTICES

## STORMWATER (SWPPP) NOTES

CONTRACTOR IS REQUIRED TO COMPLY WITH GOOD HOUSE KEEPING PRACTICES



VICINITY MAP

SCALE 1" : 2 MI

## SHEET INDEX

### GENERAL NOTES

- A.1 COVER SHEET
- A.2 GENERAL NOTES
- A.3 SITE PLAN - DAIRY
- A.4 SITE PLAN - DIGESTER

### CIVIL DRAWINGS

- C.1 GRADING PLAN
- C.2 CROSS SECTIONS
- C.3 GRADING DETAILS

### DIGESTER DRAWINGS

- D.1 COVER SYSTEM
- D.2 SLURRY SYSTEM
- D.3 MIXERS
- D.4 DETAILS


### LINER DRAWINGS

- L.1 LINER - DETAILS
- L.2 LINER - DETAILS
- L.3 LINER - DETAILS

## SHEET REFERENCE

### SECTIONS:

SECTION NAME  
SHEET NUMBER



### DETAILS:

DETAIL NAME  
SHEET NUMBER



B  
C.3

## CONTACT INFO

ENGINEER:  
CRAIG HARTMAN, RCE 73837  
HARTMAN ENGINEERING, INC.  
3121 W. CERES CT.  
VISALIA, CA 93291  
(559) 563-0181

DAIRY CONTACT:  
BERNARD TE VELDE  
13866 4TH AVE  
HANFORD, CA 93230



113 N. CHURCH ST,  
SUITE 521  
VISALIA, CA 93291  
(559) 563-0181



### PROJECT:

LONE OAK#1

DAIRY  
DIGESTER

### CLIENT:

BERNARD TE VELDE  
13866 4TH AVE  
HANFORD, CA 93230

REVISION LOG:

PLOT DATE: 01/08/18

JOB NO.: 17003

SCALE: AS SHOWN

SHEET NO.: A.1



SPECIFICATIONS FOR ENGINEERED FILL MATERIAL OF ABOVE GRADE EMBANKMENTS OR AS REQUIRED

TEST PARAMETER	TEST METHOD	FREQUENCY	ACCEPTANCE CRITERIA
Compaction Curves	ASTM D1557 (Modified Proctor)	Change in material	N/A
Grain Size Distribution	ASTM D422 (Sieve)	Change in material	At least 30% passing No. 200 U.S. Standard Sieve. Per Specifications (1)
Soil Classification	ASTM D2487 (USCS)	Change in material	Suitable for compaction (2,3)
Maximum Particle Size	ASTM D422 (Sieve)	Change in material	½ inch, ¼ top 6 inches
Maximum Water soluble Sulfate (SO <sup>4-</sup> ) in Soil (Concrete Slab locations)	ASTM C1580	Change in material	0.2% by weight
Site Preparation Specifications:			
1. Clearing: Prior to earthwork operations, the area to be developed should be stripped of vegetation, organic topsoil, and cleared of cow waste and miscellaneous debris from the proposed construction areas. Deeper clearing may be required in localized areas. The actual depth of clearing should be reviewed by a licensed Geotechnical Engineer at the time of construction. The limits of stripping and clearing should be at least five feet bey ond the limits of construction.			
2. Compaction: The scarified subgrade and subsequent fill placed at the site should be moisture conditioned to near optimum moisture content, and compacted to at least and 90 percent for 2:1 side slope pond of maximum dry density as determined by ASTM test method D1557.			
3. Material for fill: Fill should consist of select material. Native soil, free from organic, vegetation, and rocks or cobbles larger than three inches, may be used as fill at the site. Import material must be reviewed by licensed Geotechnical Engineer prior to transport to the site.			
4. Fill placement: Fill material should be moisture-conditioned to +/- 2% of the optimum moisture content prior to compaction. Fill material with excessiv e moisture should be allowed to dry prior to compaction or be mixed with dry soil to bring the fill to a workable moisture content. Fill should be placed in level lifts not exceeding a loose, uncompacted thickness of eight inches, and compacted as engineered fill.			
Sub-grade requirements for fill only :			
-Over Excavate for minimum 1 ft. to meet Engineered Fill Borrow Material Guidelines and Pond Liner Sub-grade requirements			
-Well mixed soil			
-6 in max lifts			
-Upper 6 inches is of fine-finished soil particles no greater than ¼ in.+			
Notes:			
Field tests shall not be required, but fill borrow material specifications must meet the acceptance criteria outlined in Table 1.			
Refer to Geotechnical Report			

FILL TEST SPECIFICATIONS FOR SUB-GRADE

TEST PARAMETER	TEST METHOD (1)	FREQUENCY	ACCEPTANCE CRITERIA
Uncompacted Lift Thickness	Visual Observation	Continuous	8-in.(2)
Construction Oversight	Visual Observation	Continuous	Maximum particle size 1/2 inch.
In-Place Moisture Alternative Method	ASTM D2216 (Oven Dry)	1 per every 10 Nuclear tests	+/-2% of Optimum Moisture Content per ASTM D1557
In-Place Moisture Rapid Field Methods (3,4,5)	ASTM D6938 (Nuclear Method)	3 per acre per lift, min. 2 per day	+/-2% of Optimum Moisture Content per ASTM D1557
In-Place Density Alternat e Method	ASTM D2937(Drive Cylinder)	1 per every 10 Nuclear tests	90% of Maximum Dry Density per ASTM D1557
In-Place Density Rapid Field Methods (1)	ASTM D6938 (Nuclear Method)	3 per acre per lift, min. 2 per day	90% of Maximum Dry Density per ASTM D1557
Subgrade Thickness	Surveying Measurement	At 50-foot centers	Minimum 1 ft.(5)
Clod Size	Visual Observation	Continuous	Per Specification

Notes:

See earthwork section for anchor trench, excavation, backfill, and compaction requirements.

(1) ASTM Test Method, unless otherwise noted. Results of all tests performed to be reported as per method reporting criteria.

(2) The sub-grade shall be scarified to a depth of 1 ft. lower than finished grade, compacted, and tested in accordance with the requirements of this table.

(3) Must be verified by ASTM D2216 (Oven) overnight method once every day or once per change in material

(4) Must be verified by ASTM D2937 (Dry Cylinder) twice per day or per change in material

(5) Calibration Procedure: ASTM D7013-04: Standard Guide for Nuclear Surface Moisture and Density Gauge Calibration Facility Set-up

POND SPECIFICATIONS FOR SUBGRADES CUT BELOW GROUND (For Slopes 2:1 or shallower)

**Side Slopes:** The certified Civil Engineer/CQA Chief Officer shall walk final side slopes after cut by heavy equipment and confirm no SW or SP soils and no loose soils. All SW, SP, or soils that are not amenable to a firm and unyielding subgrade shall be removed and replaced down to a minimum 3 ft. below sloped surface. Any soils removed and replaced shall meet the Engineered Fill requirements in Table 1.

**Pond Bottom:** 1. An as-built survey of the pond bottom shall take place after subgrade construction to insure minimum slopes are achieved. Pond Bottom shall be tested per criteria below. Any soils not meeting the requirements below (i.e. that is not firm and unyielding) shall be removed and replaced down to a minimum 2 ft. Any soils removed and replaced shall meet the Engineered Fill requirements in Table 1. The Civil Engineer may make determination of soils meeting requirements or not based upon visual inspection which shall be included in the Subgrade Certification Report and signed and sealed by a Civil Engineer and CQA Officer.

TEST PARAMETER	TEST METHOD (1)	FREQUENCY	ACCEPTANCE CRITERIA
In-Place Density Rapid Field Methods (1)	ASTM D6938 (Nuclear)	3 per acre	90% of Maximum Dry Density per ASTM D1557
In-Place Moisture Rapid Field Methods (3,4,5)	ASTM D6938 (Nuclear Methods)	3 per acre per lift, min. 2 per day	+/-2% of Optimum Moisture Content per ASTM D1557
Construction Oversight	Visual Observation	Continuous	Maximum particle size 1/2 inch.
Subgrade Slope	Surveying Measurement	200 ft. maximum grid	Min 1%

60 MIL HDPE GEOMEMBRANE CONSTRUCTION QUALITY ASSURANCE (CQA)

TEST PARAMETER	TEST METHOD	FREQUENCY	ACCEPTANCE CRITERIA
Thickness (min. ave.) -Lowest individual for 8 out of 10 values -Lowest individual for any of the 10 values	ASTM D5994	1 per lot or 1 per 70,000 ft <sup>2</sup> , whichever is greater	Nom. (-5%)  -10%  -15%
Tensile Properties -yield strength -break strength -strain at yeild -break strength	ASTM D6693 Type IV	1 per lot or 1 per 70,000 ft <sup>2</sup> , whichever is greater	≥126 lb./in. ≥90 lb./in. ≥12% ≥100%
Puncture Resistance	ASTM D4833	1 per lot or 1 per 70,000 ft <sup>2</sup> , whichever is greater	108 lb. (min.)
Tear Resistance	ASTM D1004, Die C	1 per lot or 1 per 70,000 ft <sup>2</sup> , whichever is greater	42 lb. (min.)
Interface Shear -60-mil HDPE/subgrade soil -Drainage geocomposite	ASTM D5321 ASTM D6243	2 tests or 1 per 200,000 ft <sup>2</sup> , whichever is greater	
Seam Shear	ASTM D6392	1 test per 500 lineal feet or per GRI GM-14 and 20.	95% of min. yield strength
Seam Peel -Extrusion -Fusion	ASTM D6392	1 test per 500 lineal feet or per GRI GM-14 and 20.	72% yield & ffb (1)
Non-destructive Seam Test	ASTM D5820 (Pressure Test)	Continuous	35 psi for 5 min.
	ASTM D5641 (Vacuum Box)		5 psi for 15 sec.
	ASTM D5641 (Spark Test)		No Spark
Electric Leak Location	ASTM D7002 (Water Puddle)	Once on constructed liner	Max 1 mm. diameter hole sensitivity
	ASTM D6747 (Selection Process)		
	ASTM D7007 (Water /Earth)		Max 6 mm. diameter hole sensitivity
	ASTM D7240 (Spark Test 2011)		
Notes: ffb: Film Tear Bond			

NOTES:

THE APPROVED WORK PLAN WHICH INCLUDES THE CONSTRUCTION QUALITY ASSURANCE PLAN, OPERATION, MAINTENANCE AND MONITORING PLAN, CONSTRUCTION DRAWINGS, AND SOILS REPORT TOGETHER AS A PACKAGE ARE THE COMPLETE SPECIFICATIONS REQUIRED FOR CONSTRUCTION OF THE POND AND LINER SYSTEM.



113 N. CHURCH ST,  
SUITE 521  
VISALIA, CA 93291  
(559) 563-0181



PROJECT:

LONE OAK #1

DAIRY  
DIGESTER

CLIENT:  
BERNARD TE VELDE  
13866 4TH AVE  
HANFORD, CA 93230

GENERAL NOTES  
CONSTRUCTION

REVISION LOG:


PLOT DATE: 01/08/18

JOB NO.: 17003

SCALE: AS SHOWN

SHEET NO.: A.2  
188 0188





113 N. CHURCH ST,  
SUITE 521  
VISALIA, CA 93291  
(559) 563-0181



PROJECT:  
**LONE OAK#1**

**DAIRY  
DIGESTER**

CLIENT:  
BERNARD TE VELDE  
13866 4TH AVE  
HANFORD, CA 93230


S I T E P L A N

DIGESTER

REVISION LOG:

PLOT DATE:	01/08/18
JOB NO.:	17003
SCALE:	AS SHOWN
SHEET NO.:	A.3





113 N. CHURCH ST,  
SUITE 521  
VISALIA, CA 93291  
(559) 563-0181



PROJECT:

LONE OAK#1

DAIRY  
DIGESTER

CLIENT:  
BERNARD TE VELDE  
13866 4TH AVE  
HANFORD, CA 93230

S I T E P L A N

DAIRY

REVISION LOG:

PLOT DATE: 01/08/18

JOB NO.: 17003

SCALE: AS SHOWN

SHEET NO.: A.4





113 N. CHURCH ST,  
SUITE 521  
VISALIA, CA 93291  
(559) 563-0181



PROJECT:

LONE OAK#1

DAIRY  
DIGESTER

CLIENT:  
BERNARD TE VELDE  
13866 4TH AVE  
HANFORD, CA 93230

GRADING PLAN

DIGESTER

REVISION LOG:


PLOT DATE: 01/08/18

JOB NO.: 17003

SCALE: AS SHOWN


SHEET NO.: C.1

10191






GRADING NOTES:

- 1.CONTRACTOR SHALL INFORM ENGINEER OF ANY DISCREPANCIES OR ERRORS IN PLANS PRIOR TO CONSTRUCTION.
2. CONTRACTOR SHALL MEET SPECIFICATIONS OF TABLE 2 WITHIN THE APPROVED CONSTRUCTION QUALITY CONTROL PLAN.
3. CONTRACTOR SHALL SMOOTH DRUM ROLL FINAL SURFACE AND REMOVE ANY ROCK OR MATERIAL GREATER THAN 1/2 INCH.







113 N. CHURCH ST,  
SUITE 521  
VISALIA, CA 93291  
(559) 563-0181



PROJECT:

**LONE OAK#1**

**DAIRY  
DIGESTER**

CLIENT:  
BERNARD TE VELDE  
13866 4TH AVE  
HANFORD, CA 93230

GRADING SECTIONS

DIGESTER

REVISION LOG:


PLOT DATE: 01/08/18

JOB NO.: 17003

SCALE: AS SHOWN

SHEET NO.: C.2






**A ANCHOR TRENCH / SUMP PROFILE VIEW**


N.T.S.

DIMENSION TABLE (FT.)	
LETTER	POND
L	1.7'
M.1	2.7'
U	20'
R	1.5'
S	3'
T	3'
X	30'
Y	30'
Z	5.5'



**B SUMP PLAN VIEW**

N.T.S.



**C SIDE SLOPE TRENCH**

N.T.S.



113 N. CHURCH ST,  
SUITE 521  
VISALIA, CA 93291  
(559) 563-0181



PROJECT:

**LONE OAK#1**

**DAIRY  
DIGESTER**

CLIENT:  
BERNARD TE VELDE  
13866 4TH AVE  
HANFORD, CA 93230

GRADING DETAIL  
DIGESTER

REVISION LOG:

PLOT DATE: 01/08/18




JOB NO.: 17003

SCALE: AS SHOWN

SHEET NO.: C.3

10193






- NOTES:
1. GAS VENTS AROUND PERIPHERY OF LAGOON @ MAX. 40' O.C.
  2. STRAP NOT WELDED TO BIO-GAS HEADER PIPE.
  3. WRAP 60 MIL PRIMARY LINER OVER CONCRETE & EXTRUSION WELD.











**MIXER - HATCH**

N.T.S.




**AIR INJECTION & MIXER HATCH**

N.T.S.




**MIXER - PLAN VIEW**

N.T.S.




**MIXER - ISOMETRIC W/FLOAT IN PLACE**

N.T.S.




**MIXER - ISOMETRIC**

N.T.S.




**MIXER - SIDE VIEW**

N.T.S.



**MIXER - FRONT VIEW**

N.T.S.



113 N. CHURCH ST,  
SUITE 521  
VISALIA, CA 93291  
(559) 563-0181



PROJECT:

**LONE OAK#1**

**DAIRY  
DIGESTER**

CLIENT:  
BERNARD TE VELDE  
13866 4TH AVE  
HANFORD, CA 93230

MIXER  
DETAILS

REVISION LOG:

PLOT DATE: 01/08/18


JOB NO.: 17003

SCALE: AS SHOWN

SHEET NO.: D.3




PS 124 0196





## MOISTURE TRAP DETAIL

N.T.S.



## BIO-GAS VALVE

N.T.S.

## BALL VALVE JUNCTION


N.T.S.

## BOLLARD DETAIL

N.T.S.



113 N. CHURCH ST,  
SUITE 521  
VISALIA, CA 93291  
(559) 563-0181



PROJECT:

**LONE OAK#1**

**DAIRY  
DIGESTER**

CLIENT:  
BERNARD TE VELDE  
13866 4TH AVE  
HANFORD, CA 93230

DETAILS

REVISION LOG:

PLOT DATE: 01/08/18

JOB NO.: 17003

SCALE: AS SHOWN

SHEET NO.: D.4



GENERAL NOTES  
LINER  
DETAILS

REVISION LOG:


PLOT DATE: 01/08/18

JOB NO.: 17003


SCALE: AS SHOWN

SHEET NO.: L.1

0198




**FRONT VIEW**




**SIDE VIEW**

**LCRS, LYSIMETER AND DRAINAGE SUMP PROFILE**




**DIGESTER ANCHOR TRENCH DETAIL**

NOTES: 1. CONTRACTOR TO USE ANCHOR SYSTEM OR PROVIDE DETAILS AND DESIGN FOR ALTERNATIVE TO BE APPROVED BY ENGINEER. N.T.S.



**HDPE CROSS SECTION**

N.T.S.




**TYPICAL PERFORATION DETAIL**

N.T.S.





OPTIONAL TIER 1 DOUBLE LINER-LAYERING SYSTEM WITH DRAIN LINER VERIFY WITH OWNER


SMOOTH/STUDDED/ 60-NET-60 LINER LAYERS					
DESCRIPTION	LOCATION	MATERIAL	THICKNESS (MIN)	TOP FINISH	BOTTOM FINISH
PRIMARY LINER	TOP	HDPE	60 MIL	SMOOTH	SMOOTH CONDUCTIVE
DRAINAGE NET	MIDDLE	HDPE	200 MIL	N/A	N/A
SECONDARY LINER	BOTTOM	HDPE	60 MIL	SMOOTH	SMOOTH



**A** DOUBLE LAYER 60-NET-60 DOUBLE LAYER WITH DRAIN LINER N.T.S.



**B** HDPE LINER-SMOOTH WELDS N.T.S.




DRAIN LINER SMOOTH END WELD PATCH

**C** 3'X3' DRAIN PATCH WELD N.T.S.

1.1 - Engineer/Designer Site Plan and Design - Lone Oak Farms #1


1.1.3 - Engineered Project Site Plan and Design



**D** AGRU DRAIN LINER END/END WELD NOTE: AGRU DRAIN LINER DOES NOT HAVE STUDS ALONG THE EDGE SO EDGE/EDGE SEAMS DO NOT REQUIRE DRINGING OR CAP. N.T.S.

2' WIDE STRIP OF 200 MIL GEONET. TACK WELD AT 8'

**C** P.3 3'X3' DRAIN PATCH



NOTE: CQA OFFICER IS RESPONSIBLE TO ADD PATCHES AS NEEDED FOR FLOW

**E** AGRU DRAIN LINER CROSS SEAM NET PLAN VIEW NOTE: TYPICAL OF ALL DRAIN LINERS

1.2 - Lakeside Pipeline LLC - Application - 2018 Solicitation SB 1383 Dairy Pilot Projects

THIS IS AN ORIGINAL UNPUBLISHED WORK AND MAY NOT BE DUPLICATED, PUBLISHED OR OTHERWISE USED WITHOUT THE WRITTEN CONSENT OF HARTMAN ENGINEERING INC. ©



113 N. CHURCH ST,  
SUITE 521  
VISALIA, CA 93291  
(559) 563-0181



PROJECT:  
LONE OAK#1

DAIRY  
DIGESTER

CLIENT:  
BERNARD TE VELDE  
13866 4TH AVE  
HANFORD, CA 93230


LINER DETAILS	REVISION LOG:

PLOT DATE:	01/08/18
JOB NO.:	17003
SCALE:	AS SHOWN
SHEET NO.:	L2


1.2 - Lakeside Pipeline LLC - Application - 2018 Solicitation SB 1383 Dairy Pilot Projects

THIS IS AN ORIGINAL UNPUBLISHED WORK AND MAY NOT BE DUPLICATED, PUBLISHED OR OTHERWISE USED WITHOUT THE WRITTEN CONSENT OF HARTMAN ENGINEERING INC. ©






**A** BOOT SKIRT N.T.S.



## BOOTLESS PIPE PENETRATION LINER FASTENING



VENT ORIFICE (ISOMETRIC VIEW)



# POPLAR LANE DAIRY DIGESTER

## BENCHMARK

THE TOPOGRAPHIC SURVEY WAS PERFORMED UTILIZING GLOBAL POSITIONING SYSTEM OBSERVATIONS. DISTANCES AND NUMBERS SHOWN ARE TO BE CONSIDERED GROUND VALUES. BENCHMARK AND CONTROL SHOWN ON CONTROL PLAN SHEET. THE BENCHMARK AND VERTICAL ELEVATIONS WERE DERIVED FROM THE NGS ONLINE POSITIONING SERVICE (OPUS), AND IS SHOWN ON THE NAVD 88 DATUM UTILITIZING THE GEOID 09 AS THE VERTICAL MODEL.

## PRESERVATION OF MONUMENTS

PURSUANT TO SECTIONS 8771(B) AND 8771(C) OF THE GOVERNMENT CODE, ANY MONUMENTS THAT CONTROL THE LOCATION OF BOUNDARIED, OR OTHERWISE PROVIDE HORIZONTAL OR VERTICAL SURVEY CONTROL WITHIN THE CONSTRUCTION AREA, SHALL BE LOCATED AND REFERENCED PRIOR TO CONSTRUCTION, AND A CORNER RECORD OR RECORD OF SURVEY OF THE REFERENCES SHALL BE FILED WITH THE COUNTY SURVEYOR.

PERMANENT MONUMENTATION SHALL BE SET TO PERPETUATE THE LOCATION OF ANY MONUMENT WHICH COULD BE DAMAGED OR DESTROYED, AND A CORNER RECORD OR RECORD OF SURVEY SHALL BE FILED WITH THE COUNTY SURVEYOR PRIOR TO THE RECORDING OF A CERTIFICATE OF COMPLETION FOR THE PROJECT.

## DUST CONTROL NOTES

CONTRACTOR IS REQUIRED TO COMPLY WITH GOOD HOUSE KEEPING PRACTICES

## STORMWATER (SWPPP) NOTES

CONTRACTOR IS REQUIRED TO COMPLY WITH GOOD HOUSE KEEPING PRACTICES



VICINITY MAP

SCALE 1" : 2 MI

## SHEET INDEX

### GENERAL NOTES

- A.1 COVER SHEET
- A.2 GENERAL NOTES
- A.3 SITE PLAN - DAIRY
- A.4 SITE PLAN - DIGESTER

### CIVIL DRAWINGS

- C.1 GRADING PLAN
- C.2 CROSS SECTIONS
- C.3 GRADING DETAILS

### DIGESTER DRAWINGS

- D.1 COVER SYSTEM
- D.2 SLURRY SYSTEM
- D.3 MIXERS
- D.4 DETAILS


### LINER DRAWINGS

- L.1 LINER - DETAILS
- L.2 LINER - DETAILS
- L.3 LINER - DETAILS

## SHEET REFERENCE


### SECTIONS:

SECTION NAME  
SHEET NUMBER



### DETAILS:

DETAIL NAME  
SHEET NUMBER



## CONTACT INFO

ENGINEER:  
CRAIG HARTMAN, RCE 73837  
HARTMAN ENGINEERING, INC.  
3121 W. CERES CT.  
VISALIA, CA 93291  
(559) 563-0181

DAIRY CONTACT:  
BERNARD TE VELDE SR.  
5387 KENT AVE  
HANFORD, CA 93230



113 N. CHURCH ST,  
SUITE 521  
VISALIA, CA 93291  
(559) 563-0181



### PROJECT:

POPLAR LANE

DAIRY  
DIGESTER

### CLIENT:

BERNARD TE VELDE SR  
5387 KENT AVE  
HANFORD, CA 93280

REVISION LOG:

PLOT DATE: 01/08/18

JOB NO.: 17003

SCALE: AS SHOWN

SHEET NO.: A.1



SPECIFICATIONS FOR ENGINEERED FILL MATERIAL OF ABOVE GRADE EMBANKMENTS OR AS REQUIRED

TEST PARAMETER	TEST METHOD	FREQUENCY	ACCEPTANCE CRITERIA
Compaction Curves	ASTM D1557 (Modified Proctor)	Change in material	N/A
Grain Size Distribution	ASTM D422 (Sieve)	Change in material	At least 30% passing No. 200 U.S. Standard Sieve. Per Specifications (1)
Soil Classification	ASTM D2487 (USCS)	Change in material	Suitable for compaction (2,3)
Maximum Particle Size	ASTM D422 (Sieve)	Change in material	½ inch, ¼ top 6 inches
Maximum Water soluble Sulfate (SO <sup>4-</sup> ) in Soil (Concrete Slab locations)	ASTM C1580	Change in material	0.2% by weight
Site Preparation Specifications:			
1. Clearing: Prior to earthwork operations, the area to be developed should be stripped of vegetation, organic topsoil, and cleared of cow waste and miscellaneous debris from the proposed construction areas. Deeper clearing may be required in localized areas. The actual depth of clearing should be reviewed by a licensed Geotechnical Engineer at the time of construction. The limits of stripping and clearing should be at least five feet bey ond the limits of construction.			
2. Compaction: The scarified subgrade and subsequent fill placed at the site should be moisture conditioned to near optimum moisture content, and compacted to at least and 90 percent for 2:1 side slope pond of maximum dry density as determined by ASTM test method D1557.			
3. Material for fill: Fill should consist of select material. Native soil, free from organic, vegetation, and rocks or cobbles larger than three inches, may be used as fill at the site. Import material must be reviewed by licensed Geotechnical Engineer prior to transport to the site.			
4. Fill placement: Fill material should be moisture-conditioned to +/- 2% of the optimum moisture content prior to compaction. Fill material with excessiv e moisture should be allowed to dry prior to compaction or be mixed with dry soil to bring the fill to a workable moisture content. Fill should be placed in level lifts not exceeding a loose, uncompacted thickness of eight inches, and compacted as engineered fill.			
Sub-grade requirements for fill only :			
-Over Excavate for minimum 1 ft. to meet Engineered Fill Borrow Material Guidelines and Pond Liner Sub-grade requirements			
-Well mixed soil			
-6 in max lifts			
-Upper 6 inches is of fine-finished soil particles no greater than ¼ in.+			
Notes:			
Field tests shall not be required, but fill borrow material specifications must meet the acceptance criteria outlined in Table 1.			
Refer to Geotechnical Report			

FILL TEST SPECIFICATIONS FOR SUB-GRADE

TEST PARAMETER	TEST METHOD (1)	FREQUENCY	ACCEPTANCE CRITERIA
Uncompacted Lift Thickness	Visual Observation	Continuous	8-in.(2)
Construction Oversight	Visual Observation	Continuous	Maximum particle size 1/2 inch.
In-Place Moisture Alternative Method	ASTM D2216 (Oven Dry)	1 per every 10 Nuclear tests	+/-2% of Optimum Moisture Content per ASTM D1557
In-Place Moisture Rapid Field Methods (3,4,5)	ASTM D6938 (Nuclear Method)	3 per acre per lift, min. 2 per day	+/-2% of Optimum Moisture Content per ASTM D1557
In-Place Density Alternat e Method	ASTM D2937(Drive Cylinder)	1 per every 10 Nuclear tests	90% of Maximum Dry Density per ASTM D1557
In-Place Density Rapid Field Methods (1)	ASTM D6938 (Nuclear Method)	3 per acre per lift, min. 2 per day	90% of Maximum Dry Density per ASTM D1557
Subgrade Thickness	Surveying Measurement	At 50-foot centers	Minimum 1 ft.(5)
Clod Size	Visual Observation	Continuous	Per Specification

Notes:			
See earthwork section for anchor trench, excavation, backfill, and compaction requirements.			
(1) ASTM Test Method, unless otherwise noted. Results of all tests performed to be reported as per method reporting criteria.			
(2) The sub-grade shall be scarified to a depth of 1 ft. lower than finished grade, compacted, and tested in accordance with the requirements of this table.			
(3) Must be verified by ASTM D2216 (Oven) overnight method once every day or once per change in material			
(4) Must be verified by ASTM D2937 (Dry Cylinder) twice per day or per change in material			
(5) Calibration Procedure: ASTM D7013-04: Standard Guide for Nuclear Surface Moisture and Density Gauge Calibration Facility Set-up			

POND SPECIFICATIONS FOR SUBGRADES CUT BELOW GROUND (For Slopes 2:1 or shallower)

**Side Slopes:** The certified Civil Engineer/CQA Chief Officer shall walk final side slopes after cut by heavy equipment and confirm no SW or SP soils and no loose soils. All SW, SP, or soils that are not amenable to a firm and unyielding subgrade shall be removed and replaced down to a minimum 3 ft. below sloped surface. Any soils removed and replaced shall meet the Engineered Fill requirements in Table 1.

**Pond Bottom:** 1. An as-built survey of the pond bottom shall take place after subgrade construction to insure minimum slopes are achieved. Pond Bottom shall be tested per criteria below. Any soils not meeting the requirements below (i.e. that is not firm and unyielding) shall be removed and replaced down to a minimum 2 ft. Any soils removed and replaced shall meet the Engineered Fill requirements in Table 1. The Civil Engineer may make determination of soils meeting requirements or not based upon visual inspection which shall be included in the Subgrade Certification Report and signed and sealed by a Civil Engineer and CQA Officer.

TEST PARAMETER	TEST METHOD (1)	FREQUENCY	ACCEPTANCE CRITERIA
In-Place Density Rapid Field Methods (1)	ASTM D6938 (Nuclear)	3 per acre	90% of Maximum Dry Density per ASTM D1557
In-Place Moisture Rapid Field Methods (3,4,5)	ASTM D6938 (Nuclear Methods)	3 per acre per lift, min. 2 per day	+/-2% of Optimum Moisture Content per ASTM D1557
Construction Oversight	Visual Observation	Continuous	Maximum particle size 1/2 inch.
Subgrade Slope	Surveying Measurement	200 ft. maximum grid	Min 1%

60 MIL HDPE GEOMEMBRANE CONSTRUCTION QUALITY ASSURANCE (CQA)

TEST PARAMETER	TEST METHOD	FREQUENCY	ACCEPTANCE CRITERIA
Thickness (min. ave.) -Lowest individual for 8 out of 10 values -Lowest individual for any of the 10 values	ASTM D5994	1 per lot or 1 per 70,000 ft <sup>2</sup> , whichever is greater	Nom. (-5%)  -10%  -15%
Tensile Properties -yield strength -break strength -strain at yeild -break strength	ASTM D6693 Type IV	1 per lot or 1 per 70,000 ft <sup>2</sup> , whichever is greater	≥126 lb./in. ≥90 lb./in. ≥12% ≥100%
Puncture Resistance	ASTM D4833	1 per lot or 1 per 70,000 ft <sup>2</sup> , whichever is greater	108 lb. (min.)
Tear Resistance	ASTM D1004, Die C	1 per lot or 1 per 70,000 ft <sup>2</sup> , whichever is greater	42 lb. (min.)
Interface Shear -60-mil HDPE/subgrade soil -Drainage geocomposite	ASTM D5321 ASTM D6243	2 tests or 1 per 200,000 ft <sup>2</sup> , whichever is greater	
Seam Shear	ASTM D6392	1 test per 500 lineal feet or per GRI GM-14 and 20.	95% of min. yield strength
Seam Peel -Extrusion -Fusion	ASTM D6392	1 test per 500 lineal feet or per GRI GM-14 and 20.	72% yield & ffb (1)
Non-destructive Seam Test	ASTM D5820 (Pressure Test)	Continuous	35 psi for 5 min.
	ASTM D5641 (Vacuum Box)		5 psi for 15 sec.
	ASTM D5641 (Spark Test)		No Spark
Electric Leak Location	ASTM D7002 (Water Puddle)	Once on constructed liner	Max 1 mm. diameter hole sensitivity
	ASTM D6747 (Selection Process)		
	ASTM D7007 (Water /Earth)		Max 6 mm. diameter hole sensitivity
	ASTM D7240 (Spark Test 2011)		
Notes: ffb: Film Tear Bond			

NOTES:

THE APPROVED WORK PLAN WHICH INCLUDES THE CONSTRUCTION QUALITY ASSURANCE PLAN, OPERATION, MAINTENANCE AND MONITORING PLAN, CONSTRUCTION DRAWINGS, AND SOILS REPORT TOGETHER AS A PACKAGE ARE THE COMPLETE SPECIFICATIONS REQUIRED FOR CONSTRUCTION OF THE POND AND LINER SYSTEM.



113 N. CHURCH ST,  
SUITE 521  
VISALIA, CA 93291  
(559) 563-0181



PROJECT:

POPLAR LANE

DAIRY  
DIGESTER

CLIENT:  
BERNARD TE VELDE SR  
5387 KENT AVE  
HANFORD, CA 93280

GENERAL NOTES CONSTRUCTION	REVISION LOG:				

PLOT DATE: 01/08/18

JOB NO.: 17003

SCALE: AS SHOWN

SHEET NO.: A.2





113 N. CHURCH ST,  
SUITE 521  
VISALIA, CA 93291  
(559) 563-0181



PROJECT:  
**POPLAR LANE**

**DAIRY  
DIGESTER**

CLIENT:  
BERNARD TE VELDE SR  
5387 KENT AVE  
HANFORD, CA 93280

S I T E   P L A N  
D I G E S T E R

REVISION LOG:

PLOT DATE: 01/08/18

JOB NO.: 17003

SCALE: AS SHOWN

SHEET NO.: A.3





113 N. CHURCH ST,  
SUITE 521  
VISALIA, CA 93291  
(559) 563-0181



PROJECT:  
**POPLAR LANE**

**DAIRY  
DIGESTER**

CLIENT:  
BERNARD TE VELDE SR  
5387 KENT AVE  
HANFORD, CA 93280

S I T E P L A N

DAIRY

REVISION LOG:

PLOT DATE:	01/08/18
JOB NO.:	17003
SCALE:	AS SHOWN
SHEET NO.:	A.4







113 N. CHURCH ST,  
SUITE 521  
VISALIA, CA 93291  
(559) 563-0181




PROJECT:  
**POPLAR LANE**  
  
**DAIRY  
DIGESTER**  
  
CLIENT:  
BERNARD TE VELDE SR  
5387 KENT AVE  
HANFORD, CA 93280


GRADING PLAN	DIGESTER	REVISION LOG:	

PLOT DATE:	01/08/18
JOB NO.:	17003
SCALE:	AS SHOWN
SHEET NO.:	C.1



0205



- GRADING NOTES:
1. CONTRACTOR SHALL INFORM ENGINEER OF ANY DISCREPANCIES OR ERRORS IN PLANS PRIOR TO CONSTRUCTION.
  2. CONTRACTOR SHALL MEET SPECIFICATIONS OF TABLE 2 WITHIN THE APPROVED CONSTRUCTION QUALITY CONTROL PLAN.
  3. CONTRACTOR SHALL SMOOTH DRUM ROLL FINAL SURFACE AND REMOVE ANY ROCK OR MATERIAL GREATER THAN 1/2 INCH.







113 N. CHURCH ST,  
SUITE 521  
VISALIA, CA 93291  
(559) 563-0181



PROJECT:  
**POPLAR LANE**


**DAIRY  
DIGESTER**

CLIENT:  
BERNARD TE VELDE SR  
5387 KENT AVE  
HANFORD, CA 93280

GRADING SECTIONS	DIGESTER	REVISION LOG:	

PLOT DATE:	01/08/18
JOB NO.:	17003
SCALE:	AS SHOWN
SHEET NO.:	C.2






**A** ANCHOR TRENCH / SUMP PROFILE VIEW


N.T.S.

DIMENSION TABLE (FT.)	
LETTER	POND
L	1.7'
M.1	2.7'
U	20'
R	1.5'
S	3'
T	3'
X	30'
Y	30'
Z	5.5'



**B** SUMP PLAN VIEW

N.T.S.



**C** SIDE SLOPE TRENCH

N.T.S.



113 N. CHURCH ST,  
SUITE 521  
VISALIA, CA 93291  
(559) 563-0181



PROJECT:  
POPLAR LANE

DAIRY  
DIGESTER


CLIENT:  
BERNARD TE VELDE SR  
5387 KENT AVE  
HANFORD, CA 93280

GRADING DETAIL  
DIGESTER

REVISION LOG:

PLOT DATE: 01/08/18  
JOB NO.: 17003  
SCALE: AS SHOWN  
SHEET NO.: C.3






**A BALLAST TUBE DETAIL**


N.T.S.

DESCRIPTION	LOCATION	MATERIAL	THICKNESS (MIN)	TOP FINISH	BOTTOM FINISH
COVER	TOP	HDPE	80 MIL	SMOOTH	SMOOTH



**C HDPE COVER-SMOOTH WELDS**

N.T.S.



**B BIO-GAS PIPING DETAIL**

NOTES:

1. GAS VENTS AROUND PERIPHERY OF LAGOON @ MAX. 40' O.C.
2. STRAP NOT WELDED TO BIO-GAS HEADER PIPE.
3. WRAP 60 MIL PRIMARY LINER OVER CONCRETE & EXTRUSION WELD.

N.T.S.

PROJECT:

**POPLAR LANE**

**DAIRY  
DIGESTER**

CLIENT:  
BERNARD TE VELDE SR  
5387 KENT AVE  
HANFORD, CA 93280

COVER SYSTEM  
DIGESTER

REVISION LOG:


PLOT DATE: 01/08/18

JOB NO.: 17003


SCALE: AS SHOWN

SHEET NO.: D.1







**A SLUDGE REMOVAL PIPE ANCHOR DETAIL**  
NOTE: ANCHOR TO BE USED ON HORIZONTAL SURFACES ONLY, AT BOTTOM OF LAGOON N.T.S.



**B TYPICAL PIPE STRAP-DOWN DETAIL**  
NOTE: MAXIMUM 10' O.C. SPACING BETWEEN PIPE STRAP-DOWNS, U.N.O. N.T.S.



**C TYPICAL SLUDGE PIPE-PROFILE**  
N.T.S.



**D BAFFLE SECTION**  
N.T.S.



113 N. CHURCH ST,  
SUITE 521  
VISALIA, CA 93291  
(559) 563-0181



PROJECT:  
**POPLAR LANE**

**DAIRY  
DIGESTER**


CLIENT:  
BERNARD TE VELDE SR  
5387 KENT AVE  
HANFORD, CA 93280

SLURRY REMOVAL  
SYSTEM  
DIGESTER

REVISION LOG:


PLOT DATE: 01/08/18  
JOB NO.: 17003  
SCALE: AS SHOWN  
SHEET NO.: D.2






**MIXER - HATCH**

N.T.S.




**AIR INJECTION & MIXER HATCH**

N.T.S.




**MIXER - PLAN VIEW**

N.T.S.




**MIXER - ISOMETRIC W/FLOAT IN PLACE**

N.T.S.




**MIXER - ISOMETRIC**

N.T.S.




**MIXER - SIDE VIEW**

N.T.S.



**MIXER - FRONT VIEW**

N.T.S.



113 N. CHURCH ST,  
SUITE 521  
VISALIA, CA 93291  
(559) 563-0181



PROJECT:

POPLAR LANE

DAIRY  
DIGESTER

CLIENT:  
BERNARD TE VELDE SR  
5387 KENT AVE  
HANFORD, CA 93280

MIXER  
DETAILS

REVISION LOG:


PLOT DATE: 01/08/18

JOB NO.: 17003

SCALE: AS SHOWN


SHEET NO.: D.3






MOISTURE TRAP DETAIL

N.T.S.




BIO-GAS VALVE

N.T.S.



BALL VALVE JUNCTION

N.T.S.



BOLLARD DETAIL

N.T.S.



113 N. CHURCH ST,  
SUITE 521  
VISALIA, CA 93291  
(559) 563-0181



PROJECT:  
POPLAR LANE

DAIRY  
DIGESTER

CLIENT:  
BERNARD TE VELDE SR  
5387 KENT AVE  
HANFORD, CA 93280

DETAILS

REVISION LOG:

PLOT DATE: 01/08/18  
JOB NO.: 17003  
SCALE: AS SHOWN  
SHEET NO.: C.3










OPTIONAL TIER 1 DOUBLE LINER-LAYERING SYSTEM WITH DRAIN LINER VERIFY WITH OWNER


SMOOTH/STUDDED/ 60-NET-60 LINER LAYERS					
DESCRIPTION	LOCATION	MATERAIL	THICKNESS (MIN)	TOP FINISH	BOTTOM FINISH
PRIMARY LINER	TOP	HDPE	60 MIL	SMOOTH	SMOOTH CONDUCTIVE
DRAINAGE NET	MIDDLE	HDPE	200 MIL	N/A	N/A
SECONDARY LINER	BOTTOM	HDPE	60 MIL	SMOOTH	SMOOTH



**A** DOUBLE LAYER 60-NET-60 DOUBLE LAYER WITH DRAIN LINER N.T.S.




**B** HDPE LINER-SMOOTH WELDS N.T.S.




DRAIN LINER SMOOTH END WELD PATCH

**C** 3'X3' DRAIN PATCH WELD N.T.S.

3.8 - Engineered Digester Site Plan and Design - Poplar Lane Dairy



**D** AGRU DRAIN LINER END/END WELD N.T.S.  
NOTE: AGRU DRAIN LINER DOES NOT HAVE STUDS ALONG THE EDGE SO EDGE/EDGE SEAMS DO NOT REQUIRE DRINGING OR CAP.



NOTE: CQA OFFICER IS RESPONSIBLE TO ADD PATCHES AS NEEDED FOR FLOW

**E** AGRU DRAIN LINER CROSS SEAM NET PLAN VIEW N.T.S.  
NOTE: TYPICAL OF ALL DRAIN LINERS

1.2 - Lakeside Pipeline LLC - Application - 2018 Solicitation SB 1383 Dairy Pilot Projects



113 N. CHURCH ST,  
SUITE 521  
VISALIA, CA 93291  
(559) 563-0181



PROJECT:  
POPLAR LANE

DAIRY  
DIGESTER

CLIENT:  
BERNARD TE VELDE SR  
5387 KENT AVE  
HANFORD, CA 93280

LINER DETAILS	REVISION LOG:

PLOT DATE:	01/08/18
JOB NO.:	17003
SCALE:	AS SHOWN
SHEET NO.:	L2

THIS IS AN ORIGINAL UNPUBLISHED WORK AND MAY NOT BE DUPLICATED, PUBLISHED OR OTHERWISE USED WITHOUT THE WRITTEN CONSENT OF HARTMAN ENGINEERING INC. ©






N.T.S.




N.T.S.



SHEET NO.: L.3

021





VICINITY MAP  
NOT TO SCALE

SPECIAL NOTE

WHERE UNDERGROUND AND SURFACE STRUCTURES ARE SHOWN ON THE PLANS, THE LOCATIONS, DEPTH AND DIMENSIONS OF STRUCTURES ARE BELIEVED TO BE REASONABLY CORRECT, BUT ARE NOT GUARANTEED. SUCH STRUCTURES ARE SHOWN FOR THE INFORMATION OF THE CONTRACTOR, BUT INFORMATION SO GIVEN IS NOT TO BE CONSTRUED AS A REPRESENTATION THAT SUCH STRUCTURES WILL, IN ALL CASES, BE FOUND WHERE SHOWN, OR THAT THEY REPRESENT ALL OF THE STRUCTURES WHICH MAY BE ENCOUNTERED.

SITE SAFETY AND PROTECTION NOTES

THE DUTY OF THE ENGINEER, OWNER OR ITS AGENTS TO CONDUCT CONSTRUCTION REVIEW OF THE CONTRACTOR'S PERFORMANCE AND THE UNDERTAKING OF INSPECTIONS OR THE GIVING OF INSTRUCTIONS AS AUTHORIZED HEREIN IS NOT INTENDED TO INCLUDE REVIEW OF THE ADEQUACY OF THE CONTRACTOR'S SAFETY MEASURES IN, ON, OR NEAR THE CONSTRUCTION SITE AND SHALL NOT BE CONSTRUED AS SUPERVISION OF THE ACTUAL CONSTRUCTION NOR MAKE THE ENGINEER, OWNER OR ITS AGENTS RESPONSIBLE FOR PROVIDING A SAFE PLACE FOR THE PERFORMANCE OF WORK BY THE CONTRACTOR, SUBCONTRACTORS, OR SUPPLIERS, OR FOR ACCESS, VISITS, USE, WORK, TRAVEL OR OCCUPANCY BY ANY PERSON.

THE CONTRACTOR SHALL HAVE AT THE WORK SITE, COPIES OR SUITABLE EXTRACTS OF CONSTRUCTION SAFETY ORDERS, ISSUED BY CAL-OSHA. CONTRACTOR SHALL COMPLY WITH PROVISIONS OF THESE AND ALL OTHER APPLICABLE LAWS, ORDINANCES AND REGULATIONS. THE CONTRACTOR MUST COMPLY WITH PROVISIONS OF THE SAFETY AND HEALTH REGULATIONS FOR CONSTRUCTION, PROMULGATED BY THE SECRETARY OF LABOR UNDER SECTION 107 OF THE CONTRACT WORK HOURS AND SAFETY STANDARDS ACT, AS SET FORTH IN TITLE 29 C.F.R.

TO PROTECT THE LIVES AND HEALTH OF CONTRACTOR'S EMPLOYEES UNDER THE CONTRACT, THE CONTRACTOR SHALL COMPLY WITH ALL PERTINENT PROVISIONS OF THE "MANUAL OF ACCIDENT PREVENTION IN CONSTRUCTION" ISSUED BY THE ASSOCIATED GENERAL CONTRACTORS OF AMERICA, INC., AND SHALL MAINTAIN AN ACCURATE RECORD OF ALL CASES OF DEATH, OCCUPATIONAL DISEASE, AND INJURY REQUIRING MEDICAL ATTENTION OR CAUSING LOSS OF TIME FROM WORK, ARISING OUT OF AND IN THE COURSE OF EMPLOYMENT OR WORK UNDER THE CONTRACT.


THE CONTRACTOR ALONE SHALL BE RESPONSIBLE FOR THE SAFETY, EFFICIENCY, AND ADEQUACY OF CONTRACTOR'S FACILITIES, APPLIANCES, AND METHODS AND FOR ANY DAMAGE, WHICH MAY RESULT FROM THEIR FAILURE OR THEIR IMPROPER CONSTRUCTION, MAINTENANCE OR OPERATION.

THE CONTRACTOR AGREES THAT IT SHALL ASSUME SOLE AND COMPLETE RESPONSIBILITY FOR JOB SITE CONDITIONS DURING THE COURSE OF CONSTRUCTION OF THIS PROJECT, INCLUDING SAFETY OF ALL PERSONS AND PROPERTY; THAT THIS REQUIREMENT SHALL APPLY CONTINUOUSLY AND NOT BE LIMITED TO NORMAL WORKING HOURS; AND THAT THE CONTRACTOR SHALL DEFEND, INDEMNIFY AND HOLD THE OWNER, PROVOST & PRITCHARD CONSULTING GROUP, AND THEIR RESPECTIVE AGENTS HARMLESS FROM ANY AND ALL LIABILITY, REAL OR ALLEGED, IN CONNECTION WITH THE PERFORMANCE OF WORK ON THIS PROJECT, EXCEPTING FOR LIABILITY ARISING FROM THE SOLE NEGLIGENCE OF OWNER, ENGINEER, OR THEIR RESPECTIVE AGENTS.

THE OWNER AND ITS AGENTS' SITE RESPONSIBILITIES ARE LIMITED SOLELY TO THE ACTIVITIES OF THEIR EMPLOYEES ON SITE. THESE RESPONSIBILITIES SHALL NOT BE INFERRED BY ANY PARTY TO MEAN THAT THE OWNER OR ITS AGENTS HAVE RESPONSIBILITY FOR SITE SAFETY. SAFETY IN, ON, OR ABOUT THE SITE IS THE SOLE AND EXCLUSIVE RESPONSIBILITY OF THE CONTRACTOR ALONE. THE CONTRACTOR'S METHODS OF WORK PERFORMANCE, SUPERINTENDENCE AND THE CONTRACTOR'S EMPLOYEES, AND SEQUENCING OF CONSTRUCTION ARE ALSO THE SOLE AND EXCLUSIVE RESPONSIBILITIES OF THE CONTRACTOR ALONE.

RIVER RANCH DAIRY  
KINGS COUNTY

LAGOON DIGESTER



SITE MAP  
NOT TO SCALE

PROJECT BENCHMARK

XXXX

ELEVATION = XXX.XX' NAVD88 DATUM

ONSITE BENCHMARK

XXXX

ELEVATION = XXX.XX' NAVD88 DATUM

GPS GRADING CONTROL POINTS

FOUR POINTS WILL BE SET OUTSIDE THE FOUR CORNERS OF THE PROPOSED LAGOON FOR GPS MACHINE CONTROL GRADING.

GENERAL NOTES

1. USED MATERIAL, REJECTS, MISFITS, OR SECONDS, ETC. ARE NOT ACCEPTABLE FOR CONSTRUCTION OF THE PROPOSED FACILITIES.
2. ALL CONSTRUCTION SHALL BE IN CONFORMANCE WITH THESE PLANS, AND PROJECT SPECIFICATIONS.
3. CONTRACTOR SHALL FIELD VERIFY THE HORIZONTAL AND VERTICAL LOCATIONS OF ALL EXISTING FACILITIES PRIOR TO COMMENCING WORK. CALL UNDERGROUND SERVICE ALERT (USA) AT 8-1-1. CONTRACTOR SHALL MAKE ENGINEER AWARE OF ANY DISCREPANCIES.
4. THRUST RESTRAINTS TO BE PROVIDED AT ALL PIPELINE BENDS, WHETHER OR NOT SHOWN ON THE PLANS.
5. ALL CONSTRUCTION SHALL BE PERFORMED IN ACCORDANCE WITH APPLICABLE HEALTH AND SAFETY LAWS OF THE STATE OF CALIFORNIA AND CAL/OSHA STANDARDS.
6. TRENCH BACKFILL AND RESERVOIR EMBANKMENTS SHALL BE COMPACTED IN ACCORDANCE WITH THE SPECIFICATIONS AND THE GEOTECHNICAL REPORT CONTAINED IN THE SPECIFICATIONS.
7. CONTRACTOR WILL BE RESPONSIBLE FOR THE REPAIR OF ALL PIPELINE CRACKS, WHICH DEVELOP DURING CONSTRUCTION OF IMPROVEMENTS AFFECTING EXISTING FACILITIES.
8. ALL EXCESS MATERIAL AND/OR DEBRIS SHALL BE REMOVED UPON COMPLETION OF INSTALLATION.
9. CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING ADEQUATE DUST CONTROL AT ALL TIMES.

SHEET INDEX	
SHEET NO.	DESCRIPTION
LL1	COVER
LL2	PLAN
LL3	CROSS SECTIONS
LL4	DETAILS 1
LL5	DETAILS 2
LL6	DETAILS 3
LL7	CUT FILL MAP

COPYRIGHT 2017 BY PROVOST & PRITCHARD CONSULTING GROUP, INC. ALL RIGHTS RESERVED. THE ENGINEER, OWNER OR ITS AGENTS TO CONDUCT CONSTRUCTION REVIEW OF THE CONTRACTOR'S PERFORMANCE AND THE UNDERTAKING OF INSPECTIONS OR THE GIVING OF INSTRUCTIONS AS AUTHORIZED HEREIN IS NOT INTENDED TO INCLUDE REVIEW OF THE ADEQUACY OF THE CONTRACTOR'S SAFETY MEASURES IN, ON, OR NEAR THE CONSTRUCTION SITE AND SHALL NOT BE CONSTRUED AS SUPERVISION OF THE ACTUAL CONSTRUCTION NOR MAKE THE ENGINEER, OWNER OR ITS AGENTS RESPONSIBLE FOR PROVIDING A SAFE PLACE FOR THE PERFORMANCE OF WORK BY THE CONTRACTOR, SUBCONTRACTORS, OR SUPPLIERS, OR FOR ACCESS, VISITS, USE, WORK, TRAVEL OR OCCUPANCY BY ANY PERSON.

PRELIMINARY  
NOT FOR CONSTRUCTION  
5/22/17

FOR  
REVIEW  
ONLY

LAGOON DIGESTER  
RIVER RANCH DAIRY  
KINGS COUNTY  
LAGOON DESIGN  
COVER

EST-4588  
PROVOST & PRITCHARD  
CONSULTING GROUP  
An Employee Owned Company  
286 WEST CROMWELL AVENUE  
FRESNO, CALIFORNIA 93711-6162  
559/449-2700 FAX 559/449-2715  
www.ppgcg.com

DESIGN ENGINEER:  
GABRIEL DO-REYNOSO  
LICENSE NO:  
81090

DRAFTED BY:  
P&P  
CHECKED BY:  
SCB





DATE: 5/3/17  
JOB NO: 301717001

PROJECT NO:  
PHASE:

0 1" = 100'  
ORIGINAL SCALE SHOWN IS  
ONE INCH. ADJUST SCALE FOR  
REDUCED OR ENLARGED PLANS.

SHEET  
LL1





**DIGESTER LAGOON DIMENSIONS**

THE DIGESTER LAGOON IS 830 FEET LONG BY 350 FEET WIDE BY 26 FEET DEEP. THERE IS 2 FEET OF FREEBOARD SO THE NOMINAL DEPTH IS 24 FEET (SEE SECTION AT STA 6+00 ON SHEET LL3). INTERIOR SIDE SLOPES ARE 2.5:1. TOP OF BANK WIDTH IS 20 FEET (NORTH AND EAST BANK) AND 25 FEET (WEST AND SOUTH BANK). EXTERIOR SIDE SLOPES ARE 3:1.

- CONSTRUCTION LEGEND**
- GM OVERLAP GEONET EDGES A MINIMUM OF 3 INCHES. INSTALL PLASTIC CABLE TIES EVERY 5 FEET.
  - GT OVERLAP GEONET ENDS OR END TO EDGE WITH MATERIALS SHINGLED DOWN A MINIMUM 5 FEET FROM THE TOE OF POND IN THE DIRECTION OF THE SLOPE A MINIMUM OF 12 INCHES. INSTALL PLASTIC CABLE TIES EVERY 12 INCHES.
  - LP LEAKAGE PIPE TRENCH
  - P1 INLET PIPE
  - P2 OUTLET PIPE
  - PR REMOVE EXISTING PIPE
  - S1 LCRS/LYSIMETER SUMPS
  - SS 1/8" STAINLESS STEEL CABLE LOCATED AT TOE OF SLOPE AND EXITS AT SURFACE.
  - T1 ANCHOR TRENCH (TYPICAL AROUND PERIMETER OF POND)
  - V1 VENT ORIFICE
  - V2 2' WIDE DOUBLE FACED 160ML MINIMUM GEOCOMPOSITE VENT STRIPS. (MATERIAL TO BE APPROVED BY ENGINEER)

- NOTES**
- POND SUBGRADE AND LINER SHALL BE INSTALLED IN ACCORDANCE WITH THE POND DESIGN WORK PLAN THAT HAS BEEN APPROVED BY THE REGIONAL WATER QUALITY CONTROL BOARD.
  - HIGH WATER LINE (HWL) IS THE FREEBOARD LEVEL.
  - POINTS WILL BE GIVEN FOR GPS LOCATION OF GRADING EQUIPMENT.

PRELIMINARY  
NOT FOR CONSTRUCTION  
5/22/17

FOR  
REVIEW  
ONLY

LAGOON DIGESTER  
RIVER RANCH DAIRY  
KINGS COUNTY  
LAGOON DESIGN  
PLAN

EST-4568  
**PROVOST & PRITCHARD**  
CONSULTING GROUP  
An Employee Owned Company  
288 WEST CROMWELL AVENUE  
FRESNO, CALIFORNIA 93711-6162  
559/449-2700 FAX 559/449-2715  
www.ppeng.com










DESIGN ENGINEER:  
GABRIEL DO-REYNOSO  
LICENSE NO:  
81090  
DRAFTED BY:  
P&P  
CHECKED BY:  
SCB  
DATE: 5/3/17  
JOB NO: 301717001  
PROJECT NO:  
PHASE:  
ORIGINAL SCALE SHOWN IS  
ONE INCH. ADJUST. SCALE FOR  
REDUCED OR ENLARGED PLANS.  
SHEET  
**LL2**

7021









pg 214

6/22/2017 1:25 PM G:\6 Jong\_Jack-3017\3017-River Ranch Dairy-6165 Jackson Ave Hanford CA\301717001-Digester Project\DWG\SHEET\LAGOON\LL2 PLAN.dwg -Gabriel Do Reynoso









**PROVOST & PRITCHARD**  
EST. 1988  
An Employee Owned Company  
286 WEST CROMWELL AVENUE  
FRESNO, CALIFORNIA 93711-6162  
559/449-2700 FAX 559/449-2715  
www.ppeng.com

DESIGN ENGINEER: GABRIEL DO-REYNOSO  
LICENSE NO: 81090  
DRAFTED BY: P&P  
CHECKED BY: SCB  
DATE: 5/3/17  
JOB NO: 301717001  
PROJECT NO:  
PHASE:  
ORIGINAL SCALE SHOWN IS ONE INCH. ADJUST SCALE FOR REDUCED OR ENLARGED PLANS.  
SHEET **LL4** OF 7021


LAGOON DIGESTER  
RIVER RANCH DAIRY  
KINGS COUNTY  
LAGOON DESIGN  
DETAILS 1

**PRELIMINARY  
NOT FOR CONSTRUCTION  
5/22/17**

DATE: 5/22/17  
BY: [Signature]  
REVISION: [Signature]  
No. [Signature]

Copyright 2017 by Provost & Pritchard Engineering Group, Inc. All rights reserved. This drawing is the property of Provost & Pritchard Engineering Group, Inc. and is not to be reproduced, stored in a retrieval system, or transmitted in any form or by any means, electronic, mechanical, photocopying, recording, or by any information storage and retrieval system, without the prior written permission and consent of Provost & Pritchard Engineering Group, Inc. The third party shall hold the firm of Provost & Pritchard Engineering Group, Inc. harmless from and defend and bear the cost of Provost & Pritchard Engineering Group, Inc.'s legal fees associated with enforcing these rights.






NOT TO SCALE

1  
LL5

### TYPICAL LINER LAYERS AT SUMP

#### NOTES


1. 12" SCH 40 CAN BE SUBSTITUTED W/ CLASS 125



NOT TO SCALE

2  
LL5


### LINER LAYERS AT LCRS & LYSIMETER PIPES




FEET

3  
LL5


### LEAKAGE PIPE-DOUBLE LINER



#### SECTION B



#### SECTION A



#### PLAN VIEW

FEET

4  
LL5

### LCRS & LYSIMETER DRAINAGE SUMPS

#### NOTES

1. FILL BOTH LYSIMETER AND LCRS SUMPS WITH ROUNDED GRAVEL, 1/2" TO 3/4" WASHED GRAVEL CLASSIFIED AS ROUNDED AS DEFINED IN ASTM D2488.
2. DURING CONSTRUCTION GEOTEXTILE FABRIC SHALL EXTEND 2 FT BEYOND EDGE OF LINER.
3. LCRS/LYSIMETER PIPE LAYOUT IS SCHEMATIC DUE TO ANGLE OF PIPE INTRUSION INTO THE SUMP. DIMENSIONS MAY VARY.

PRELIMINARY  
NOT FOR CONSTRUCTION  
5/22/17

FOR  
REVIEW  
ONLY

LAGOON DIGESTER  
RIVER RANCH DAIRY  
KINGS COUNTY  
LAGOON DESIGN  
DETAILS 2

EST-1508  
**PROVOST & PRITCHARD**  
CONSULTING GROUP  
An Employee Owned Company  
286 WEST CROMWELL AVENUE  
FRESNO, CALIFORNIA 93711-6162  
559/449-2700 FAX 559/449-2715  
www.ppgcg.com

DESIGN ENGINEER:  
GABRIEL DO-REYNOSO  
LICENSE NO:  
81090

DRAFTED BY:  
P&P

CHECKED BY:  
SCB

DATE: 5/3/17

JOB NO: 301717001



PROJECT NO:

PHASE:

ORIGINAL SCALE SHOWN IS  
ONE INCH. ADJUST SCALE FOR  
REDUCED OR ENLARGED PLANS.

SHEET  
LL5





PRELIMINARY  
NOT FOR CONSTRUCTION  
5/22/17

FOR REVIEW ONLY

LAGOON DIGESTER  
RIVER RANCH DAIRY  
KINGS COUNTY  
LAGOON DESIGN

DETAILS 3

EST-1568  
PROVOST & PRITCHARD  
CONSULTING GROUP  
An Employee Owned Company  
286 WEST CROMWELL AVENUE  
FRESNO, CALIFORNIA 93711-6162  
559/449-2700 FAX 559/449-2715  
www.ppeng.com

DESIGN ENGINEER:  
GABRIEL DO-REYNOSO  
LICENSE NO:  
81090

DRAFTED BY:  
P&P

CHECKED BY:  
SCB

DATE: 5/3/17

JOB NO: 301717001

PROJECT NO:


PHASE:

0 1"  
ONE INCH SCALE SHOWN IS  
ONE INCH ADJUST SCALE FOR  
REDUCED OR ENLARGED PLANS.


SHEET  
LL6

6/22/2017 1:26 PM G:\e\_jong\_jack-3017\3017-River Ranch Dairy\Jong-Jack-3017-Digester Project\DWG\SHEET\LAGOON\LL6 DETAILS 3.dwg -Gabriel Do Reynoso






CUT FILL MAP



EXISTING TOPOGRAPHY



COPYRIGHT 2017 BY PROVOST & PRITCHARD ENGINEERING GROUP, INC. ALL RIGHTS RESERVED. No part of this publication may be reproduced, stored in a retrieval system, or transmitted, in any form or by any means, electronic, mechanical, photocopying, recording, or by any information storage and retrieval system, without the prior written permission of Provost & Pritchard Engineering Group, Inc. The third party shall hold the firm of Provost & Pritchard Engineering Group, Inc. harmless from and defend and bear the cost of Provost & Pritchard Engineering Group, Inc.'s legal fees associated with defending and enforcing these rights.

ELEVATION TABLE					
NUMBER	MINIMUM ELEVATION	MAXIMUM ELEVATION	2D AREA	3D AREA	COLOR
1	-13.26	-3.40	164108.14	165168.65	
2	-3.40	-0.75	109848.56	110467.69	
3	-0.75	0.00	11180.51	14697.84	
4	0.00	0.05	1268.20	1532.34	
5	0.05	0.40	4972.40	6832.90	
6	0.40	0.90	8012.39	10666.36	
7	0.90	1.20	12931.65	14461.39	
8	1.20	1.30	10239.21	10519.21	
9	1.30	1.80	19028.65	19405.76	
10	1.80	4.88	34608.32	35295.26	

NOTES

- POINTS WILL BE GIVEN FOR GPS LOCATION OF GRADING EQUIPMENT.
- EXISTING LAGOON IS ASSUMED TO BE 20 FEET DEEP.

GRADING QUANTITIES

CUT: ±44,353 CY  
FILL: ±5,768 CY  
NET CUT: ±38585 CY  
CUT FACTOR: =1  
FILL FACTOR: =1

QUANTITIES ARE APPROXIMATE AND ARE BASED ON SURVEY DATA POINTS.

PRELIMINARY  
NOT FOR CONSTRUCTION  
5/22/17

FOR  
REVIEW  
ONLY

LAGOON DIGESTER

RIVER RANCH DAIRY  
KINGS COUNTY

LAGOON DESIGN

CUT FILL MAP

EST-1968  
**PROVOST & PRITCHARD**  
CONSULTING GROUP  
An Employee Owned Company  
288 WEST CROMWELL AVENUE  
FRESNO, CALIFORNIA 93711-6162  
559/449-2700 FAX 559/449-2715  
www.ppg.com

DESIGN ENGINEER:  
GABRIEL DO-REYNOSO  
LICENSE NO:  
81090

DRAFTED BY:  
P&P  
CHECKED BY:  
SCB

DATE: 5/3/17

JOB NO: 301717001

PROJECT NO:

PHASE:

0 1"

ORIGINAL SCALE SHOWN IS  
ONE INCH. ADJUST SCALE FOR  
REDUCED OR ENLARGED PLANS.

SHEET


LL7



**Lakeside Pipeline Dairy Digester Cluster**

**Decade Centralized Dairy - Digester 1**

*Mass Balance Diagram (Richard Westra Dairy Connected to Decade Centralized Digester)*






**Lakeside Pipeline Dairy Digester Cluster**

**Decade Centralized Dairy - Digester 1**

*Mass Balance Diagram (Richard Westra Dairy—post-project)*






## Lakeside Pipeline Dairy Digester Cluster

### Decade Centralized Dairy - Digester 1

Mass Balance Diagram (Decade Dairy—post-project)






**Lakeside Pipeline Dairy Digester Cluster**

**Clear Lake Dairy - Digester 2**

*Mass Balance Diagram (post-project)*






**Lakeside Pipeline Dairy Digester Cluster**

**Dixie Creek Dairy - Digester 3**

*Mass Balance Diagram (post-project)*






## Lakeside Pipeline Dairy Digester Cluster

### Double L Cattle - Digester #4

Mass Balance Diagram (post-project)






## Lakeside Pipeline Dairy Digester Cluster

### High Roller Dairy - Digester #5

Mass Balance Diagram (post-project)






## Lakeside Pipeline Dairy Digester Cluster

### Lakeside Dairy - Digester 6

Annotated Manure Treatment Diagram (pre-project)






# Lakeside Pipeline Dairy Digester Cluster

## Lone Oak Farms #1 - Digester #7

Mass Balance Diagram (post-project)





## Lakeside Pipeline Dairy Digest Cluster

### Poplar Lane Dairy - Digester 8

Mass Balance Diagram (post-project)

